

JANUARY 20, 1971



SATURN

HISTORICAL OFFICE
MANAGEMENT SERVICES OFFICE

SATURN ILLUSTRATED CHRONOLOGY

by
DAVID S. AKENS
A&TS-MS-H

SATURN'S FIRST ELEVEN YEARS
APRIL 1957 through APRIL 1968

(MHR-5) SATURN ILLUSTRATED CHRONOLOGY:
SATURN'S FIRST ELEVEN YEARS, APRIL 1957
- APRIL 1968 (NASA) 306 p HC \$17.50

302

CSCL 22B


G3/31

Unclas
15866

N74-12495

NASA

NATIONAL AERONAUTICS AND SPACE ADMINISTRATION



**HISTORICAL OFFICE
MANAGEMENT SERVICES OFFICE**

**SATURN
ILLUSTRATED
CHRONOLOGY**

by
DAVID S. AKENS

**SATURN'S FIRST ELEVEN YEARS
APRIL 1957 through APRIL 1968**

First Edition: 1963

Second Edition: 1965

Third Edition: 1967

Fourth Edition: 1969

Fifth Edition: 1971

TABLE OF CONTENTS


	Page
1957	1
1958	2
1959	3
1960	8
1961	13
1962	35
1963	49
1964	72
1965	99
1966	127
1967	158
1968	203
ACKNOWLEDGMENTS.	227
APPENDICES.	229
GLOSSARY	235
REFERENCES	245
INDEX	259

SATURN ILLUSTRATED CHRONOLOGY


In April 1957 the scientific organization directed by Dr. Wernher von Braun began studies which led to Saturn, America's first rocket developed for space investigation. The team at Redstone Arsenal, Alabama, hoped to design launch vehicles that could carry 20,000- to 40,000-pound payloads for orbital missions or 6000- to 12,000-pound payloads for escape missions. High-thrust booster stages were essential.

In December 1957 the von Braun group, then working with the Army Ballistic Missile Agency (ABMA), proposed a program to the Department of Defense (DOD).¹ At that time the United States was considering an integrated missile and space vehicle development program. Creation of a booster with 1,500,000 pounds of thrust was the aim of the proposed program.

To secure this much power ABMA first considered clustering four 380,000-pound thrust Rocketdyne E-1 engines.



SATURN ILLUSTRATED CHRONOLOGY




1

1. Proposed configuration of a clustered booster.

This initial concept was discarded because of the time required to complete development of this type engine. However, ABMA continued studies to determine if engines already developed could be used.

On August 15, 1958, the Advanced Research Projects Agency (ARPA) formally initiated what was


2



2. Thor-Jupiter engine
3. Booster tooling

to become the Saturn project. The agency, a separately organized research and development arm of the Department of Defense, authorized ABMA to conduct a research and development program at Redstone Arsenal for a 1,500,000-pound thrust vehicle booster. A number of available rocket engines would be clustered. This design would be tested by a full-scale static firing by the end of 1959.²

The liquid oxygen (LOX) and fuel tanks developed for the Redstone and Jupiter missiles could be



3

modified for use in the proposed booster. An existing engine, the S-3D, used on both the Thor and Jupiter missiles, could be modified to produce an increased thrust of 188,000 pounds. Numerous tools and fixtures developed for the Redstone and Jupiter program could also be used with comparatively little modification. Thus it was possible to begin booster development with hardware of proven reliability. Time for design and development of some important booster components and tooling could be significantly shortened and cost reduced.


As an immediate step a contract was awarded Rocketdyne Division of North American Aviation on September 11, 1958, to uprate S-3D, the Thor-Jupiter engine. After redesign, simplification, and modification, the engine would be the H-1.

In October 1958 ARPA expanded its program objectives. A multistage carrier vehicle capable of performing advanced space missions would be built. The vehicle was tentatively identified as Juno V. ARPA requested Redstone personnel to study a complete vehicle system so that upper-stage selection and development could begin, and initiated a study of Atlantic Missile Range (AMR) launch facilities which could accommodate the launch vehicle.³ Later, on December 11, 1958, ARPA authorized the Army Ordnance Missile Command (AOMC) to begin design, modification, and construction of a captive static test tower and



4. Early H-1 Engine
5. Preliminary concept of Launch Complex 34, Cape Canaveral

5



SATURN ILLUSTRATED CHRONOLOGY

facilities for use in the booster development program. AOMC was also to determine the design requirements for necessary launch facilities.⁴

While the booster-vehicle program was being formulated and expanded, development work on the H-1 engine continued. The first full-power H-1 engine firing occurred in December 1958 at the Rocketdyne facility in Canoga Park, California.


Concurrently with development of the H-1 engine, studies were conducted pertaining to the feasibility of a larger single-chamber rocket engine. On January 9, 1959, Rocketdyne agreed by contract to design, develop, and test such an engine, designated as the F-1. This engine, burning LOX and RP-1, a kerosene-type fuel, would generate a very high thrust, approximately 1,500,000 pounds.

Construction of the ABMA static test stand for large boosters began January 10, 1959. Meanwhile, Army representatives of the ARPA board visited AMR to discuss selection of a site for large vehicle launch facilities at Cape Canaveral, Florida. By February 1959, a contract had been awarded for construction of the blockhouse at the site (Launch Complex 34). A design contract was also awarded for a movable structure which would be used to assemble and service the vehicle on the launch pedestal.

On February 3 an ARPA memorandum officially renamed the large launch vehicle project Saturn. ARPA representatives presented the proposed National Vehicle Program to the President and the National Aeronautics and Space Council on March 2, 1959. Included were the proposed Saturn B and C vehicle systems.⁵

On March 13 ABMA submitted to ARPA the results of the Saturn System Study. This study indicated that either an Atlas or a Titan could be used as the second stage of the proposed vehicle.⁶ During May ARPA decided that modified Titan hardware

6




6. Saturn B

7. Saturn C

7




8



8. Vehicles using Titan and Atlas stages

9. Atlas Centaur vehicle (Centaur second stage) showing a. Atlas stage, b. second stage, c. payload, d. electronic and guidance package, e. liquid hydrogen tank, f. LOX tank, and h. RP-1 tank

9



could be used for the second stage and that the third stage could use a slightly modified Centaur vehicle.

By April 28 the first production H-1 engine (H-1001) had been delivered on schedule to ABMA. ABMA's first firing test of this engine, later used in the first test booster, was performed successfully on May 26, 1959.⁷

On July 5, 1959, construction of the Saturn block-house for Launch Complex 34 began at Cape Canaveral. On July 27 when the last Jupiter air-frame was completed, Redstone Arsenal shops began retooling to support the Saturn project.

Late in July the Director of Defense Research and Engineering notified the Air Force and ARPA to consider common development of the Saturn second stage and the booster for the proposed Dyna Soar; requirements for these stages appeared to be similar. Until review of this, neither agency was to make a firm commitment for the redesign of existing boosters or development of new ones.

ARPA then ordered cessation of the AOMC in-house and contractor work relating to the Titan second stage. An exception was made of some preliminary work not directly connected with the stage diameter.⁸


Work continued on the Saturn booster stage. While studies of the proposed Saturn-Dyna Soar combination were in progress, ARPA, on August 1, authorized ABMA to proceed toward captive firing the Saturn booster early in 1960.

In September representatives of AOMC, NASA, and the Air Force presented Saturn, Nova, and Titan C systems to the Booster Evaluation Committee of the Office of the Secretary of Defense. On the basis of these presentations ARPA chose Saturn. ARPA then requested that Redstone scientists determine the Saturn configurations which could best carry NASA payloads.

SATURN ILLUSTRATED CHRONOLOGY

During October 1959 consideration of Saturn vehicle configurations continued. On October 29 and 30 ABMA presented a second Saturn System Study to ARPA and National Aeronautics and Space Administration (NASA), proposing various upper-stage configurations which offered increased payload capability and growth potential. In December 1959, after evaluation of previous presentations, NASA and ARPA requested that AOMC prepare an engineering study for a three-stage Saturn configuration.

Because of its large size and weight, the Saturn booster could not be transported by air or land. Water transportation appeared most feasible, and




11

ARPA, on October 23, 1959, authorized AOMC to proceed with engineering work for dock facilities. These would be located on the Tennessee River at the southern boundary of Redstone Arsenal. In December AOMC was further authorized to construct the facilities and to build a barge to transport the booster to Cape Canaveral.

On November 18 NASA assumed technical direction of the Saturn project pending its formal transfer from ARPA. Administrative direction was retained by ARPA until March 16, 1960, when transfer of both administrative and technical direction would become effective.

10



10. H-1 engine in alignment fixture


11. Model of blockhouse at Launch Complex 34

On December 15 the Saturn Vehicle Evaluation Committee (the Silverstein Committee) reached a decision on Saturn upper-stage configurations. This committee, composed of representatives from NASA, ARPA, DOD, and the Air Force, recommended a long-range development program for a Saturn vehicle with upper-stage engines burning liquid hydrogen and liquid oxygen. The initial vehicle, identified as C-1, was to be a stepping stone to a larger vehicle, the C-2. A building-block concept was proposed that would yield a variety of Saturn configurations, each using previously proven developments as far as possible. These recommendations were accepted by the NASA Administrator. On December 31, 1959, a ten-vehicle program was established.⁹


The C-1 vehicle configuration included the S-I, the S-IV, and the S-V stages. The S-I stage would have eight H-1 engines. Fueled by LOX/RP-1, the engines clustered were expected to produce a

12. C-1 and earlier vehicles:
a. Redstone, b. Jupiter-C,
c. Mercury Redstone, d.
Jupiter, e. Juno II, and f.
Saturn C-1
13. Proposed C-2

12




13



SATURN ILLUSTRATED CHRONOLOGY

14



- 14. Booster stage (S-I)
- 15. Second stage (S-IV)


total of 1,500,000 pounds of thrust. The S-IV stage was conceived of as a four-engine liquid oxygen-liquid hydrogen fueled unit capable of producing a total of 80,000 pounds of thrust. The S-V stage would use two of the same engines as the S-IV stage and this stage would provide an additional 40,000 pounds of thrust.

The Saturn project was approved on January 18, 1960, as a program of the highest national priority (DX rating).


To develop the second stage of Saturn C-1, NASA sought a contractor. A bidder's conference concerning this S-IV stage was held at Huntsville, January 26 and 27, 1960. By February 29 twelve companies had submitted contract proposals.

Redstone Arsenal scientists started to work on the first stage. By 1960 the formal test program to prove out the clustered booster concept was

15




16



16. Third stage (S-V)
17. Moving Saturn test booster from assembly to test
18. Booster in test stand





18



well under way. A mockup of the Saturn booster was installed in the ABMA test stand on January 4, 1960, to check mating of the booster and stand and to test servicing methods. This mockup was removed from the test stand and the complete test booster, SA-T, was installed in its place during February 1960.

During March the executive order transferring the Saturn program to NASA became effective.¹⁰ Later in the month two of Saturn's eight first-stage engines passed an initial static firing test of

17



approximately eight seconds' duration. This test was identified as number SAT-01, the first live firing of the Saturn test booster (SA-T). It occurred on March 28.¹¹ In a second test (SAT-02), on April 6, four engines were successfully static fired for seven seconds. All eight engines of the test booster were successfully fired on April 29 in an eight-second test.¹²

SATURN ILLUSTRATED CHRONOLOGY

On May 17 a second eight-engine static firing of 24 seconds' duration generated a thrust of 1.3 million pounds. The third successful eight-engine firing lasted 35 seconds.¹³

Meanwhile, NASA reviewed the S-IV proposals received in February. On April 26 NASA awarded Douglas Aircraft Company a contract to develop and build the second stage.

During May NASA announced that Rocketdyne had been selected to develop the high-thrust J-2 engine. This engine, of the type defined by the Silverstein Committee in December 1959, would burn liquid hydrogen-liquid oxygen. It would be used in an advanced Saturn vehicle.

The first ten Saturn flight vehicles would be numbered from SA-1 to SA-10. SA-10 would be the prototype of the operational Saturn.

On May 26, 1960, assembly of the booster stage for the first Saturn flight vehicle began in Huntsville.

On July 1, 1960, the Saturn program was formally transferred to the George C. Marshall Space Flight Center (MSFC).¹⁴ A second series of static tests had just been successfully completed on the first stage of Saturn C-1.

On July 26 NASA signed a supplemental agreement with Douglas Aircraft Company covering the second stage. Douglas would design, develop, and fabricate the four-engine S-IV stage.

Contracts were also let on August 10, 1960, with Pratt & Whitney to develop and produce LR-119 engines; the Government would furnish these engines to the contractors responsible for building the S-IV and S-V stages of the C-1 vehicle. The LR-119, an uprated LR-115 engine, was expected to generate 17,500 pounds of thrust.


On August 14, 1960, construction began on the

19. Booster static firing
20. Model of J-2 engine

19




20



21




22




- 21. Assembly of main LOX tank for SA-1 booster
- 22. Assembly of tanks on SA-1 booster
- 23. Structural fabrication of SA-1 booster

23



SATURN ILLUSTRATED CHRONOLOGY


24



movable service structure for Launch Complex 34 at Cape Canaveral.

On August 15 the Air Force requested NASA assistance in planning the application of Saturn to Dyna Soar. After conferring with Air Force, MSFC agreed on October 6 to provide a preliminary study.


26



12

- 24. Installation of engines on SA-1 booster
- 25. Initial configuration of the S-IV stage
- 26. Construction of service tower and pedestal

25




- 27. Unveiling bust of General George C. Marshall
- 28. Dr. von Braun and President Eisenhower
- 29. Mr. Glennan, President Eisenhower, and Dr. von Braun
- 30. Proposed Saturn C-1 Apollo Configuration

27




28



29



30



On September 8 the facilities of the National Aeronautics and Space Administration at Huntsville, Alabama, were dedicated and designated as the George C. Marshall Space Flight Center. President Eisenhower, Mrs. George C. Marshall, NASA Administrator T. Keith Glennan, and many other national, state, and local dignitaries participated in the ceremony.

On October 21 NASA awarded to Convair a study contract for a second upper stage, the S-V. On October 25 NASA selected Convair, General Electric, and Martin to conduct individual feasibility studies of an advanced manned spacecraft as part of Project Apollo.¹⁵

MSFC started a new series of static firing tests of the test booster (modified to the SA-1 flight configuration and designated SA-T1) on December 2, 1960. An eight-engine test lasting two seconds was first. The next week a test of two engines was conducted in a six-second firing. The series of booster tests was successfully concluded on December 20, 1960, by a 60-second firing of all eight engines. Fabrication of the tanks for the booster stage of the second Saturn flight vehicle (SA-2) was completed during December. Assembly of the booster began immediately.

In January Convair Astronautics submitted a proposal for an S-V upper stage for the Saturn vehicle; however, later in the month Dr. von Braun proposed that the C-1 vehicle be changed from a three-stage to a two-stage configuration in support of the Apollo program. NASA decided to delete requirements for the S-V stage on C-1 vehicles.

On January 16 the booster stage for the SA-1 flight vehicle was moved from assembly to checkout. During January also, wind tunnel testing of a model Saturn booster began at the Arnold Engineering Development Center, Tullahoma, Tennessee; the tests were designed to study base heating phenomena of the clustered stage.

SATURN ILLUSTRATED CHRONOLOGY

Two additional studies began in January 1961. NASA awarded North American and Ryan Aeronautical Company contracts to investigate feasibility of recovering the S-I booster stage after the vehicle flight by using a Rogallo paraglider. A design contract was awarded for equipment which would be used at MSFC to check out the S-I stage automatically.

On January 25 a meeting was held at MSFC to study S-II stage requirements for the Saturn C-2 vehicle. S-II stage trajectory, performance, and structural analysis calculations were completed and made a part of the preliminary Saturn-Dyna Soar proposal.¹⁶

During January a dummy of the S-IV stage was completed at MSFC and moved to checkout. On January 31 MSFC static fired all eight engines of the SA-T1 test booster for 113 seconds.¹⁷

A dummy S-V stage, built for use on SA-1, was received from Convair on February 8 and mated to the dummy S-IV stage. The first horizontal assembly of the complete C-1 vehicle was accomplished during February. MSFC completed SA-T1 static tests on February 14. By February 27 Convair had provided MSFC with a second dummy S-V stage.¹⁸ This stage would first be used during dynamic tests of a complete dummy vehicle; later the dummy S-V would be used on a flight vehicle.


Liquid hydrogen engine development problems led to studies early in March to determine the possibility of using the first-generation LR-115 type Centaur engine on the Saturn S-IV stage, rather than second-generation Centaur engine, the LR-119.

Meanwhile, the booster was removed from the test stand on March 2 and loaded aboard the Palaemon for river trials. Also on March 2, 1961, as a part of the booster recovery studies, tests began at Cape Canaveral to determine the feasibility of reusing H-1 engines after exposure to salt water.

31



32



31. SA-1 Checkout

32. Saturn booster recovery

33. C-2 Second Stage concept

33



34




34. Movement of dummy S-IV stage to checkout

35



35. First horizontal mating of the Saturn vehicle
36. Removal of the booster from the static test stand

36



SATURN ILLUSTRATED CHRONOLOGY

Construction work at Launch Complex 34 continued to progress satisfactorily, with the service structure, blockhouse, and gas facilities nearing completion.


On March 7 the SA-1 booster was moved to the MSFC static test stand for preflight checkout. On March 14 the Palaemon, carrying the SA-T1, left the MSFC dock on its first training trip. Following its return the test booster went to MSFC shops for modification to the SA-T2 configuration. Looking beyond the booster, MSFC began construction in March of a facility to be used in familiarizing personnel with the handling of liquid hydrogen. MSFC presented plans on March 23 to accelerate the C-2 program and recommended that a prime contractor be selected to develop the S-II stage. MSFC also recommended use of six LR-115 engines in the S-IV stage instead of four LR-119 engines. Pratt & Whitney would still be the supplying contractor. MSFC then proposed certain design changes in the S-I stage including an increase in propellant capacity, the addition of fins, and increased structural support for later versions of the booster.

On March 29, 1961, MSFC received NASA Headquarters approval for the six-engine configuration


37



38



39



40




37. Salt water test of H-1 engine

38. Facilities construction at Launch Complex 34

39. The barge Palaemon

40. Redesigned tail of the Saturn booster

41



- 41. Six-engine configuration of the S-IV stage
- 42. Artist's concept of Apollo capsule
- 43. Air transport of S-IV stage

of the S-IV.¹⁹ On March 31 NASA approved acceleration of the C-2 program and development of the C-2 vehicle for a three-stage escape mission. MSFC was authorized to begin a two-phase procurement of an S-II stage.²⁰

During March further decisions were made concerning engines for the S-IV stage. MSFC decided to redirect effort from development of the LR-119 to the RL10-A-1, an engine that could be used in common by both the Centaur and the S-IV stage.

On April 10 NASA announced the Project Apollo objective of developing an orbiting laboratory for the study of effects of radiation and prolonged weightlessness, first with animals and later with

42



43



SATURN ILLUSTRATED CHRONOLOGY

a three-man crew. During April Douglas reported that air transport for the S-IV stage was feasible. Douglas had been authorized in 1960 to study air transportation for S-IV stages. This would greatly reduce the time which would be required if the stages were moved by water from California to MSFC at Huntsville, and thence to Cape Canaveral, Florida. The use of gliders, blimps, and aircraft to carry the stages was also considered.


On April 17 the Palaemon began its first trial run to Cape Canaveral. The barge carried a water-ballasted tank simulating the size and weight of the S-I booster, plus a dummy S-V stage for the SA-1. The barge reached Cape Canaveral on April 30. After rehearsing movement of the booster along roads at the Cape, the simulator was reloaded aboard the Palaemon. The dummy S-V stage remained at the Cape. On May 3 the barge began its return trip, arriving at the Redstone Arsenal dock May 15.²¹

MSFC completed construction of the dynamic test tower on April 17, the same day that the Palaemon left for Florida. The dynamic tower permits checkout of the mechanical mating of the C-1 vehicle, and aids in determining the vehicle's natural bending characteristics and the effect of simulated flight vibrations.

MSFC held a Saturn S-II preproposal conference April 18; the first phase of S-II procurement was expected to begin during May. On April 21 Douglas reported to MSFC that the major problem in S-IV stage development was disposal of hydrogen gas generated during engine chilldown.

On April 29, 1961, the first flight qualification test (SA-01) of the SA-1 booster was successfully accomplished in an eight-engine, 30-second test. A second static firing of the SA-1 booster, May 5, 1961, was terminated prematurely because of a problem which caused a shutdown signal through the fire detection system.²²

44



45



46




44. Booster simulator being loaded aboard Palaemon

45. Unloading simulator at the Cape

46. Route of the Palaemon to Cape Canaveral

47. Installing dummy S-I on Dynamic Test Tower


47



A third eight-engine static firing test of the SA-1 booster, performed May 11, lasted 111 seconds and was satisfactory. Meanwhile, assembly of the SA-2 flight vehicle continued, and fabrication of the LOX and fuel tanks for the SA-3 vehicle was begun.²³


In May 1961 NASA Headquarters accepted MSFC's March proposal to incorporate design changes into the S-I stage of the C-1 vehicle. The changes would permit the C-1 to be used as a two- or three-stage vehicle possessing satisfactory safety requirements for the two-stage manned mission. This change eliminated the immediate need for an S-V stage with the C-1 except for possible special missions. Also during May 1961 MSFC began re-examination of the capabilities of the Saturn C-2 configuration to support lunar circumnavigation missions. Results of this examination indicated that a Saturn vehicle of even greater performance would be desirable.

48




48. Positioning flight booster in test stand
49. Configurations of Saturn flight vehicles
50. Separation of upper stages from booster

50



49




SATURN ILLUSTRATED CHRONOLOGY


On May 18 the first phase of S-II procurement began when MSFC requested industry to prepare capability proposals for the design and development of the stage. Also during May Pratt & Whitney shipped a mockup of the RL10-A-3 engine to Douglas and Convair for checks to assure that the engine was physically compatible with both the S-IV stage and the Centaur vehicle. Among other activities in May the Martin Company was awarded a contract to study launch vehicle systems which could be used in lunar exploration beyond the initial Project Apollo flights. These studies included transportation systems for a lunar landing and immediate return for three men, a thirty-day stay on the moon for three men, and a permanent moon base to accommodate 10 to 12 men.

MSFC tested the S-IV dummy stage for the SA-1 flight vehicle May 20-25, 1961. After successful testing the Center began to ready the stage for shipment to Cape Canaveral.

During June construction of the liquid hydrogen test site neared completion at Douglas Aircraft's Sacramento Test Facility (SACTO). Utilizing LOX facilities existing from earlier programs, the site includes two 90,000-gallon liquid hydrogen storage tanks and test stands capable of testing S-IV hardware under a variety of conditions.



51



51. Model of the RL10-A-3 engine

52. Testing of dummy S-IV stage

53



54




- 53. Sacramento test facility
- 54. Dummy Saturn vehicle in dynamic test stand
- 55. Tail Area mockup
- 56. Forward interstage mockup


Engine gimbal tests performed at MSFC during April and May had indicated the advisability of increasing the stiffness of the engine control support structure in the booster. To investigate this matter further, the control engine support structure of the S-I stage of the dynamic test vehicle was modified and a series of single-engine gimbal tests begun on May 29, 1961. As test results were of marginal satisfaction, a new type of actuator servo valve was installed. Further test results were satisfactory. The dummy booster was moved to the dynamic test stand early in June and, for the first time, vertically mated with dummy S-IV and S-V stages. The assembled vehicle was then readied for dynamic testing.²⁴

During May and June 1961 Douglas Aircraft had continued fabrication of full-scale mockups of S-IV stage sections. These mockups are used to check the mating of different sections of the stage and to determine equipment locations.

55



56



On June 2 a lock collapsed at the Wheeler Dam on the Tennessee River. All movement of river traffic was halted. Because the Palaemon was trapped in the upper river, MSFC decided to transport the booster in it overland to a point below the dam. There the stage would be reloaded on barge to continue the trip to Cape Canaveral. To support this plan MSFC obtained a Navy barge which had been mothballed at Pensacola, Florida.

SATURN ILLUSTRATED CHRONOLOGY

Necessary modifications began so that the new barge, renamed the Compromise, could carry the S-I and dummy S-IV stages and dummy payload.

On June 5, 1961, Launch Complex 34 at Cape Canaveral was dedicated in a brief ceremony and turned over to NASA.⁵⁸ In Huntsville final acceptance testing of the S-I stage for the first flight booster began on June 12, 1961. The first operation accomplished was the mechanical mating of the S-IV dummy stage. Design work for later Saturn vehicles also continued at MSFC. On June 15, 1961, a mockup of the new instrument unit portion of the vehicle was completed; this unit, containing guidance and instrumentation, would fly above the upper stages of the last five Saturn C-1 vehicles.

58

59



On June 21 Phase II procurement of the S-II stage began. Four companies were invited to attend the Phase II meeting at MSFC and submit proposals.

After a meeting held in June with Douglas, MSFC directed that the S-IV stage be redesigned to incorporate chilldown venting through which accumulated hydrogen gas could be disposed.

Dr. von Braun announced on June 23 that further engineering design work on the C-2 configuration would be discontinued; effort would instead be re-directed toward clarification of the Saturn C-3 and Nova concepts. Capabilities of the proposed C-3

57


- 57. The barge Compromise
- 58. Launch Complex 34
- 59. Launch Complex 34, blockhouse interior
- 60. Instrument unit mockup

60




- 61. Comparison of Saturn
- 62. Possible Nova Configurations
- 63. Proposed C-3/Apollo configuration
- 64. Installation of SA-T2 on static test stand

61




62



63



64



configuration in supporting the Apollo mission would be determined.

On June 27 the first static test of the SA-T2 booster (the SA-T1 booster modified to the configuration of the SA-2 booster stage) was successfully accomplished at MSFC. This was an eight-engine, 30-second test to confirm effectiveness of the new actuator servo valve and the stiffening of the control engine support structure.²⁶

During the last week in June a contract was awarded to Chrysler Corporation for performance of qualification and reliability testing on various engine, hydraulic, mechanical, and structural components of the Saturn booster. Another contract was awarded in the same month for preliminary design of a facility to static test the J-2 engine.

To commemorate the first anniversary of Marshall Space Flight Center, an open house was held at the Center on July 1, 1961. Attending were such national figures as the NASA Administrator, James Webb; the Director of NASA Launch Vehicle Programs, Major General Don Ostrander; and numerous other national, state, and local dignitaries.

A few days later dynamic testing of SA-D1 began for the purpose of investigating the bending modes of the vehicle and also to continue studies into tank resonances initiated by Langley Research Center

SATURN ILLUSTRATED CHRONOLOGY

during June. While dynamic testing proceeded at MSFC, Rocketdyne in California began static firing tests of a complete F-1 engine. The engine would build up to 1.5 million pounds of thrust when perfected.

Early in July MSFC awarded a contract to Minneapolis-Honeywell for necessary engineering and manufacturing services to adapt the Centaur guidance set to Saturn requirements. Also in July, MSFC awarded a six-month contract to the Boeing Company to study the feasibility of creating huge vehicles by joining solid-propellant "superboosters" with liquid-propellant upper stages.

During July MSFC successfully completed the second and third static firings of the SA-T2 test booster.²⁷ These tests evaluated modifications to reduce engine structure vibration, evaluated flame curtain materials, and checked out a LOX depletion system similar to that used on SA-1. During


65



66



67




68

69



- 65. Dr. von Braun, James E. Webb, and Maj. Gen. Ostrander
- 66. H-1 and F-1 engine comparison (H-1 in foreground)
- 67. Static firing of F-1 engine
- 68. Proposed solid propellant boosters for large space vehicles
- 69. Static firing of SA-T2
- 70. Concept of new static test facility, MSFC
- 71. Artist's concept of Apollo separation from second stage


71



the third test MSFC simulated for the first time the inflight engine cutoff sequence, that is, shutdown of the inboard engines six seconds before shutdown of the outboard engines.

MSFC awarded a contract to the Space Technology Laboratories, Inc., Los Angeles, California, during July, to investigate the relative merits and potential problems of assembling the giant Saturn boosters in horizontal and vertical positions. Other contracts awarded by the Center in July included qualification and reliability testing of Saturn ground support equipment, subsystems, and components, construction of a special assembly building at Cape Canaveral, and site development for the Center's new static test facility in Huntsville.

70




Also in July NASA's Space Task Group invited 12 companies to submit proposals for the manned lunar Apollo spacecraft. Meanwhile, the Center contemplated a nuclear-powered Saturn upper stage and awarded contracts for a six-month RIFT (reactor-in-flight test) design analysis to General Dynamics/Astronautics, Douglas Aircraft Company, Lockheed Aircraft Corporation, and the Martin Company.

SATURN ILLUSTRATED CHRONOLOGY

Assembly of the booster stage for the SA-3 vehicle began on July 31, 1961.²⁸ The following day the SA-2 booster was transferred from the assembly area to checkout. On August 3 a planned 114-second static test of the SA-T2 booster was terminated after 1.2 seconds when instrumentation indicated an unacceptably high temperature of the LOX pump inlet on engine No. 1. The test was rescheduled for the following week. On August 7 the SA-T2 booster was successfully fired in a 124-second test.

Checkout of the SA-1 flight booster, started in June, was completed early in August.²⁹ The booster stage, the dummy S-IV stage, and the dummy payload body were shielded with protective covers and loaded on their respective transporters. The stages and payload body were then moved from the MSFC shops to the docking facilities on the Tennessee River and loaded aboard the Palaemon. On August 5 the barge began the first leg of the trip to Cape Canaveral. At Wheeler Dam the units

73



75

74



76

72

72. Concept of Saturn with nuclear powered stage

73. Booster movement to docking facility

74. Payload movement around Wheeler Dam


75. Booster movement around Wheeler Dam

76. S-I and S-IV stages aboard the Compromise



- 77. Unloading Compromise
in Florida
- 78. First Saturn booster
erection at Cape Canaveral
- 79. S-IV erection at Cape
Canaveral
- 80. Payload body erection
into service structure


77




were unloaded, transported to a dock below the dam, and placed on the second barge, the Compromise, to continue the 2200-mile trip to Florida. On August 15 the Compromise arrived at the Cape and unloaded her cargo; MSFC began assembling the first flight vehicle on the launch pedestal.³⁰

Early in August MSFC invited bids for the construction of a new Saturn launch complex (Launch Complex 37) at Cape Canaveral. Scheduled for completion in late 1962, the new complex would support the high launch rate planned for the Saturn vehicle.³¹

79



80



An F-1 engine was fired on August 16 at Edwards Air Force Base; although the test was terminated after one and one-half seconds, the engine had built up one million pounds of thrust.


On August 24 NASA designated Cape Canaveral as the base for all manned lunar flights and other space missions requiring advanced launch vehicles. NASA would secure an 80,000-acre tract of land, increasing its total area in the vicinity to

SATURN ILLUSTRATED CHRONOLOGY

97,000 acres. The additional land was needed because of the tremendous vibration and noise expected with later launch vehicles.

On September 7 NASA selected the Government-owned Michoud Ordnance Plant near New Orleans as the site for industrial production of the S-I stage. The plant would be operated by industry under the technical direction of MSFC. MSFC continued preparations for a conference to secure estimates from industry on production of the S-I stage.³²


On September 11 NASA selected North American Aviation to develop and build the S-II stage for an advanced Saturn launch vehicle. The stage



will be used in both manned and unmanned missions.

Army Engineers awarded a contract on September 13 for the construction of Launch Complex 37 at Cape Canaveral. The complex would include a mobile steel tower, a blockhouse, and a cable tower on a 120-acre site at the north end of the Cape.

81




81. First Saturn assembled
on Launch pedestal


82. Saturn launch complex
37

83. Artist's concept of launch pedestal for Launch Complex 37

83




84



84. Michoud plant at New Orleans
85. Saturn SA-1 Flight vehicle on launch pedestal

85



By September 15, 1961, the SA-1 vehicle was completely assembled on the launch pedestal at Launch Complex 34. The service structure was moved back, leaving the Saturn standing as it would at launch.

On September 26 a preproposal conference was held at New Orleans to secure bids for industrial production of the S-I stage. Four days later, on September 30, a ground-breaking ceremony was held to begin construction of the Marshall Center's Central Laboratory and Office Building.

Testing continued in September and October at the Marshall liquid hydrogen test facility, where problems in the handling and use of liquid hydrogen are studied. The SA-2 flight booster was installed in the MSFC static test tower early in October. On October 10 a successful eight-engine, 33-second test (SA-04) was performed to check reliability and performance of booster and gimbal systems. Test SA-05 was successfully conducted on October 24 for a duration of 112 seconds. Test objectives included evaluation of the flight cutoff sequence.³³

Late in October NASA selected a 13,550-acre site in Mississippi on which to build a facility for static testing Advanced Saturn and Nova first stages. This location of the Mississippi Test Facility is only 35 miles from the Michoud Plant

SATURN ILLUSTRATED CHRONOLOGY

where industry would manufacture the S-I and S-IC stages.³⁴

The first launch of the Saturn vehicle took place on October 27, 1961. The vehicle, 162 feet high and weighing 460 tons at liftoff, rose to a height of 85 miles during its journey. The inboard engines shut down after 109 seconds of burning; the outboard engines cut off six seconds later. The booster stage produced the 1,300,000 pounds of thrust intended for the first four flight tests. (On subsequent tests, the thrust would be increased to 1,500,000 pounds.) At a speed of approximately 3600 miles per hour the Saturn followed a precalculated flight path to land within 13 miles of predicted impact, over 214 miles from Cape Canaveral. The launch was considered almost flawless.³⁵

On November 6, 1961, MSFC directed North American to redesign the S-II stage to incorporate five J-2 engines, providing a total of 1,000,000 pounds stage thrust.³⁶


Work at the new large-booster static test stand at MSFC was interrupted in November for redesign of the stand to accept thrust levels of more than 7.5 million pounds.

On November 10, 1961, NASA received proposals from five firms for the development and production of the advanced Saturn booster.

NASA announced selection of Chrysler Corporation on November 17 to negotiate a contract to build, check out, and test 20 S-I boosters. These boosters would be manufactured at the Michoud Plant. The contract was signed in mid-January 1962.³⁷

On November 19 the nation's first liquid hydrogen engine, the RL10, successfully completed its preliminary flight rating test. Producing 15,000 pounds thrust, the engine, designed and developed by Pratt & Whitney, performed about 30 percent


86



86. Launch of Saturn SA-1 flight vehicle

87. S-II stage cutaway

87



better than engines using hydrocarbon fuels. Six such engines would power the Saturn S-IV stage.

After this progress in arranging for development of a large launch vehicle NASA, on November 29, 1961, awarded North American Aviation a contract for the design and construction of its payload, a three-man spacecraft.

Marshall Space Flight Center and Manned Spacecraft Center planned to use the C-1 research and development vehicles for vehicle-payload compatibility tests and early systems tests of the spacecraft. The spacecraft was designated Apollo, also the name of the Saturn vehicle missions project.

The Apollo project would be divided into three basic missions: earth orbital flights, circumlunar flights, and manned landings on the moon. The two-stage Saturn C-1 was to support earth-orbital flights of prototype Apollo command modules during the 1964-1965 period. The advanced Saturn C-5 would support reentry and circumlunar Apollo flights.

Meanwhile, the SA-T3 test stage was installed in the test stand. On November 30, 1961, MSFC conducted a test to investigate flight cutoff sequencing, perform an "engine out" test, and study fuel and LOX tank levels. The test was prematurely cut off at 95 seconds by the automatic fire detection system. No hardware damage occurred. This was the first of a series of tests to verify SA-3 design improvements.³⁸

The last of the Saturn 70-inch tanks to be manufactured by MSFC was completed the week of December 4. Future 70-inch tanks would be built by Chance-Vought in Dallas, Texas, and shipped initially to MSFC and later to Michoud for the Chrysler assembled stages.

On December 5, 1961, Atomic Energy Commission (AEC)-NASA Space Nuclear Propulsion Office


SATURN ILLUSTRATED CHRONOLOGY

selected the Aetron Division of Aerojet-General Corporation's proposal as the basis for a Nerva engine test stand contract. The Nerva would be used in nuclear stages with a reactor derived from the Kiwi-B test series. Two days later a pre-proposal conference was held at Huntsville, Alabama, to select a prime contractor for the reactor-in-flight test (RIFT) stage launch vehicle. The RIFT vehicle, planned for use as an upper stage of a Saturn vehicle, would be powered by the Nerva nuclear engine.³⁹

Marshall awarded a design contract on December 6 for modification to the west side of the Center's existing static test tower. The tower, scheduled for completion by the summer of 1963, would be used for acceptance testing of Chrysler S-I stages.

At the Douglas Sacramento Test Facility (SACTO), prototype S-IV stage tankage was installed and propellant loading tests begun on December 11, 1961.


Marshall completed modifications to the Saturn




88

88. S-IV tankage at SACTO test facility

89




90



- 89. Barge Promise
- 90. F-1 engine and test stand
- 91. S-IC stage

91



barge Compromise on December 14, 1961. The barge, renamed Promise, was readied for movement to Wheeler Dam where it would receive stages of the SA-2 flight vehicle. On the same day another F-1 engine test was performed at the Rocketdyne test facility. The engine reached its rated 1.5 million pounds thrust in a short main-stage firing.

NASA selected the Boeing Company on December 15 as a possible prime contractor for the first stage (S-IC) of the advanced Saturn vehicle.⁴⁰ The S-IC, powered by five F-1 engines, would be 33 feet in diameter and about 140 feet high. The manufacturing program at Michoud was to produce 24 flight stages and one ground test stage.⁴¹ In December MSFC awarded a contract to the Mason-Rust Company to perform housekeeping and other administrative services at the New Orleans Michoud Plant.

SATURN ILLUSTRATED CHRONOLOGY

NASA selected Douglas Aircraft on December 21, 1961, to negotiate a contract to modify the Saturn S-IV stage by installing a single J-2 Rocketdyne engine of 200,000 pounds thrust. The modified stage, identified as the S-IVB, would be used as a third stage of the advanced Saturn C-5 configuration.⁴²


On December 28, the Mississippi Test Facility was officially named Mississippi Test Operations by Dr. Robert C. Seamans of NASA Headquarters.

Assembly of the SA-4 flight booster began January 2, 1962. The SA-3 booster successfully completed functional and pressure engine tests and entered pre-static checkout on January 8, 1962.⁴³


NASA announced on January 24 that Aerojet-General Corporation had been selected for design and development of a new liquid hydrogen engine. The engine, known as the M-1, was to power the second stage of the Nova launch vehicle. Its thrust would be 1,200,000 pounds.

MSFC awarded a contract to Constel-Ets-Hokin late in January for the construction of the umbilical tower for Launch Complex 34 at Cape Canaveral. The tower would carry the electrical, pneumatic, and hydraulic connections used in fueling and servicing upper stages.⁴⁴

92



93




92. S-IVB stage cutaway

93. Saturn C-5

94. SA-2 erected on launch pedestal

94



DECEMBER 1961 - MARCH 1962

On January 25, 1962, NASA approved development of the three-stage Saturn C-5 vehicle under the direction of MSFC. The vehicle would support manned circumlunar flights and manned landings by earth or lunar orbit rendezvous method. The C-5 was expected to be capable of placing 120 tons in low earth orbit or escaping 45 tons to the vicinity of the moon.⁴⁵


On February 6, 1962, a 46-second C-1 booster test firing was successfully conducted at MSFC. Stages of the Saturn SA-2 flight vehicle departed Huntsville on February 16 for Cape Canaveral. The vehicle arrived at Cape Canaveral on February 27, 1962, and by March 1 the vehicle was erected on the launch pad of Launch Complex 34. A static firing of the SA-T3 booster was conducted on February 20, 1962. The test, scheduled to last until LOX depletion cutoff, was terminated at 55 seconds due to fire indication at engine No. 6. No damage resulted.⁴⁶

On February 9 a preliminary contract was awarded the Space and Information Systems Division (S&ID), North American Aviation, to design, develop, and fabricate the S-II stage of the C-5 vehicle. MSFC signed a preliminary S-IC development contract with Boeing Company on February 14.⁴⁷

On March 4 NASA selected Sverdrup Parcell Company to provide design criteria and initial planning for the test facilities at the Mississippi Test Operations.⁴⁸

On March 19 the booster for the SA-3 flight vehicle was installed in the test tower, and preparations were begun for the first flight qualification test.⁴⁹ At Douglas Aircraft structural assembly of the first all-systems vehicle was completed in March 1962. The all-systems vehicle, a heavily instrumented configuration of the second (S-IV) stage, would be used to check out all operating S-IV systems.

95



95. Regional map showing
Mississippi Test Facility
96. S-IV All-systems vehicle

96

On April 10, 1962, the SA-3 booster successfully performed its first flight qualification test in a static firing of 31 seconds' duration.⁵⁰ On the same day representatives of 13 companies attended a preproposal conference at MSFC concerning the Nova launch vehicle designs. Submittal of bids was required late in the month.

The large liquid hydrogen engine, J-2, which would power the S-II and S-IVB stages for advanced Saturn vehicles, reached 90 percent sea-level thrust in its initial hot firing tests on April 11. On the same day the huge F-1 engine, being developed to power the S-IC stage, performed a successful 150-second static firing.⁵¹



In mid-April reconstruction of the Wheeler Dam Lock on the Tennessee River was completed; transportation of Saturn flight stages could be made without land detour.⁵²


NASA Headquarters announced on April 18 that the highest national priority (DX) had been

97



97. Construction of Launch
Complex 37
98. Launch of Saturn SA-2
Flight Vehicle

98



approved for the Apollo, Saturn C-1, and Saturn C-5. The priority included all stages, engines, facilities, and related construction for production, test, research, launch, and instrumentation.⁵³

NASA launched the second Saturn flight vehicle, the SA-2, from Cape Canaveral on April 25. As with the SA-1, the vehicle was launched without a technical hold during the 10-hour countdown. This vehicle had a secondary mission. After first stage shutoff at 65 miles altitude the water-filled upper stages were exploded, dumping 95 tons of water in the upper atmosphere. The massive ice cloud produced rose to a height of 90 miles. The experiment, called Project High Water, was performed to investigate the effects on the ionosphere of the sudden release of such a great volume of water. This experiment did not interfere with the major goal of the flight which was achieved when the first-stage engines burned out 116

SATURN ILLUSTRATED CHRONOLOGY

seconds after launch. Every phase of the flight was considered successful.⁵⁴

A 31-second duration eight-engine test of the SA-3 flight booster was conducted on May 17 with excellent overall performance.⁵⁵ The final SA-3 booster acceptance firing test was performed on May 24 for a duration of 119 seconds.⁵⁶

On May 26, 1962, Rocketdyne successfully conducted the first full-thrust, long-duration F-1 engine test. On the same day SA-4 booster fabrication was completed.⁵⁷


In mid-May MSFC directed Douglas to produce a 260-inch-diameter S-IVB stage. The increase of 40 inches over the initially planned diameter permitted development of a more optimum sized

99

99. Static firing of F-1 engine




100



100. C-1 first stage test
stand

101. Saturn C-1B vehicle

101



stage. Also during May the Center decided to increase S-II stage length from 75 feet to 81.5 feet and decrease the S-IC stage length from 141 feet to 138 feet.

On June 5 MSFC contracted to modify the Saturn C-1 booster static test stand at MSFC. The stand, originally built to test the Redstone and Jupiter missiles and later modified for Saturn testing, would provide test positions for two C-1 first stages.⁵⁸

On June 9 Pratt & Whitney completed preliminary flight rating tests of the RL10-A-3 engine for the Saturn C-1 second stage. All test objectives were successfully met. At MSFC the first SA-4 test booster static firing was successfully conducted on June 18 for a duration of 31 seconds.⁵⁹

During June bids were requested for construction of a static test stand to captive fire the Saturn C-5 booster. The stand, to be located at MSFC, would provide handling equipment and thrust restraint for boosters up to 178 feet in length, 48 feet in diameter, and with thrust of up to 7.5 million pounds. Including a crane at the top, the tower would stand 405 feet high, more than twice as tall as the present Saturn C-1 booster test stand.

NASA and Rocketdyne signed letter contracts on July 2 for further development and production of the F-1 and J-2 engines. The contracts, extending through 1965, cover long lead-time items in F-1 engine research and development and early production effort on F-1 and J-2 engines. On July 7 SA-5 flight booster assembly began at MSFC.⁶⁰

A new Saturn vehicle was needed. NASA announced on July 11 that a new, two-stage Saturn-class vehicle would be developed for manned earth-orbital missions with full-scale Apollo spacecraft.⁶¹ The Saturn would be known as the Saturn C-1B. Simultaneously, NASA announced selection of lunar orbit rendezvous as the method


SATURN ILLUSTRATED CHRONOLOGY


for performing the manned lunar landing. This lunar rendezvous mode would require the use of only one Saturn C-5 vehicle to inject the spacecraft into an earth-lunar trajectory. The entire Apollo spacecraft would not land on the moon after its separation from the launch vehicle's third stage. Rather, one unit of the spacecraft, a lunar excursion module, or "bug," would land and later rejoin the rest of the orbiting Apollo.

Meanwhile, progress on Saturn C-1 continued. On July 12 the second static test of the SA-T4 stage was manually terminated after 12 seconds; a broken ground instrumentation wire had caused an erroneous pressure drop indication. Pressure measurement loss caused a premature cutoff of a third SA-T4 static test conducted on July 13. A fourth firing of 120 seconds duration was conducted on July 17; overall performance was excellent. The stage was removed from the test stand on July 20, and MSFC began uprating the engines to 188K thrust level. The uprated stage was redesignated the SA-T4.5.⁶²

102

102. Launch Complex 39





103. Saturn C-5 launch pad

On July 21 NASA Headquarters announced construction plans for Launch Complex 39, Saturn C-5 launch facilities. The 350-foot-high vehicle would be erected and checked out vertically in a special 48-story assembly building. Following checkout a 2500-ton crawler vehicle would move the Saturn C-5 to its launch pad.⁶³

In July NASA announced that a computer center would be established at Slidell, Louisiana, to service the Michoud Operations. The Center, to be one of the nation's largest, would perform engineering calculations necessary in the development, building, and static testing of the Saturn C-1 and C-5 boosters.

To assure C-5 strength, MSFC awarded a design contract in July for a 360-foot-high dynamics test tower. The Saturn C-5 launch vehicle would be suspended in the tower and vibrated by mechanical and electrical means. This simulation of free-flight conditions would determine the vehicle's natural bending modes.⁶⁴

SATURN ILLUSTRATED CHRONOLOGY

On August 6, 1962, NASA and Chrysler Corporation signed a contract for production of 21 C-1 boosters, to be delivered between late 1964 and early 1966. The stages would be produced by Chrysler at the Michoud Plant near New Orleans.⁶⁵ On the same date NASA announced that the Boeing Company had received a supplementary contract from MSFC for work leading to design, development, fabrication, and test of the C-5 booster.

A C-5 second stage contract for design, development, fabrication, and testing of the S-IVB stages was awarded Douglas on August 8. The contract called for 11 of the stages: five for ground tests

104



(two of which would be used later as inert flight stages) and six for powered flight.⁶⁶


Next, provision was made for C-5 guidance and control. On August 13 MSFC selected the C-5 instrument unit design. The cylindrical unit would measure 260 inches in diameter and stand 36 inches high. All vehicle guidance and control equipment would be mounted on panels fastened within this structure.

On August 15 NASA awarded Rocketdyne Division a two-year contract to continue H-1 engine research and development. These first Saturn

104. NASA Computer Center,
Slidell, Louisiana

105. C-5 Dynamic Test
Tower



105



106

- 106. S-IV battleship static firing
- 107. S-IC static test stand

107



booster engines would also be used in Saturn IB boosters.

C-1 second stage progress continued. On August 17 Douglas performed the first S-IV battleship static firing at the Sacramento Test Facility in California. The stage developed approximately 90,000 pounds of thrust for a planned 10 seconds duration; all test objectives were met. A successful full 420-second firing was performed on October 4. In the final phase of testing a total of 11 tests were conducted, the last one on November 8.

MSFC on August 31 awarded a contract for construction in Huntsville of the S-IC static test stand superstructure.⁶⁷ During August Phase I construction of the Launch Complex 34 umbilical tower was completed at AMR. Also in August, MSFC received the Douglas preliminary proposal covering modification of the S-IVB stage for use in the C-1B vehicle.

The SA-3 flight booster was shipped to Cape Canaveral on September 9, arrived on September 19, and was erected on the launch pad on September 21.⁶⁸ By September 24 the inert upper stages and payload had been erected on the booster.


SATURN ILLUSTRATED CHRONOLOGY

Early in September ground breaking ceremonies were held at Seal Beach, California, where assembly and test facilities for the second (S-II) stage of Saturn C-5 would be. The S-II facility would be constructed by the Navy and operated by North American Aviation's S&ID.

On September 11 President Kennedy and Vice President Johnson, with other key Government officials, visited MSFC as part of a two-day tour of four U. S. space centers.

On September 15 Michoud technicians installed a 42-foot boring mill, the largest known, for use in C-5 production.⁶⁹ Also in mid-September, MSFC provided Douglas 90-day program authorization to investigate minimum changes necessary to adapt C-5 second stages to C-1B. Douglas would also study attachment of the S-IVB stages to the C-1 booster, as well as separation during flight.

108



109




108. S-II stage assembly and test facility


109. President Kennedy visits MSFC

- 110. Installation of 42-foot boring mill
- 111. Mississippi Test Facility

110



111



On September 25 assembly began of the SA-6 flight booster. Meanwhile, preliminary plans were completed for development of the Mississippi Test Operations. First phase of the three-phase program included building two test stands each for static firing the S-IC and S-II stages and about 20 service and support buildings. Improvement of approximately 15 miles of river channel and construction of a canal within the test facility would permit transportation of stages from Michoud to Mississippi Test Operations test stands.

All objectives were met during the second SA-4 booster flight qualification static firing on September 26. A record burning time was set when the inboard engines operated for 121.5 seconds and the outboard engines for 127.43 seconds. The SA-4 booster was removed from the static test tower on October 1; post-static checkout began.⁷⁰ On the same day MSFC let a contract for construc-

SATURN ILLUSTRATED CHRONOLOGY

tion of the vertical assembly building foundation at Michoud.⁷¹

During September MSFC directed S&ID to develop a plan for C-5 dual plane separation. In dual plane separation, S-IC separation would be followed by separation of the S-II interstage.

The first industry-produced booster was started October 4 at Michoud when Chrysler began fabrication of S-I-8, the first of 21 Saturn C-1 boosters it was scheduled to produce.


Two J-2 engine full-thrust firing tests, of 50 and 94 seconds duration respectively, were successfully performed prior to a long-duration static firing on October 4. The long-duration engine test conducted by Rocketdyne was satisfactory throughout the scheduled 250 seconds operation.⁷² A second long-duration test of 220 seconds was successfully conducted on October 6 at the Santa Susana Test Facility.

During October MSFC began tests on the C-1 up-rated test stage SA-T4.5. Tests were to check the integrity of the propulsion system and effect of the 188K engines on the flame deflector. After tests were successfully concluded the stage went to Michoud for use in checking out facilities.

MSFC awarded a Saturn C-5 contract on October 5 for construction in Huntsville of a combined S-IC stage vertical assembly building and hydrostatic test tower.⁷³ NASA Headquarters approved on October 12 the Saturn C-5 second stage (S-II) long-term research and development contract with S&ID.⁷⁴

On October 15 NASA Headquarters approved the Saturn C-5 vehicle development schedule, Plan V.⁷⁵ The plan includes funding and test program adjustments, assembly of the first S-IC flight stage at MSFC, and launch and ground test schedule changes.

112



113




114




- 112 Dual plane separation
- 113. J-2 test facility
- 114. S-IC Stage facility

115. SA-5 configuration
 116. Unloading S-IV stage
 at MSFC

115



116



In October NASA arranged to dredge an access channel to the Saturn C-5 Complex 39 Vertical Assembly Building and Launch Pad area at Merritt Island, Florida. On October 2 MSFC contracted for construction of a flame deflector for the MSFC Saturn S-IC test stand.⁷⁶

During October MSFC decided to fly a Jupiter-type payload with the fifth Saturn flight.⁷⁷ Saturn C-1 second stage progress included completion of the S-IV Hydrostatic/Dynamics Stage at Santa Monica. It began its trip to MSFC via the Victory Ship Smith Builder on October 26, was transferred to the barge Promise at New Orleans, and delivered to MSFC on November 16 for six months of comprehensive dynamic testing.⁷⁸

The Launch Operations Center awarded a contract in October to modify the Complex 34 fuel, LOX, and liquid nitrogen servicing systems in preparation for Saturn C-1 Block II vehicle launches. SA-5 flight booster assembly was completed on November 6 and the booster transferred for pre-static checkout.⁷⁹ Assembly of the SA-D5 booster for dynamics testing was completed on October 29. This stage was installed in the MSFC dynamics test tower on November 13, 1962. The SA-D5 booster simulated configuration of the final Saturn C-1 boosters which were expected to be used for manned flights.

During November Douglas awarded subcontracts for development of the S-IVB's 1750-pound thrust ullage motors and 150-pound thrust attitude control motors.

On November 8 the last S-IV battleship test with RL10-A-1 engines was completed at SACTO; 11 tests totaling 1137.6 seconds were accomplished. The A-1 engines were then removed and installation began of RL10-A-3 operational-type engines for the next phase of battleship hot firing tests.⁸⁰

Cost negotiations between MSFC and Boeing began

SATURN ILLUSTRATED CHRONOLOGY


on November 15 for the long-term S-IC stage development and production contract.

The third Saturn flew on November 16. SA-3 was successfully launched from Cape Canaveral, carrying a full propellant load of 750,000 pounds. It rose to a height of about 104 miles. Flight range was 131 statute miles. Inboard engine cutoff occurred as planned after 141 seconds of flight; outboard engine cutoff came eight seconds later. Project High Water was performed as a secondary mission on SA-3 as on SA-2.⁸¹

On December 13 a contract was awarded for the construction of the Michoud S-IC Hydrostatic Test and Vertical Assembly Building. Also at Michoud, Chrysler Corporation began fabrication of the tenth and final research and development Saturn booster, S-I-10.⁸²

In December design of Marshall's C-5 Dynamic Test Tower was completed; Douglas awarded a contract for fabrication of the S-IVB battleship tank; and, at Cape Canaveral, the Corps of Engi-


117



117. Launch of SA-3 Flight Vehicle


118. Vertical Assembly Building at Michoud

118



neers awarded a contract for design of the Launch Complex 39 Vertical Assembly Building.

119



119. Launch Complex 39
Vertical Assembly Building
120. SA-D5 booster

120



Initial checkout of the S-IV all-systems vehicle began at Santa Monica in late December.⁸³ Douglas began fabrication of S-IV-111, the first production S-IV flight stage.

Rocketdyne studied causes of the F-1 engine combustion instability first encountered during June 1962. Testing with modified engine hardware began in the latter part of 1962 and was scheduled to continue during 1963.⁸⁴

During early January 1963 construction began at the Huntington Beach Assembly Facility where Douglas Aircraft Company will assemble S-IVB stages.

In January MSFC began dynamics tests of the SA-D5 vehicle configuration.⁸⁵ The Center finished expansion of its static test tower for Saturn C-1 Block II first stages.

Douglas completed checkout of the S-IV dynamic/facilities vehicle at Santa Monica and, during January, sent this vehicle to Cape Canaveral for use in checkout of Launch Complex 37B facilities.⁸⁶

MSFC shipped by barge the complete SA-4 vehicle from Huntsville to Cape Canaveral. The complete vehicle was erected on Launch Complex 34 by February 5.⁸⁷

SATURN ILLUSTRATED CHRONOLOGY

121



121. S-IV Dynamic/Facilities stage at Cape Canaveral

122. SA-4 on Launch Complex 34


On January 26 at SACTO, Douglas static fired the RL10-A-3-powered S-IV battleship vehicle. Test duration was 468 seconds.⁸⁸ On February 1 Douglas shipped the S-IV all-systems vehicle from Santa Monica to SACTO for testing.⁸⁹ At Launch Complex 37B the launch control center, automatic ground control station, and umbilical tower were completed on January 30.

During the first week of February NASA Headquarters announced a change in Saturn vehicle nomenclature. Saturn C-1 became Saturn I, Saturn C-1B became Saturn IB, and Saturn C-5 became Saturn V.⁹⁰


Saturn V hardware development was under way. In early February Boeing began S-IC bulkhead gore-forming operations at Wichita, Kansas.⁹¹

On February 4 MSFC decided to modify the west side of the MSFC static test tower for F-1 engine testing. The modification would allow single F-1 engine tests to begin several months earlier than scheduled. The stand would later be reconverted for S-I static testing. On February 8 MSFC awarded a contract for construction of a single F-1 engine test stand superstructure at MSFC.

122




123




- 123. Saturn Vehicles
- 124 S-IC bulkhead gore forming
- 125 F-1 test stand

125



124



Early in February S&ID began occupancy of the Seal Beach assembly and test facility where Saturn V second stages would be assembled and tested. Also in February S&ID successfully completed S-IC/S-II stage dual plane separation impingement tests.⁹²

The first live Saturn I second stage would be powered by liquid hydrogen, still not flight proven. The S-IV battleship stage permitted tests of this

SATURN ILLUSTRATED CHRONOLOGY

126




126. S-II Seal Beach facility
127. Crawler-transporter

new technology. On February 18 and 19 S-IV battleship turbine spinup tests were unsuccessful due to inadequate purge procedures; however, on February 23 a successful spinup test was accomplished. Two days later the second battleship firing testing RL10-A-3 engines was terminated after 6.5 seconds when a hydrogen leak caused a fire at engine No. 4. No damage resulted.⁹³

On February 20 NASA began contract negotiations for design, fabrication, erection, and testing of

127




the crawler-transporter which would transport the Saturn V vehicle to the launch pad of Launch Complex 39. The contract was signed on March 29, 1963.

NASA Headquarters on February 20 approved the plan for modification of the basic Chrysler contract. The plan provides for redesign of the S-I stages.⁹⁴

For Saturn V, NASA Headquarters approved the Boeing S-IC definitive contract on February 21. Boeing will design, develop, and manufacture one ground test stage and nine flight stages at the Michoud Plant in New Orleans.⁹⁵ On February 27 the Corps of Engineers awarded a design contract for the Saturn V test facilities at the Mississippi Test Operations.

MSFC awarded a contract in February for construction of three micrometeoroid satellites, two for flight and one for backup.⁹⁶ The satellites,

128



128. Micrometeoroid satellite


secondary payloads for Saturn I vehicles SA-8 and SA-9, would be used to obtain data on frequency and penetration of micrometeoroids in low earth orbits and to relay the information back to earth. On February 27 the first S-I-5 flight qualification static test (SA-11) was successfully conducted at MSFC for a planned duration of 32 seconds.

SATURN ILLUSTRATED CHRONOLOGY

On February 19 at the Michoud Plant, Boeing completed the first Y-ring for the S-IC test fuel tank; on March 4 the Y-ring was delivered to MSFC where the fuel tank would be assembled.⁹⁷ Also at Michoud during February a contract was awarded for design and construction of the engineering building.

During February, construction of Test Stand 2B at SACTO was completed and the propellant pneumatic systems were installed and checked out.

130




On March 1 Rocketdyne successfully gimballed an F-1 engine during a hot firing test in California.⁹⁸ On the same day qualification of explosive forming dies for S-II gore segments began at North American's El Toro Facility.

S&ID awarded a construction contract for the electro-mechanical mockup at Downey, California, on March 1; the mockup will be used for design and engineering verification of various S-II systems. On March 8 MSFC awarded a one-year contract to industry for operation of the Slidell Computer Facility at Slidell, Louisiana.

Dynamic testing of the SA-D5 vehicle was completed on March 7.⁹⁹ On March 13 a second flight qualification static firing of S-I-5 was conducted

129




129. Static firing of S-I-5


130. Completed Y-ring at Michoud

131. Explosive forming dies

131



132



132. SA-5 Instrument unit
133. SA-4 launch

133



for a planned period of 143 seconds. Subsequent analysis revealed propulsion system irregularities, and a third static firing was conducted on March 27 to confirm corrections. This test, successfully conducted for a duration of 144 seconds, concluded S-I-5 flight qualification testing.¹⁰⁰

NASA Headquarters approved MSFC procurement plan for four additional S-IVB stages on March 22.¹⁰¹ On the same day, at MSFC, checkout of the SA-5 instrument unit was begun.


Saturn SA-4, the fourth and last of the single-powered-stage, Block I vehicles, was successfully launched on March 28 from Launch Complex 34. The vehicle, carrying several Block II components for test, reached an altitude of 80 statute miles. Range was 218 statute miles and peak velocity 3660 miles per hour. As a secondary mission the No. 5 inboard engine was cut off at 100 seconds to test the vehicle engine-out capability. Overall performance of the flight was very satisfactory.¹⁰²

As the Saturn I project entered its final phase, work on the larger Saturns proceeded. On March 12 Douglas, S-IVB stage contractor, invited bids for a construction contract for the Beta Complex at SACTO; the contract was awarded in late March.¹⁰³ Also in March S&ID placed a contract for the S-II battleship tank structure; fabrication of components began early in April. The first S-IC cylindrical skin segment was completed by Boeing at Wichita during April.

The S-I-D5 stage was removed from the Dynamics Test Tower at MSFC on March 18. The booster was shipped to Cape Canaveral on April 5 for use in facilities checkout of Launch Complex 37B. The stage arrived at the Cape on April 15 and was erected three days later. On April 19 the S-IV Dynamics/Facilities vehicle was erected. Calibration and mechanical checks were begun the week of April 24, followed by propellant loading tests early in May.

SATURN ILLUSTRATED CHRONOLOGY


134



135



136



134. Facility checkout of Launch Complex 37B

135. Checkout of S-IV-5

136. Completion of S-IV battleship test program

During early April Douglas finished checkout of S-IV-5 at Santa Monica. On April 19 the stage arrived at SACTO and was installed on Test Stand 2B on May 22. Static testing followed modifications and engineering changes.¹⁰⁴


On April 22 MSFC installed S-I-6 in its static test tower. The first short-duration static firing was successfully conducted on May 15 for a duration

of 33.75 seconds.¹⁰⁵

Douglas initiated S-IV all-systems propellant loading tests at SACTO on April 1. Tank bending and insulation cracking halted testing for field repair of the tank. On May 14 another test was performed and a hydrogen leak was detected in the common bulkhead. The vehicle was removed from Test Stand 2B for inspection repair on May 18.¹⁰⁶


At SACTO Douglas completed the S-IV battleship test program with a final LOX depletion firing of 444 seconds on May 4. Sixteen tests totaling 4302.5 seconds were accomplished using the RL10-A-3 engines. The complete battleship test

137



137. Douglas Huntington
Beach Facility
138. S-IVB forward mockup

138



program (including both A-1 and A-3 engines) had a total firing time of 5440.1 seconds. On May 13 a one-engine gimbal test was conducted. On May 21 the battleship tank was shipped from SACTO to MSFC. It was used by the Center for liquid hydrogen slosh test. Five of the six engines were shipped to MSFC and used on the dynamic vehicle for gimbaling tests.¹⁰⁷

SATURN ILLUSTRATED CHRONOLOGY

During May the S-IVB Huntington Beach fabrication and assembly building was completed and construction of the assembly tower begun. Also during May MSFC received the S-IVB forward area mockup from Douglas to be used to determine interface requirements between the S-IVB and instrument unit.

On May 18 at Michoud Chrysler finished clustering of propellant containers for S-I-8, the first booster fabricated by industry rather than by federal personnel at MSFC.¹⁰⁸

During early May the J-2 engine, used on S-IVB and S-II stages, was successfully fired for the first time at a simulated space altitude in excess of 60,000 feet. The engine developed 200,000 pounds thrust; after 20 seconds the test was terminated as programmed.¹⁰⁹

On May 13 NASA negotiated a firm cost proposal for incorporation of dual plane separation for S-IC/S-II stages with S&ID.¹¹⁰ During mid-May land clearing at Mississippi Test Operations began in preparation for the dredging of a barge harbor and access channel; a 10.5-mile track of railroad was completed into the test site.

Dynamic testing of the S-IV stage, instrument unit, and Jupiter-type payload was completed at MSFC during mid-May. On May 23 the Apollo boilerplate and associated units were installed and testing resumed; this phase of testing was completed on June 16. Also during May MSFC engineers completed the design of the S-IC stage transporter.


On May 28 MSFC awarded a contract for Federal Aviation Agency (FAA) certification flights of a modified B-377 aircraft. The aircraft would be used for transportation of the S-IV stage and other cargoes. Formal FAA certification was received on July 10.¹¹¹

During the first of June MSFC personnel began occupancy of the new Central Laboratory and Office

139. Fabrication and assembly of S-I-8 at Michoud; a. barrel assembly, b. lower thrust ring, c. tail unit, d. thrust structure, e. spider beam, f. LOX and fuel tanks ready for clustering, g. installation of center LOX tank, h. clustering 70-inch LOX tanks, i. clustering 70-inch fuel tanks, j. final assembly

140. Pregnant Guppy aircraft


139 a.



b.



c.




d.




e.



f.




g.




h.



i.



j.



140



Building. Also at MSFC construction of the Saturn V Dynamic Test Tower foundation began in early June. A full-duration, S-I-6 flight qualification static test was successfully conducted on June 6 for 142.37 seconds. The inboard engines were cut off by LOX low-level sensors at 136 seconds and the outboard engines six seconds later. On June 17 the stage was removed from the stand for post-static checkout.¹¹²


On June 5 limited beneficial occupancy was granted

SATURN ILLUSTRATED CHRONOLOGY


on the S-IC stage Vertical Assembly and Hydrostatic Test Facility at MSFC.¹¹³ Clustering of tanks for S-I-9, the last Saturn I booster to be fabricated at MSFC, began on June 4 and was completed on June 19; inboard engine installation was completed on July 17.¹¹⁴

On June 17 the Corps of Engineers awarded contracts for excavation for lock and bascule bridge, emergency service building, dredging of East Pearl River and clearing of Saturn V complex at

143




144



141



142



141. Saturn V Dynamic tower

142. S-IC facility

143. Assembly of S-I-9 stage

144. Dredging at Mississippi Test Facility


the Mississippi Test Operations. At MSFC gimbaling tests on engine No. 1 of the S-IV stage were completed in pitch and yaw directions on June 28. Three days later dynamic tests of the S-IV stage with Apollo boilerplate and launch escape system were completed.

Pre-static checkout of the S-IV-5 stage at SACTO began on June 18.¹¹⁵ During late June repair of the all-systems common bulkhead was completed. On July 6 the vehicle was installed on Test Stand 1 at SACTO. At Santa Monica, Douglas completed checkout of the S-IV-6 stage on July 19.¹¹⁶

During June MSFC welded the upper bulkhead for the S-IC test fuel tank to the Y-ring.

145. Mating bulkhead to Y-ring

145



June facility checkout of Launch Complex 37 Pad B was completed at Cape Canaveral. The S-IV Dynamics/Facilities vehicle was flown to the West Coast for flight performance test of the Pregnant Guppy aircraft.

The S-I-D5 stage departed Cape Canaveral on July 1 aboard the barge Palaemon, arriving at MSFC

SATURN ILLUSTRATED CHRONOLOGY


on July 14; the stage was used for additional dynamic testing. On July 9 MSFC directed Chrysler to proceed with fin redesign as part of the S-IB stage redesign effort.¹¹⁷

On July 25 the Corps of Engineers awarded a contract for construction of S-IC and S-II stage test stand foundations at Mississippi Test Operations. At MSFC during late July the concrete towers for the S-IC Static Test Stand were completed and steel erection begun. The Center successfully welded the S-IC upper cylindrical skin section to the Y-ring.

During July construction of foundations was completed for Test Stand 1 and 3 at SACTO Beta Complex. Also at SACTO, Douglas initiated hydrostatic test and calibration of the S-IVB battleship tank on August 2.

On August 5 NASA completed S-IB contract negotiations with Chrysler Corporation at Michoud.¹¹⁸

146



146 S-IB stage

147. S-IC static test tower

147



The following day S-IVB/Saturn IB contract negotiations were completed with Douglas Aircraft Corporation at Santa Monica.

On August 6 the Corps of Engineers awarded a construction contract for the Mississippi Test Operations Laboratory and Engineering Building. During August hydraulic dredging and fill operations were completed for the vertical assembly building at Cape Canaveral. MSFC awarded a contract on August 6 for assembly of two S-IC transporters; assembly began two days later.

148




On August 11 MSFC started the S-I-5, S-IU-5, and Payload toward Cape Canaveral.¹¹⁹ MSFC installed on the barge Promise a complete dynamics test vehicle of the SA-6 configuration in the dynamic test tower.¹²⁰

Also at MSFC during early August the S-IC aft area mockup was completed, with two F-1 engine mockups attached.¹²¹

On August 5 the first attempt to acceptance fire the S-IV-5 stage at SACTO was aborted at 63.6 seconds due to an indication of fire in the engine area; however, inspection revealed an instrumentation malfunction in ground support equipment. On August 12 a successful 477-second, full-duration S-IV-5 flight qualification firing was conducted.¹²² During August the S-I-5 stage, booster

149



148. Construction at Launch Complex 39
149. S-IC stage aft area mockup

SATURN ILLUSTRATED CHRONOLOGY

for the fifth Saturn flight vehicle, was erected at Cape Canaveral.

On September 1 Dr. Wernher von Braun, MSFC Director, announced a major reorganization of the Center. Progress in the Saturn program, and a rise in industrial participation to approximately 90 percent of the budget, necessitated the changes. The Center created two major subdivisions — Research and Development Operations and Industrial Operations. Research and Development Operations, composed of the nine technical divisions redesignated laboratories, was strengthened for its Huntsville-based operations and for specialized contractor assistance. Industrial Operations was created to direct the portion of the Center's work performed by prime contractors, mainly the development of stages and engines for the Saturn I, Saturn IB, and Saturn V multi-stage rockets.¹²³


150



150 S-IV-5 acceptance firing

151. MSFC reorganization

151




In mid-September Douglas flew the S-IV-5 from SACTO to the Cape via the Pregnant Guppy aircraft.¹²⁴ Other Saturn I progress in September included MSFC's final assembly of the S-I-9 and Douglas' beginning of pre-static checkout of the S-IV-6 stage.

The Saturn IB second stage contract modification was signed by Douglas and submitted to NASA on September 10. In the same month a joint MSFC/Manned Spacecraft Center Ad Hoc safety meeting considered Saturn IB crew safety and developed a "Preliminary Emergency Detection System" specification. Douglas began installing insulation on the S-IVB battleship stage, a heavier version for ground tests of the S-IVB flight stage.¹²⁵


During September MSFC completed Saturn V's S-IC forward area mockup and completed the S-IC-T (all systems) intertank assembly.¹²⁶ Numerous research activities were under way: MSFC's Test Laboratory studied sound suppression problems, Jet Propulsion Laboratory (JPL) and Lewis Research Center began S-IC base heat-

152




152. Loading of S-IV stage
153. Intertank for S-IC-T

153



SATURN ILLUSTRATED CHRONOLOGY

154



ing tests. The contractor for the Saturn V second stage, S&ID of North American Aviation, began PERT reporting at Seal Beach on the S-II program with eleven networks reflecting about 8500 activities. On September 23 S&ID sent MSFC the S-II and forward interface mating mockups for use in mating tests of the S-IC forward skirt.¹²⁷

In October technicians at Launch Complex 37B joined the S-IV-5 stage, payload, and instrument unit to the S-I stage. Pre-launch checkout of the SA-5 vehicle continued.¹²⁸ In Huntsville MSFC completed the SA-5 flight operational sequence plan, providing for nine-hour completion of launch day tasks.

Progress on the other Saturn I vehicles continued during October. Chrysler completed assembly of the S-I-8 stage at Michoud.¹²⁹ MSFC personnel discovered and corrected minor problems in the in-

154. Experimental firing in sound suppressor development program

155. S-II stage activities; a. S-II aft interstage mockup, b. S-II forward interstage mockup, c. S-II bulkhead fabrication building at Seal Beach, d. S-II structural test tower at Seal Beach, e. bulkhead fabrication area at Seal Beach, f. gore forming facility at El Toro, g. S-II skate bulkhead welders at Seal Beach, h. Explosive forming die at El Toro

155 a.




b.



c.



d.




e.



f.



g.



h.



strument unit network of the SA-6 vehicle.¹³⁰ The Center's Test Laboratory static tested the SA-7 booster for the first time, and on October 22 performed the second and final acceptance test on S-I-7 for a duration of 138.93 seconds.¹³¹ The Douglas second stage work at SACTO included initiation of pre-static checkout of the S-IV-6 and start of assembly of the S-IV-10.

NASA approved a Chrysler contract modification in October that provided for 12 Saturn IB boosters in lieu of operational Saturn I boosters. At Michoud, Chrysler continued design studies on components for these S-IB stages. MSFC approved the design release for the S-IB spider beam and completed the 50 percent design review of the gaseous oxygen line and diffuser. Douglas continued work on hydrostatic and dynamic test equipment for Saturn IB's second stage and began assembly of its S-IVB battleship stage at SACTO. Douglas began fabricating an S-IVB liquid hydrogen test tank in Huntsville for use in J-2 engine tests.

Boeing personnel at Michoud completed the Saturn V booster lower thrust ring assembly in October.¹³² MSFC personnel continued fabrication of the fuel tank and other major components for the S-IC test stage. S&ID continued fabrication and assembly of ground test S-II stages and construction of test stands. On October 31 MSFC received from Rocketdyne Division of North American Aviation the first production model of the huge F-1 engine.¹³³

NASA announced on October 30 a rephasing of Saturn manned flight missions. Saturn I manned missions were dropped and six Saturn I vehicles thereby deleted. The Saturn I program will terminate with completion of the ten unmanned flight vehicle research and development program. NASA approved speed-up of Saturn IB development. The more powerful Saturn IB vehicle will launch the Project Apollo manned flights in preparation for Saturn V's manned moon mission. "All-up" testing will be utilized in future Saturn flights. That

SATURN ILLUSTRATED CHRONOLOGY

is, there will be no further flights with dummy stages; development flights will test Saturn vehicles in final configuration.¹³⁴

In November NASA postponed the fifth Saturn I flight because of technical problems with the SA-5 vehicle.¹³⁵ At SACTO Douglas placed the SA-6 vehicle's second stage in a test stand. On November 22 Douglas conducted a successful 460-second acceptance firing of this S-IV-6 stage.¹³⁶ During November Douglas finished assembly of another Saturn I second stage, the S-IV-7. The first Chrysler-built booster, S-I-8, was in final check-out.

MSFC and Chrysler completed their study of the use of uprated H-1 engines in Saturn IB's booster


157




158




156 a.



b.



c.



156. Erection of SA-5 at Cape Canaveral, a. instrument unit, b. S-IV-5 stage, c. hoisting instrument unit, d. payload adapter, e. hoisting payload, f. payload, g. SA-5 at Launch Complex 37B
157. S-IVB liquid hydrogen test tank, MSFC

d.



e




f.



158. Michoud mechanic drilling holes in the first S-IC lower thrust ring

159. S-II test stand construction at Santa Susana; a. flame deflector in battle-ship test stand, b. all-systems test stand, c. battle-ship test stand

g




159a



c.



b.




SATURN ILLUSTRATED CHRONOLOGY


stage. On November 8, after Chrysler determined engine load criteria and Saturn IB schedule impact, MSFC directed Rocketdyne to develop the more powerful engine.¹³⁷ Douglas occupied its joint Engineering Development Systems Integration Laboratory/Systems Integrations Area facility on November 1. Second stages for Saturn IB (S-IVB) will be assembled and tested in this Huntington Beach facility. At Michoud during the month Chrysler completed a mockup of the S-IB spider beam and began manufacturing the second stage adapter.¹³⁸

NASA contracted on November 12 for a Saturn V launch pad at Kennedy Space Center, Complex 39.¹³⁹ The pad will cost over \$19 million. MSFC continued manufacture of Saturn V booster test stage components in November. The Center began S-IC stage test fuel tank assembly in its new Vertical Assembly Building. Additions to the Saturn V booster contract increased Boeing support to MSFC and raised the total value of the S-IC contract to more than \$447 million. On November 8 MSFC contracted for a \$13.4 million test complex at Mississippi Test Operations for the Saturn V

160



161




160. Second stage for SA-6 flight being placed in SACTO stand for acceptance testing
161. Spider beam mockup for Saturn IB's first, S-IB, Stage

b.




162 a



162. Saturn V booster test stage components; a. assembly of S-IC test fuel tank, b. welding S-IC bulkhead

163



164



163. Assembly of S-II battleship

164. First J-2 extended-duration firing test

second stage (S-II). At Seal Beach, S&ID continued assembly of the S-II battleship stage for static tests.

An important engine development milestone occurred on November 27 with Rocketdyne's first extended-duration firing test of the J-2 engine. This successful test of the 200,000-pound thrust, liquid hydrogen-fueled engine lasted for more than 8 minutes. The J-2 will power upper stages of both the Saturn IB and the Saturn V vehicles.¹⁴⁰

On November 28 the name of the NASA facility at Cape Canaveral was changed officially to John F. Kennedy Space Center (KSC).


MSFC in December postponed the SA-5 flight until January 1964 after discovering cracks in fuel line fittings on the S-I-5 stage. MSFC decided to replace critical tubing on it and all remaining S-I stages. On December 13 MSFC accepted from Chrysler at Michoud the first industry-built Saturn I booster (S-I-8).

By the end of December Chrysler had completed and MSFC had approved most of the structural redesign of Saturn IB's first stage.¹⁴¹ During the month NASA awarded the basic S-IVB contract modification which also accelerated the program for this Saturn IB second stage.¹⁴² Also, Douglas completed fabrication of major components for the S-IVB hydrostatic test stage.¹⁴³

Saturn V progress during the month included MSFC's first F-1 engine tests on December 3 and 5. Duration of the first firing tests was 1.25 seconds. The second firing lasted 10 seconds.¹⁴⁴ On December 20 NASA updated the Boeing S-IC contract to amend the stage delivery schedule.¹⁴⁵ The contract as changed meant that MSFC rather than Boeing would provide the second S-IC flight booster. On December 27 NASA amended the prime S-II stage contract with S&ID in order to make the first S-II flight stage "live" instead of

SATURN ILLUSTRATED CHRONOLOGY

165



165. MSFC F-1 engine firing test

dummy.¹⁴⁶ During December NASA signed an agreement with the Military Sea Transport Service (MSTS); by the agreement the USNS Point Barrow would be used for shipment of S-II stages from the West Coast manufacturing site to test and launch sites.¹⁴⁷

January 1964 saw the beginning of the last phase of the Saturn I research and development program. The first four flight vehicles had carried dummy second stages. Now flight testing of second stages began.

Early in January technicians installed new tubing assemblies in the SA-5 booster. On January 24 Douglas second stage work under way at SACTO suffered a setback when the S-IV all-systems vehicle exploded during an attempt to static fire it.¹⁴⁸ An overpressurized oxidizer tank caused loss of this vehicle as well as damage to the test stand

DECEMBER 1963 - FEBRUARY 1964

and ground support equipment. On January 27 a blocked fuel line caused a two-day postponement of the SA-5 flight; technicians had failed to remove a flange used in checking the LOX line.¹⁴⁹

On January 29, 1964, NASA launched the fifth Saturn I. The liquid hydrogen-fueled second stage, flight tested for the first time, functioned perfectly. First-stage engines shut off as planned, 147 seconds after liftoff. The second stage separated, ignited, burned for 8 minutes, and with the attached instrument unit and sand-filled nosecone attained orbit as an earth satellite. Time from liftoff until orbit was 10.32 minutes. The almost 19-ton satellite was the heaviest ever orbited.¹⁵⁰

Meanwhile, MSFC continued production of test components and expansion of test facilities for Saturn IB and Saturn V multi-stage rockets. NASA announced in January that construction budgets for Saturn IB and Saturn V facilities at Michoud and the nearby Mississippi Test Operations would be \$6,534,000 and \$61,991,000, respectively, for FY 65.

In February MSFC shipped Saturn I's sixth flight booster and instrument unit from Huntsville to

166. a. Fifth Saturn I flight
b. second stage separation

166 a.



b.




SATURN ILLUSTRATED CHRONOLOGY

KSC; the trip by barge took eleven days.¹⁵¹ Douglas flew the S-IV-6 stage to the Cape. On February 19 MSFC successfully completed meteoroid payload fairing separation tests for SA-8 and SA-9 missions. MSFC decided that the sixth Saturn I vehicle would have an active guidance system.

In February, Chrysler started fabrication of components for the first two Saturn IB boosters, utilizing some of the components available from cancelled Saturn I vehicles. Second stage accomplishments included Douglas's fabrication work on the S-IVB/IB-1 as well as further development of the S-IVB hydrostatic, all-systems, dynamic, and battleship test stages. Douglas also worked on an S-IVB facilities checkout stage.¹⁵³


167



167. Saturn I LOX tank which will be modified for Saturn IB

Saturn V progress included MSFC's successful hydrostatic testing on February 8 of the first stage (S-IC) test fuel tank.¹⁵⁴ During February the Center conducted seven static tests on an F-1 engine.¹⁵⁵ At Edwards AFB an F-1 engine systems test on February 28 ended in an explosion and severe engine damage. Rocketdyne attributed the explosion to structural failure of the LOX pump.¹⁵⁶ Rocketdyne's other systems tests were generally successful. S&ID continued manufacture of the S-II battleship stage thrust structure and aft skirt assembly in its stand at Santa Susana.

168



168. Saturn V test fuel tank

During February atmospheric physicists of MSFC's Aero-Astrodynamic Laboratory participated in a wind data study. In the ten-day search for atmospheric jet streams which affect rocket flight they released 161 weather balloons (rawinsondes). This was part of an extensive measuring program in the southeastern United States originated by MSFC to aid Saturn stage structural designers in studies on sound propagation.

In March Kennedy Space Center technicians worked overtime preparing for the sixth Saturn I launching. In Huntsville, MSFC performed vibration tests on the SA-9 instrument unit, S-IU-9, and also began dynamics testing on vehicles in the SA-8, SA-9, and SA-10 configurations. MSFC successfully static fired S-I-9, final booster manufactured by the Center, in a short duration test.¹⁵⁷ Douglas continued second stage production and started static tests on the S-IV-7 at SACTO.¹⁵⁸ Chrysler completed fabrication and replacement of critical tubing assemblies for S-I-10 at Michoud.

Saturn IB activities during March included begin-

SATURN ILLUSTRATED CHRONOLOGY

ning of fabrication of components for the second S-IVB flight stage, the S-IVB/IB-2.¹⁵⁹ Douglas also started assembly of the S-IVB dynamics test stage in its assembly tower at Huntington Beach. Early in March the Center awarded a contract to IBM for Saturn IB and Saturn V instrument unit digital computers and data adapters.¹⁶⁰ MSFC also arranged for integrating the eight systems of the Saturn IB and Saturn V instrument units. These systems are: guidance, control, electrical, measuring, telemetry, radio frequency, structural, and environmental. International Business Machines (IBM), under a \$5.5 million contract, will provide development plans, test plans, and procurement specifications during the five-year first phase of the contract.¹⁶¹ On March 23 NASA published Saturn IB mission assignments as coordinated with MSFC and Manned Spacecraft Center.¹⁶²

At Seal Beach, S&ID began assembly of the first Saturn V second stage (S-II) flight hardware. S&ID technicians conducted three successful tests of S-IC/S-II separation techniques. In Huntsville MSFC moved the completed S-IC test fuel tank to its load test facility on March 6.¹⁶³ Other MSFC Saturn V activities during the month included con-

169. Saturn I second stage production

170. S-IVB Dynamics Test Stage



171. MSFC static test stand for Saturn V booster

172. Joining Apollo to SA-6


173. S-I-8, first industry-produced Saturn booster, being unloaded from barge at MSFC

169


170



171



172a.



b.



struction progress on the \$30 million static test facility in the Center's West Test Area. This Saturn V static test facility will be used to test four S-IC stages in Huntsville: one flight booster built at Michoud by Boeing, a nonflight MSFC-built stage, and the first two S-IC flight stages, both to be built by MSFC. The Center completed the Dynamic Test Stand superstructure in March.¹⁶⁴

NASA completed Saturn I second stage negotiations with Douglas Aircraft Corporation on April 17; scope changes increased the Douglas S-IV contract by \$22 million. During April the Apollo command module was mated to the spacecraft. This Apollo payload was then joined to the SA-6 vehicle at Cape Kennedy.¹⁶⁵ On April 24 the first industry-produced Saturn I booster arrived at MSFC from Michoud. The Chrysler-built S-I-8 stage went directly to MSFC's static test stand. On April 29 Douglas successfully acceptance fired the S-IV-7 stage.¹⁶⁶ During April the Center decided to make minor changes in the S-IU-9 on the basis of vibration test results. MSFC announced that the SA-10 vehicle would carry a meteoroid detection satellite as its payload. This type payload, also to be used for the SA-8 and SA-9 flights,

173




SATURN ILLUSTRATED CHRONOLOGY

will aid the investigation of hazards from meteoroid particles to both manned and unmanned spacecraft.¹⁶⁷


During a Saturn IB procurement discussion early in April, NASA and MSFC discussed the problem of orbital debris. NASA inquired about the possibility of controlled reentry of the S-IVB stage. Marshall feared a critical loss of load capability if the S-IVB were redesigned to provide this, but study of the problem continued. Early in April Douglas completed the S-IVB structural test stage at Huntington Beach. On April 14 the forward dome of the dynamics test stage for Saturn IB second stages was damaged during production proof testing of the propellant tank assembly. At Michoud during April, Chrysler progressed in the fabrication and assembly of the S-IB-1, the booster stage for SA-201, the first Saturn IB flight vehicle.¹⁶⁸ Chrysler technicians were putting together two major structural assemblies, the second stage adapter and the thrust structure, for the S-IB-1.

Early in April MSFC negotiated with Radio Corporation of America (RCA) for 19 ground computer systems to be used in checkout, static test, and launching of Saturn IB and Saturn V vehicles. Cost of these systems and seven ordered last year will total more than \$47 million. They will be used at Michoud, Mississippi Test Operations, and Cape Kennedy Launch Complexes 34, 37, and 39.¹⁶⁹ NASA completed instrument unit arrangements for Saturn IB and Saturn V during April. Under a prime contract effective May 1, IBM became lead contractor for work which, together with previous instrument unit assignments to IBM, is expected to cost \$175 million over a five-year period.¹⁷⁰ NASA delegated management of this work to MSFC. Meanwhile, Army engineers requested bids for an MSFC facility to study noise characteristics and sonic environment data independent of full-scale firings. Saturn IB and V upper stage engine production and testing continued at Rocketdyne's Canoga Park and Santa Susana sites. Rocketdyne delivered the first J-2 production

174



175



174. Mockup of instrument unit for Saturn IB and Saturn V

175. First J-2 production engine delivered to Douglas


engine to Douglas for the S-IVB battleship during April.¹⁷¹

Saturn V booster facilities in Huntsville continued to expand during April. MSFC awarded a con-

SATURN ILLUSTRATED CHRONOLOGY


tract worth more than \$2½ million to Sullivan, Long, and Hagerty of Birmingham, Alabama, for a 100-foot-high hangar to house large components of this S-IC stage. NASA provided almost \$6 million additional support for the S-IC booster program at Michoud in a contract supplement awarded the Boeing Company for additional research, quality assurance, and mission planning. At Downey, California, S&ID completed fabrication of two giant bulkheads for the Saturn V second stage (S-II). NASA also modified S&ID's contract in April, adding more than \$12 million to provide for vertical checkout of the S-II stages at Seal Beach and at Mississippi Test Operations. The Center studied ground support equipment (GSE) needs for Saturn V. On April 22 MSFC held a conference on electrical support equipment (ESE) to be furnished by General Electric. MSFC personnel prepared a preliminary schedule of Saturn V GSE deliveries and installation.

176



176 Moving Saturn V booster tank bulkhead at Michoud

177



177. Sixth Saturn I flight

Early in May stress corrosion was discovered in aluminum tube assemblies in the S-IV-6 stage. These were replaced without delay to the SA-6 flight. However, minor problems in fueling the S-IV-6 stage caused a six-day launch delay and GSE compressor trouble held up the flight two days.¹⁷²

MSFC negotiated with Douglas on May 19 for Saturn IB ground support equipment and additional Saturn IB second stages. On May 27 MSFC and Douglas personnel agreed on a Douglas program of computer reporting for MSFC on S-IVB/IB status.


On May 4 Saturn V personnel met in Washington to consider the Apollo reliability and quality assurance program. During the month MSFC completed a plan for integrating computer information from Saturn V systems, stages, and projects. MSFC and Manned Spacecraft Center continued Saturn/Apollo interface study in meetings during May.

The sixth Saturn I flight occurred on May 28. The SA-6 flight was successful, as all preceding flights had been. The vehicle's guidance system, active in this flight for the first time, corrected a deviation from the planned trajectory caused by premature shutdown of one of the engines. The payload, 37,300 pounds and slightly lighter than that of the record SA-5 load, included a boilerplate Apollo spacecraft which reentered the atmosphere and disintegrated as expected after 3.3 days and 50 orbits of the earth.¹⁷³ On the day this flight took place, MSFC started the seventh flight booster and instrument unit on the water voyage to Cape Kennedy.

At the end of May 1964 four Saturn I flights remained. Fabrication of stages for the Saturn IB was under way. Saturn V, the launch vehicle for the Apollo mission, began to emerge. Ground test stages were taking form, and huge facilities that would test them were rising at MSFC,

SATURN ILLUSTRATED CHRONOLOGY

178 a.




Michoud, Mississippi Test Operations, and contractors' sites.


During June MSFC, KSC, Manned Spacecraft Center, and associated contractors evaluated the sixth Saturn I flight. Included in their data were films from eight onboard movie cameras recovered after the flight and nearly 1200 performance measurements telemetered to ground stations during the flight. Analysis affirmed success of the onboard guidance system, severely tested by unexpected shutdown of one of the first stage engines. This ST-124 guidance system became active shortly after second stage ignition and corrected trajectory deviation. After the SA-6 review NASA decided to lighten the S-IV stage on the four remaining flights by reducing fuel reserve.¹⁷⁴

Other Saturn I activity in June included arrival of SA-7 payload and vehicle major components at Cape Kennedy;¹⁷⁵ MSFC's successful ground firing

b.



c.




179




178. Saturn IB and Saturn V progress at time of sixth Saturn I flight; a. LOX tank assembly for S-IVB stage, upper stage for Saturn IB and V, b. first Saturn V second stage, S-II, flight hardware, c. Saturn V booster full scale mockup at Michoud
179. On-board camera photograph of SA-6 stage separation

180



181




180. ST-124 guidance stable platform
181. H-1 engine, uprated for Saturn IB booster
182. Saturn IB second stages, S-IVB, in Douglas tooling tower, Huntington Beach

of S-I-8, the first booster produced by private industry; and start of assembly of S-IU-8, instrument unit for the SA-8 vehicle.¹⁷⁶

NASA's middle-sized Saturn, Saturn IB, progressed during June to beginning of manufacture of the first flight booster. By mid-June North American Aviation-Rocketdyne had delivered the first four uprated 200,000-pound thrust H-1 engines to Michoud for the Saturn IB booster.¹⁷⁷

Chrysler began clustering tanks of the first flight booster, S-IB-1, during June.¹⁷⁸ Douglas continued work at Huntington Beach on the Saturn IB second stages and progressed with assembly of a facilities checkout stage. Instrumentation problems delayed cold flow tests on the second stage propulsion test stage, the S-IVB battleship, but Douglas reported successful checkout of the S-IVB structural test stage before testing. A ground support equipment development highlight at Huntington Beach was successful checkout of second stage prototype automatic test equipment.

182



SATURN ILLUSTRATED CHRONOLOGY

With Saturn V manufacture continuing, NASA announced during June that it would study the feasibility of increasing the weight-lifting capacity of the vehicle by more than one-third. MSFC sought proposals on which to base contracts for preliminary studies expected to cost about \$2 million.¹⁷⁹


In early July MSFC completed the last phase of the Saturn I dynamic test program with successful tests of the SA-8, 9, and 10 vehicle configuration. MSFC's Saturn I dynamic test stand would now be one of the complex of MSFC Saturn IB and Saturn V test stands.

183 a.




183. Fabrication of Saturn V; a. fuel and LOX tanks being built in Huntsville, for the Saturn V first stage, S-IC, b. structural test stage thrust unit at Seal Beach, for the Saturn V second stage, S-II


b.



184



185



184. Aerial view of MSFC
Saturn test stands
185. S-IU-9 checkout

Preparation for the seventh Saturn I flight included installation of a nonpropulsive propellant tank venting system in the second stage to reduce tumbling of the vehicle's payload in orbit.¹⁸⁰ Also, following discovery of "stress corrosion" cracks,

SATURN ILLUSTRATED CHRONOLOGY

all eight engines were removed from the SA-7 vehicle's first stage and sent back to Rocketdyne where aluminum alloy domes were substituted.¹⁸¹

The final three Saturn I vehicles neared completion. Douglas employees at Santa Monica finished inspecting the S-IV-8 stage before its delivery to SACTO for static test. Chrysler personnel at Michoud completed pre-static checkout of the final Saturn I Booster, S-I-10.¹⁸² Meanwhile, MSFC personnel at Huntsville conducted checkout of instrument unit, S-IU-9.¹⁸³ Besides these events in July, NASA amended its S-IV stage contract with Douglas to add research and development work valued at more than \$21 million.

By mid-July Chrysler at Michoud had clustered all tanks for the first Saturn IB booster, S-IB-1, and by the end of the month installed all eight up-rated H-1 engines.¹⁸⁴ Chrysler worked on the second booster (S-IB-2) components and began the

186

186. Chrysler personnel working on S-IB-2 thrust structure at Michoud




JULY 1964

third booster. Chrysler personnel also began converting the Saturn I dynamic test booster to a Saturn IV dynamic test stage. After dynamic tests this stage will be used to check out Kennedy Space Center Saturn IB launch facilities. This modified stage was designated S-IB-D/F.¹⁸⁵ Meanwhile, Douglas second stage (S-IVB) progress during July included insulating the dynamic test stage, rework on the battleship stage, and hydrostatic testing for leaks in the liquid hydrogen tank of the structural test stage.¹⁸⁶ Douglas continued work on ground support equipment.

Saturn V booster production at Michoud was several weeks behind schedule in July; parts shortages

187. Douglas personnel
working on ground support
equipment at Huntington
Beach

187




SATURN ILLUSTRATED CHRONOLOGY

accounted for some of the delay. Third stage problems included rupture of the S-IVB hydrostatic test stage because of two faulty weld repairs; tests were considered complete, however, because sufficient information had been obtained.

The first of two test stands for the Saturn V second stage (S-II) was completed by North American Aviation at its Santa Susana Field Laboratory in July. On July 11 Douglas delivered its first Saturn V third stage test hardware to Huntsville. Flown from Long Beach, California, this S-IVB stage forward skirt would connect the top of that stage to the vehicle instrument unit.

Saturn V contract action included addition of over \$22 million to Rocketdyne's F-1 engine contract for acceleration of combustion stability research and a variety of hardware and services, a \$3.6 million J-2 facility contract to Rocketdyne, a

188




188 First Saturn V hardware from Douglas

189 Blockhouse activity at SACTO during S-IV-9 acceptance firing

190 SA-7 rises

189



launch vehicle computer contract with IBM, and two contracts for more than \$2 million each to Douglas for S-IVB rocket stage items and S-IVB automatic checkout equipment, respectively. On July 13 Army's Corps of Engineers of Mobile, Alabama, acting as NASA's agent for Mississippi Test Operations construction, awarded a contract worth more than \$17 million for construction of the first test position on the giant S-IC dual test stand.


On August 6 at Sacramento Douglas personnel successfully acceptance fired S-IV-9, second stage of the SA-9 flight vehicle.¹⁸⁷ During August the Fairchild Hiller Corporation continued work on meteoroid detection satellites to be orbited by the last three Saturn I vehicles. Each satellite, soon after second stage separation and orbit, would extend its wings to a span of 96 feet. During the month NASA named the satellites "Pegasus" after the winged horse of ancient mythology. Problems with their development threatened the schedule of the last three Saturn I launches.¹⁸⁸

NASA launched its seventh Saturn I from Cape Kennedy on September 18. The two-stage rocket placed approximately 37,000 pounds of payload into an orbit similar to the interim orbit for future three-man Apollo lunar missions (145-mile apogee, 112-mile perigee). Boilerplate Apollo spacecraft command and service modules, instrument unit, and the spent S-IV stage comprised the satellite. All major test objectives were met: final development testing of Saturn I propulsion, structural, guidance, and flight control systems; development testing of Apollo spacecraft structure and design; demonstration of physical compatibility of launch vehicle and spacecraft; and test-jettisoning of spacecraft launch escape system. Cameras ejected after the flight were abandoned because of Hurricane Gladys, but some were later unexpectedly recovered. After this flight Saturn I was declared operational, achieving its goal three vehicles early.¹⁸⁹

SATURN ILLUSTRATED CHRONOLGY

Saturn IB accomplishments by late September included MSFC's strengthening of the structure and start of component assembly for S-IU-200V, a nonflight Saturn IB instrument unit. At Michoud, Chrysler personnel were modifying flight tail section, and other Saturn I test stage components, with a new spider beam. Douglas had completed propellant loading in an S-IVB propulsion test stage, the S-IVB battleship. A Saturn IB program assessment had caused MSFC to extend the test period for this stage and to terminate the all-systems test program. The S-IVB all-systems test stage became a facilities checkout stage. MSFC was reviewing the S-IVB battleship test program on a daily basis, having found that problems with propulsion testing were affecting the Saturn IB second stage development schedule.¹⁹⁰

Progress on both Saturn V engines was substantial by the end of September. MSFC had conducted a number of F-1 firing tests, and Rocketdyne was testing F-1 engine systems at Edwards. Four J-2 engines had been tested, accepted, and delivered to stage contractors.¹⁹¹



191



191. Saturn IB nonflight instrument unit

192. Clustering Saturn IB Dynamic Test stage at Michoud

193. S-IB tail section

194. S-IB spider beam


193




194



195a.



b.




195. Saturn engine manufacturing by Rocketdyne at Canoga Park; a. J-2 engine assembly, b. F-1 furnace brazing operation, c. F-1 engine assembly

196. Bulkhead for Saturn V second stage


197. Electro-Mechanical mockup for Saturn V second stage, S-II

c.




North American Aviation-S&ID announced completion of a 33-foot-wide bulkhead for the hydrogen-powered Saturn V second stage during September.¹⁹² The Electro-Mechanical Mockup for the S-II stage was completed at Downey, California, but not fully instrumented. Douglas personnel began

196



197



SATURN ILLUSTRATED CHRONOLOGY

fabricating the first flight version of the Saturn V third stage, the S-IVB/V-1.

NASA had completed negotiations with Bendix Corporation for the Saturn V instrument unit guidance platforms by the end of the month.

On October 6 MSFC concluded three and one-half years of Saturn I first stage static testing with a test of the final booster. The 156-second test indicated that the S-I-10, manufactured by Chrysler at Michoud, was satisfactory.¹⁹³ The major units of the SA-9 vehicle went to the Cape in October, and the other two Saturn I vehicles neared completion. Development of the Pegasus satellites to be carried by the last three Saturn I vehicles proceeded. During October Fairchild Hiller Company conducted tests on a canister designed to provide power, communication, and data electronics for these meteoroid measurement satellites. An adapted Apollo spacecraft service module would protect each satellite from aerodynamic heat before its injection into orbit and operation.

Two flight booster stages for the Saturn IB were visible in the Chrysler Final Assembly Area at Michoud in October. The first, S-IB-1, was ready for inspection before ground test firing. Tank clustering of the S-IB-2 was complete and other assembly operations were under way. Also near completion was S-IB-D/F, dynamic test stage converted from Saturn I. Meanwhile, Douglas had four Saturn IB second stages under way. As these S-IVB flight stages were being manufactured, Douglas was conducting tests of the propulsion subsystems and of engine chilldown procedure before full-duration static firing of the J-2 engine-powered S-IVB battleship.¹⁹⁴

Progress on Saturn V test facilities was substantial in October. Personnel at the Rocket Engine Test Site at Edwards, California, conducted four consecutive full-duration F-1 engine test firings and approved the operational readiness of the new


198



198. Last Saturn I booster ground test


stand.¹⁹⁵ Dr. von Braun assigned operation of the site to Rocketdyne after officially accepting it on behalf of NASA. The MSFC Saturn V test complex, Mississippi Test Operations, observed its

199





199. Two of three Pegasus satellites for last Saturn I flights housed inside adapted service modules
 200. Chrysler Saturn IB booster work; a. S-IB-2, b. S-IB-1, c. S-IB-D/F, d. S-I-10
 201. Douglas S-IVB stage fabrication area

201



200






202. F-1 engine test at rocket engine test site, Edwards, California

203. Mississippi Test Operations; a. laboratory and engineering building, b. test stand for second Saturn V stage, S-II, c. test stand for first Saturn V stage, S-IC

203 a.



b.



c.



third anniversary. Mississippi Test Operations will conduct final ground firings of the two lower stages of Saturn V. Testing of the other stage, S-IVB, will occur at facilities in California. S-IVB will have been flight-proven in modified form in Saturn IB flights before its use in Saturn V.

A surprising recovery of films from the seventh Saturn I flight took place in November. Almost two months after the flight, two barnacle-encrusted capsules, each containing 100 feet of color motion-picture film in good condition, were found, one on a beach of an island in the Bahamas, the other in San Salvador in Central America. Hurricane weather had thwarted recovery efforts after the flight.¹⁹⁶


Other Saturn I activity in November included erection of the SA-9 on the launch pad at Cape

- 204. Recovered cameras
- 205. S-IV-10 being moved to stand at SACTO
- 206. Chrysler Saturn IB fabrication and assembly area at Michoud
- 207. Auxiliary propulsion system for Saturn IB second stage

204



205



207



206



Kennedy. The SA-8 vehicle, to fly after SA-9, progressed; post-static checkout of the S-I-8 stage neared completion, instrument unit checkout was under way, and the S-IV-8 stage was acceptance fired.¹⁹⁷ Stages of SA-10, the final vehicle, were manufactured; Chrysler was making minor modifications and repairs in the S-I-10 stage before post-static checkout, Douglas transferred the S-IV-10 stage to the Sacramento facility where it would be acceptance fired, and in Huntsville MSFC was assembling the S-IU-10 components on schedule. Development problems on the Pegasus satellite, payload for remaining Saturn I vehicles, were being solved, and there was considerable test activity on parts of the prototype satellite.¹⁹⁸


With the first Saturn IB booster complete, Chrysler continued manufacture and assembly of the next three during November. Technicians removed engines from the first booster, S-IB-1, and shipped them to Neosho for LOX dome retrofit. Engines would be reinstalled at Michoud before delivery of the stage to MSFC for static test. At SACTO Douglas employees test fired, for the first time, the auxiliary propulsion system for the

SATURN ILLUSTRATED CHRONOLOGY

Saturn IB second stage, S-IVB. This system consists of six 150-pound thrust engines which provide attitude control after the main engine (J-2) shuts down and the S-IVB stage enters into the coast phase of flight. In Huntsville MSFC finished assembly of a nonflight Saturn IB instrument unit, S-IU-200V. On November 24 a successful S-IVB battleship firing occurred.

NASA provided for construction of Pad B of NASA's Saturn V Complex 39 at Merritt Island, Florida, by an almost \$20 million firm-fixed-price contract awarded in November. At MSFC the first Saturn V booster stage, S-IC-T, a nonflight version, was partially assembled;¹⁹⁹ the Center used parts primarily from the Boeing Company. Douglas was checking out the S-IVB dynamics test stage, manufacturing S-IVB flight stages, and conducting propulsion systems tests. On November 24 a successful S-IVB battleship firing took place.²⁰⁰ The Saturn V second stage, S-II, activity by North American Aviation included, on November 9, a successful single engine ignition S-II battleship test, hydrostatic tests of the common bulkhead test tank which certified repairs, and buildup of

208



209



208. First Saturn V booster, a nonflight version for static tests

209. First short-duration S-IVB battleship firing

the structural test vehicle, S-II-S.


By the end of December Saturn I launch preparations at Cape Kennedy were proceeding on schedule toward the established SA-9 flight date. The S-I-8 stage was ready for shipment but would be stored for a brief period before February shipment to the Cape since SA-9 would fly ahead of SA-8.²⁰¹ Fairchild Hiller was fabricating Pegasus B. General Electric Company had finished vibration and vacuum tests on Pegasus A. On December 29 Pegasus A, the first meteoroid detection satellite, arrived at Cape Kennedy from where the SA-9 would boost it into space and orbit of the earth.

Saturn IB's first flight stage booster, S-IB-1, was in pre-static checkout in December. Chrysler was completing installations in assembled S-IB-2 units and assembling spider beam for S-IB-3. Others began assembling the S-IB-4 tail section. Meanwhile, test booster S-IB-D/F was modified,

210. Buildup of Saturn V second stage, nonflight version for tests

211. Pegasus B, folded, at left, and Pegasus prototype in space-craft integration area of Fairchild Hiller Company, Hagerstown

211



210



SATURN ILLUSTRATED CHRONOLOGY

reclustered, prepared for shipment, and on December 22 departed New Orleans for Huntsville for dynamic testing. Douglas shipped the first completed S-IVB stage, S-IVB-D, a structural replica of the flight stage, from Huntington Beach on December 8.²⁰² First and second Saturn IB stages and an Apollo spacecraft were scheduled to be united for complete vehicle tests in MSFC's 200-foot-tall Dynamic Test Stand.

During December Douglas accomplished a series of test firings of the S-IVB battleship stage at SACTO. On December 23 a full-duration (415-second) firing of the battleship occurred.²⁰³

Contract for a new Saturn V test stand was signed in December. This second S-II test stand at Mississippi Test Operations will cost over \$8 million. The U. S. Army Corps of Engineers, Mobile District, construction agent for NASA's Mississippi Test facilities, awarded the contract to Malon Construction Company of Koppers Company, Inc. In Huntsville MSFC prepared for the first single-engine firing of the Saturn V test booster S-IC-T and perfected ground support equipment. MSFC's Manufacturing Engineering Laboratory (ME Lab) manufactured and assembled the LOX bulkhead of structural test stage S-IC-S in less than a month, setting a new record for building a bulkhead.²⁰⁴

212



212. Saturn IB test first stage being readied for shipment

213. First Saturn IB test second stage, S-IVB-D, at turnover ceremony at Douglas


213



From Michoud Boeing shipped to MSFC a 33-foot-diameter S-IC stage thrust structure for structural testing.²⁰⁵ Other Boeing work included building the first Saturn V fin constructed away from Marshall Center. North American Aviation-Rocketdyne accomplished Flight Rating Tests (FRT) of the F-1 engine; five of these would power the Saturn V first stage. Saturn V second-stage accomplishments included North American Aviation-S&ID's testing of J-2 engine gimbaling on the Electro-Mechanical Mockup at Downey, California;²⁰⁶ replacement of LOX bulkhead of the S-II-S; a load and pressure test of the S-II stage; and completion of S-II battleship single engine firings. A major milestone during December was North American Aviation-Rocketdyne's completion of Preliminary Flight Rating Tests (PFRT) of the J-2 engine; five of these would power each Saturn V second stage and one would power the third stage.

Two Saturn IB test stages arrived at MSFC on January 4, 1965; the S-IB Dynamic/Facilities


214



214 S-IC-S thrust structure on barge at Michoud

215 Internal ribs of first Boeing-built Saturn V fin, assembled and ready for attachment of skins

215




SATURN ILLUSTRATED CHRONOLOGY

checkout stage, S-IB-D/F, from Chrysler Corporation's Space Division at Michoud and the S-IVB Dynamic stage, S-IVB-D, from Douglas.

On January 7, ME Lab began structural fabrication of S-IU-200S/500S.

216




216. J-2 Engine gimballing test

217. Replacement of S-II-S bulkhead

On January 13 technicians at KSC attached Pegasus A, encased in its Apollo service module shroud and adapter, to the S-IV-9 stage in preparation for scheduled launch. The following day at Launch Complex 37B technicians mated the Apollo BP-16 Command Module to the Apollo Saturn (AS-9) vehicle.²⁰⁷

At Douglas Aircraft Company's Sacramento Test Center on January 21 there was a successful full-duration static firing for 480 seconds of the Saturn I S-IV-10 stage. On this same date the S-IB stage contractor, Chrysler, began clustering propellant tanks for the S-IB-3 at the Michoud Facility and, at MSFC, ME technicians completed assembly of the S-IU-10 and structural fabrication of S-IU-200D/500D and began component assembly on the latter.²⁰⁸

217




MSFC completed negotiations with Douglas on January 28 for the remaining eight S-IVB/IB stages and a set of ground support equipment. Another Saturn IB milestone on this date occurred when KSC awarded R. E. Clarson, Inc., a \$2,179,000 contract for Phase II modification of the Launch Complex 34 service structure to support Saturn IB launches.²⁰⁹

Workmen at Seal Beach, California, on January 31 completed assembly of the S-II-S stage five days ahead of schedule.

- 218. Saturn stages in route to MSFC by barge
- 219. Pegasus with wings fully extended
- 220. Assembly of S-IU-200D/500D for the Saturn IB and Saturn V


219



218



220



MSFC on February 1 completed component assembly of the instrument unit, S-IU-200D/500D, for the Saturn IB and Saturn V dynamic tests. NASA began February of 1965 with several Saturn milestones. On February 19 the space agency amended Chrysler's S-I/S-IB contract (NAS8-4016) to include prelaunch checkout support, an amendment that added about \$34,642,878 to the contract cost.²¹⁰ Also in the Saturn program, effective this date, MSFC announced the following major revisions in the S-II stage program: cancellation of the dynamic test stage, S-II-D; substitution of the structural test stage, S-II-S, as a dynamic stage; transfer of the all-systems test stage, S-II-T, from Santa Susana to Mississippi Test Operations; assignment of the facilities checkout stage,

SATURN ILLUSTRATED CHRONOLOGY

S-II-F, directly to KSC; and scheduling of an end to the Electro-Mechanical Mockup test program.²¹¹


On February 2 Chrysler at Michoud completed pre-static checkout of the first flight S-IV stage, S-IB-1, and began preparations for shipping it to MSFC for static tests.²¹² Across the country in the Saturn V program North American Aviation's S&ID began transfer of the S-II-S stage from the vertical assembly building at Seal Beach to the structural test tower, a task completed on February 3.²¹³ On this same date ME technicians prepared the S-IU-8 for shipment to KSC.

Workmen at Seal Beach completed on February 5 the S-II-S stage, first ground test stage in the Saturn S-II stage program.

The Mobile District, U. S. Army Corps of Engineers, awarded a \$4.3 million contract February 8 covering construction of the S-II stage Service and Vertical Checkout Building and the Cryogenic

221

221. Cryogenics dock at MTO after completion



Barge Service Building at Mississippi Test Operations.²¹⁴ On this same date S-IU-200F/500F component assembly began at MSFC. Also technicians completed structural fabrication of S-IU-200S/500S.


Douglas completed final assembly of the S-IVB facilities checkout stage, S-IVB-500F, on February 12 and turned the stage over to NASA at Seal Beach. Workmen then loaded it aboard the NASA barge Orion for transportation to SACTO.²¹⁵ At KSC technicians completed the countdown demonstration test for SA-9.

With launch only two days off, MSFC and Fairchild-Hiller Corporation technicians at KSC modified Pegasus A on February 14 so that one frame or logic group of the wind panels could serve as a detector for radiation-induced meteoroids.²¹⁶


On February 16 NASA launched from KSC the Saturn I SA-9 vehicle. It performed excellently during the flight and placed the Apollo boilerplate spacecraft, BP-16, and the first Pegasus satellite into separate orbits. The Pegasus A satel-

- 222. Meteoroid measurement capsule
- 223. SA-9 launch at Kennedy Space Center

223



222



SATURN ILLUSTRATED CHRONOLOGY

lite deployed its "wings" to a span of 96 feet and exposed 2300 square feet of instrumented surface to gather meteoroid data, sort the information, and transmit it to earth receiving stations. NASA launched SA-9 instead of SA-8 on this date because SA-9's S-I stage, built in-house, had progressed through manufacture and testing more rapidly than had S-I-8. ²¹⁷

The S-IVB-500F arrived at SACTO February 17 and installation began in Beta III test stand. On February 19 MSFC ME Lab began structural fabrication of S-IU-500FS.


Douglas shipped S-IV-8 to KSC from SACTO on February 23. ²¹⁸ Also on this date Douglas personnel completed post-static checkout and repair of the S-IV-10 stage and removed the stage from Test Stand Beta II at SACTO. The following day Douglas initiated pre-static checkout of the first flight S-IVB stage, S-IVB-201, at the Space Systems Center at Huntington Beach. ²¹⁹

On February 28 the first industry-produced Saturn I first stage, S-I-8, arrived at KSC from Michoud. ²²⁰

During February fabrication of major structural subassemblies for S-II-1 had begun at Seal Beach. Also during February NASA modified the H-1 engine research and development contract to include uprating the H-1 from 188,000 pounds thrust (188K) to 200K for Saturn IB application. NASA approved modifications to the Rocketdyne H-1 engine production contract converting it from cost-plus-fixed-fee (CPFF) to cost-plus-incentive-fee. (CPIF). ²²¹

On March 1, 1965, workmen ahead of schedule moved the S-IC-T out of MSFC's ME Lab and on to the static test stand where they erected it in the stand. The following day MSFC shipped the instrument unit for SA-8 (S-IU-8) to KSC while technicians erected the S-I-8 stage on Launch Complex 37B at the Cape.


224



225



226




224. S-II-1 thrust structure fabrication at Tulsa

225. S-IC-T en route from ME lab to test stand


226. Erection of S-IC-T in test stand at MSFC

227. Saturn IB Booster being moved into static test stand
228. Positioning S-IV on S-I at KSC

227



228



The S-IB-1 stage left Michoud aboard the barge Palaemon for MSFC on March 6. Eight days later the stage arrived at MSFC. Meanwhile, on March 10, ME Lab technicians completed component assembly and structural modification of S-IU-200S/500S.

On March 15 Chrysler technicians placed the S-IB-1 into a static test stand at the MSFC complex in Huntsville, and began readying the stage for static firing.²²² This same date the S-IU-200S/500S arrived at MSFC's structural test facility.

KSC technicians at Launch Complex 37B on March 17 erected the S-IV-8 stage and the S-IU-8 atop the S-I-8 stage and began a series of systems tests including radio frequency checks, tanking procedures, and simulated flights.²²³

Technicians at Michoud on March 24 installed the S-IC-D thrust structure in the vertical assembly building.

On March 26 NASA and Boeing signed a supplemental agreement incorporating a new Saturn V delivery schedule called Plan VIII.

At MSFC, on March 29, S-IU-500V structural fabrication began. The following day S-IU-500FS component assembly began. NASA on March 31 approved award of the Saturn IB/V instrument unit contract to IBM. This contract (NAS8-1400) was the first major incentive contract to be negotiated in the Saturn IB program.²²⁴


In March NASA delineated specific management roles for the Saturn IB/Centaur System to MSFC and Lewis Research Center. MSFC received project management for the Saturn IB/Centaur System and Lewis management of the Centaur System.

In the Saturn IB program on April 1 the S-IB-1 performed successfully in its first static firing,

SATURN ILLUSTRATED CHRONOLOGY

with engine cutoff initiated by the control operator after 35 seconds. Also on April 1 in the IB program NASA authorized Rocketdyne to increase the 200K H-1 engine to 205K to support Saturn IB application to even larger missions.²²⁵

229




229. Saturn IB/Centaur Configuration; a. payload, b. Third Stage (Centaur) diameter 10 feet (without shroud), c. instrument unit diameter 21.7 feet, d. second stage (S-IVB) diameter 21.7 feet, e. first stage (S-IB) diameter 21.4 feet


230. Static firing of S-IB-1 at MSFC

On April 7 Major General Samuel C. Phillips, Director, Apollo Program, NASA, forwarded to MSFC an amendment to the FY 65 Research and Development Appropriations. This authorized transfer of \$5 million to the Saturn IB Program

230



231




231. Static test of all five engines of Saturn V booster (S-IC-stage)

for Saturn IB/Centaur design effort.²²⁶

The first single-engine S-IC-T firing occurred at MSFC on April 9.

Apollo Spacecraft BP-26 arrived at KSC on April 10 and entered receiving inspection. Also on this date MSFC successfully test fired a single F-1 engine on the stage for 16.73 seconds. Three days later Chrysler test personnel successfully static fired the S-IB-1 stage the second time at MSFC; the test lasted 142 seconds. The next day, April 16, Marshall personnel successfully test fired all five of the S-IC-T stage's F-1 engines. This first



S-IC-T five-engine test occurred two months ahead of schedule and lasted 6.5 seconds.²²⁷

On April 20 workmen loaded the S-IB-1 stage on board the Palaemon for its return trip to Michoud to undergo post-static checkout and modification.²²⁸

Pegasus B, second of the micrometeoroid detection satellites, arrived at KSC on April 21 to be readied for launch.

MSFC on April 22 began negotiating with Chrysler for an equitable adjustment to contract NAS8-4016. This resulted from NASA program redirection and termination of six S-I stages. Negotiations would continue throughout 1965.

On April 24 the S-IB-1 arrived at Michoud from MSFC where it had undergone static tests. On this same date, at Santa Susana, S&ID conducted the first five-engine ignition test of the S-II battleship.²²⁹

MSFC on April 29 completed assembly of the S-IU-200F/500F.

The S-IVB contractor loaded the first flight S-IVB stage aboard the NASA barge Orion on April 30 for shipment to SACTO. Also on April 30, during the final test of S-II-S at Seal Beach, a failure occurred that seriously damaged the stage.²³⁰


232. Deployment sequence of the Pegasus

233. S-IVB-201 enroute to Courtland, California, aboard the Orion

233



234



234. S-IVB Production Sequence


S&ID activity during April included installation and checkout of Electro-Mechanical Mockup systems, beginning vertical assembly of S-II-F, and the first test to ultimate load on the S-II-S/D. In April also, NASA modified a Boeing contract to provide engineering services and instrumentation for the Saturn V dynamic test program.

On May 4 the S-IVB battleship stage successfully performed a hot-gimbal, full-duration firing at SACTO to conclude the Saturn IB battleship hot-firing test phase.²³¹ The following day S-IVB-201 arrived at Courtland, California, aboard the barge Orion. There workmen unloaded it and placed it on the S-IVB transporter for the remainder of its journey to SACTO. The next day, May 6, S-IVB-201 arrived at SACTO, and preparations began immediately for positioning it in the Beta III test stand.

On May 7 at Santa Susana there was a successful 10-second cluster firing of the S-II battleship after two previous unsuccessful attempts.²³²

Douglas on May 10 delivered the tenth and last Saturn I S-IV stage (S-IV-10) to KSC aboard the Pregnant Guppy aircraft.

MSFC submitted the procurement plan for nine additional Saturn V S-IVB stages to the NASA



235. S-II stage
236. Launch of SA-1 from pad 37B at KSC

Office of Manned Space Flight (OMSF) on May 17 for approval.

Final period of countdown for the SA-8 launch started on the afternoon of May 24 and, except for a scheduled 35-minute hold, continued uninterrupted to liftoff. Liftoff occurred the next day, May 25, as SA-8 flew in the ninth successful Saturn I flight. SA-8 placed in orbit Pegasus B.²³³

Workmen on May 25 successfully completed vertical assembly of the S-II-T, in progress at Seal Beach since February. On May 26, the first stage S-I-10, for the tenth and last Saturn I launch vehicle left Michoud on the barge Promise for KSC.


During May MSFC and Rocketdyne completed negotiations for conversion of the J-2 contract to an incentive type.²³⁴ Also in May S&ID structural assembly of the S-II-2 flight stage began at Seal Beach. And technicians at SACTO began conversion of the S-IVB battleship from the Saturn IB to the Saturn V configuration.

S-IU-10, final instrument unit for the Saturn I vehicles, arrived at KSC from MSFC on June 1, a day before KSC technicians erected the S-I-10 on Launch Complex 37B.

On June 8 the launch support crew at KSC erected



237



238

237. Rocketdyne technicians checking out a J-2 engine
238. Point Barrow, Carrier for S-IVB-500F Stage



the S-IV-10 atop the S-I stage on Launch Complex 37B. KSC technicians on June 9 erected the S-IU-10 on the SA-10 vehicle and began connecting umbilicals of the launch support equipment.

CCSD shipped the S-IB-2 stage on June 12 from Michoud to MSFC.

After arriving at Seal Beach from SACTO on the barge Orion, the S-IVB-500F stage on June 13 went aboard the USNS Point Barrow for its trip to KSC via the Panama Canal.

MSFC workmen completed structural assembly of S-IU-500V on June 14.²³⁵

The S-IB-2 stage arrived at MSFC's Huntsville dock on June 19 from where Chrysler and MSFC personnel moved it to the static test tower in preparation for a series of acceptance firings. The S-IU-200F/500F left MSFC on this date en route to Michoud to await reshipment to KSC. At KSC it would be used in facilities checkout of Launch Complex 34. On June 19 at SACTO test

SATURN ILLUSTRATED CHRONOLOGY


personnel attempted the first Saturn V development firing of the S-IVB battleship; the test ended after several seconds because of an automatic cutoff.²³⁶

The Apollo BP-9 service module and service module adapter, modified by MSFC to serve as a shroud for the Pegasus C experiment, arrived at KSC on June 21. Meanwhile at KSC, to avoid delay of the SA-10 launch and also delay of planned Launch Complex 37B modification, NASA shifted the launch to July 30, ahead of the Gemini 5 launch.²³⁷

In a last captive-firing condition test at MSFC S-IC-S on June 21 withstood 140 percent of the design load.²³⁸

The Fairchild-Hiller Corporation shipped the third


241




meteoroid detection satellite, Pegasus C, to KSC on June 22 aboard the Pregnant Guppy aircraft.

After investigating ways to reduce the complexity of the Saturn/Apollo onboard communications and tracking systems, MSFC on June 28 recommended and NASA approved deletion of the MISTRAM transponder and use of the more reliable AZUSA "C." Both were not required for program success.²³⁹ On this date also the S-II stage simulator became the first "space age" hardware to pass through the

239



240



239. Launch Complex 34 gantry at KSC

240. Pegasus with partial deployment of wings

241. Opening of locks at MTF

Mississippi Test Operations lock and into the site's seven and one-half mile canal system.

The Point Barrow arrived at KSC on June 29 with the S-IVB-500F. Arriving at KSC on June 29 was the last boilerplate version of the Apollo spacecraft command module. It arrived from MSFC along with the launch escape system.

During June MSFC began contracting negotiations with Rocketdyne for the 22 remaining engines needed for the 12 Saturn IB vehicles. S&ID technicians at Seal Beach began assembly of S-II-3, the third Saturn V flight stage.

A July 1 "third firing" of the Saturn IVB battleship stage (Saturn V configuration) at SACTO resulted in an explosion and fire that damaged wiring and instrumentation.²⁴⁰


On July 2 NASA at KSC awarded a \$6,745,000 construction contract to adapt Launch Complex 37 for Saturn IB. Also at KSC, following completion of premating systems checks and panel deployment checks, technicians on July 6 attached Pegasus C to the S-IU-10 instrument unit. They then positioned BP-9 as the shroud for the satellite. A July 6 Saturn V milestone occurred at Seal Beach, California, as workmen began vertical buildup of the S-II-1.²⁴¹

After a suggestion by NASA Administrator James E. Webb, the name of the Mississippi Test Operations was officially changed to Mississippi Test Facility (MTF).

A faulty signal from the engine pressure switch on July 8 automatically ended a first attempt to static fire S-IB-2 in the S-IB test stand at MSFC. The test, conducted by Chrysler personnel, lasted only three seconds. But the following day the S-IB-2 stage successfully performed a short-duration 35-second captive firing in the stand.²⁴² On July 12 component assembly of the S-IU-500ST started at ME Lab. A 27-second S-II battleship

242. S-IB static test
Huntsville

242




SATURN ILLUSTRATED CHRONOLOGY

firing occurred at Santa Susana Field Laboratory (SSFL) on July 13; this was the longest firing to date of the S-II program.²⁴³

The S-IB-2 stage successfully completed its series of static tests at MSFC with a 2.5-minute full-duration test on July 20.²⁴⁴

In the Saturn V program, on July 20 technicians at SSFL successfully accomplished a 150-second firing of the S-II battleship. The KSC launch crew successfully performed the countdown demonstration test for SA-10 on July 27. Final phase of countdown for the SA-10 launch was under way at 9:25 PM EST on July 29 and continued to liftoff without any technical holds. On July 30 SA-10, in the final flight test of the Saturn I program, performed excellently. The launch vehicle inserted its dual payload of Pegasus C and BP-9 into an orbital trajectory. This SA-10 flight concluded NASA's Saturn I program.²⁴⁵



243



244



245

243. Saturn SA-10, during countdown demonstration test

244. Launch of SA-10 from pad 37B, KSC

245. Technicians checking Rocketdyne-built J-2 engines on S-II stage

The second Saturn IB booster (S-IB-2) left MSFC's Huntsville port aboard the barge Palaemon on its return trip to Michoud on July 30.

A component malfunction in Pneumatic Console A at SACTO prematurely ended the first attempt to static fire S-IVB-201. But stage propellant loading and the automatic countdown sequence proceeded satisfactorily to the point of cutoff in this July 21 static firing.²⁴⁶

During July in support of the Saturn IB and V programs Rocketdyne completed the flight rating tests of the 200K J-2 engine at SSFL. Also in July, Rocketdyne initiated a development program to uprate the J-2 engine thrust capability from 200K to 230K.²⁴⁷

On August 2 MSFC personnel conducted the first successful ignition test of the MSFC S-IVB battleship. It lasted for 2.1 seconds. This first firing of the MSFC S-IVB battleship completed activation of the J-2/S-IVB test stand at MSFC.²⁴⁸

The first full-duration run of S-IC-T occurred at MSFC on August 5. The firing lasted 143.6 seconds.²⁴⁹

The S-IVB-201 stage successfully performed a full-duration firing of 452 seconds at SACTO on

246. S-IC static firing
247. Computer room during S-IVB-201 firing at Sacramento

246



247



SATURN ILLUSTRATED CHRONOLOGY

August 8. The test was computer-controlled throughout, marking the first use of a fully automatic system for performing a complete checkout, propellant loading, and static firing of a vehicle stage.²⁵⁰

On August 9 Chrysler shipped the first Saturn IB flight booster, S-IB-1, to KSC. The stage would be used in launch facilities checkout and then readied for flight.


In the Saturn V program, on August 9 S&ID at SSFL accomplished a full-duration S-II battleship cluster firing; it terminated manually after 385.6 seconds.²⁵¹ And the structure of the S-IU-200S/500S on August 13 withstood 140 percent load limit at MSFC, proving its structural integrity.²⁵² Meanwhile, Boeing workmen at Michoud began final assembly of the S-IC-4 thrust structure.

The S-IB-1 and S-IU-200F/500F arrived at KSC on August 14 aboard the barge Promise from Michoud. This cargo was the first barged through the new Port Canaveral Locks.



248

249



248. S-II battleship cluster firing at SSFL

249. S-II A-2 test stand, Mississippi Test Facility

The first two-burn full-duration firing of the S-IVB battleship lasted 170 and 320 seconds, respectively, at SACTO on August 17.²⁵³

At KSC workmen transported the S-IB-1 stage to Launch Complex 34 and erected it on the pad on August 18. MSFC used the stage as a spacer for the S-IVB-F during propellant tankings to verify the facility LOX and liquid hydrogen loading systems. On this same day workmen also completed erection of the S-IVB-500F stage and the S-IU-200F/500F on Launch Complex 34 at KSC and began vehicle checkout of the Saturn IB launch facilities. Also on August 18 Chrysler personnel at Michoud completed pre-static checkout of S-IB-3.

Conclusion of the Saturn V S-IVB battleship test program occurred at SACTO on August 20 with a two-burn test for 170 and 360 seconds.²⁵⁴ Meanwhile, at MSFC on this date technicians completed S-IU-500V assembly and delivered it to test contractor.


On August 29 MTF operations began with installation of S-II stage simulator into Test Stand A-2 for facility checkout.

The S-IVB-202 stage arrived at SACTO from Huntington Beach on September 1. The following day Douglas technicians installed the stage on the SACTO Beta III test stand and continued stage modification not accomplished at Huntington Beach because of parts shortages and design changes.²⁵⁵ Then on September 3 Douglas transported the S-IVB-201 to the Courtland dock, loaded it on board the Orion, and shipped it to Richmond, California, where it would be loaded on the ocean freighter Steel Executive for the rest of its journey to KSC.²⁵⁶

On September 8 workmen at SACTO removed the S-IVB battleship from the Beta I stand and shipped it to Tullahoma, Tennessee, for engine environmental testing.


250. S-IVB-201 being hoisted on the Steel Executive

250



SATURN ILLUSTRATED CHRONOLOGY

251



252



251. Altitude simulation test facility at Tullahoma, Tennessee

252. Aftermath of Hurricane Betsy at Michoud


Hurricane Betsy entered the Michoud area about 8 P.M. on September 9 and left severe roof and building damage at Michoud. It also washed the NASA barge Promise upon the levee, inflicting damage to the barge in the amount of \$89,138. The NASA barge Palaemon, with the S-IB-3 stage as cargo, weathered Hurricane Betsy near Baton Rouge, Louisiana, without damage during the first day of its journey from Michoud to MSFC in Huntsville.

IBM on September 9 delivered to NASA the flight launch vehicle digital computer and launch vehicle

253



254



255



253. Damage at Michoud by
Hurricane Betsy
254. NASA barge Promise
upon levee after Hurricane
Betsy
255. Hurricane Betsy leaves
Promise on levee

SATURN ILLUSTRATED CHRONOLOGY


data adapter (LVDC/LVDA) for the SA-201 vehicle.²⁵⁷

The upper stage testing in the Saturn IB dynamic test program ended at MSFC on September 11. S-IVB battleship at MSFC fired for 400 seconds on September 15, a full-duration test.²⁵⁸ On September 16 the S-IB-3 arrived at MSFC where Chrysler test engineers would static fire the stage in MSFC's S-IB test stand before returning it to Michoud.

The S-IVB-201 arrived at KSC aboard the SS Steel Executive September 19; workmen unloaded the stage and moved it to the special assembly building for receiving inspection.

On September 29 the S-II-S/D ruptured and disintegrated during a structural loading test at Seal Beach. The failure occurred at 144 percent of limit load on the aft skirt. This failure necessitated redirection of the S-II program by substitution of the S-II-T as a dynamic test vehicle


256



256. S-II-S/D ruptured during structural loading test

257. S-IU-200/500S on fabrication stand No. 1

257



258




258. Loading S-II-T on AKD
Point Barrow
259. S-IC-T static test
firing

following static testing at MTF.²⁵⁹

Workmen at Seal Beach completed manufacture of the S-II-T stage on September 30. Meanwhile, on this date IBM at Huntsville completed fabrication of the S-IU-200S/500S-II.²⁶⁰

During September NASA added to the Boeing con-

259



tract (NAS8-5608 Schedule II) \$4.5 million to provide services in connection with systems engineering and integration of mechanical GSE.


Workmen at KSC on October 1 mated the S-IVB flight stage for AS-201 (S-IVB-201) to the S-IB-1 stage on Launch Complex 34.²⁶¹ Also on October 1 NASA approved a two-year incentive contract with Pratt & Whitney for follow-on RL10 engine research and development effective this date. The contract covered qualification of RL10-A-3-3 (uprated version) for Centaur application and continued flight support. In the Saturn V program on October 1 the S-II-T, S-II all-systems stage, left Seal Beach on the Point Barrow bound for MTF.

On October 6 workmen at Michoud completed assembly of the S-IB-4 stage, and the stage entered pre-static checkout.

The first S-IC-T firing in automatic configuration occurred at MSFC on October 8 for a scheduled

SATURN ILLUSTRATED CHRONOLOGY

260




duration of approximately 45 seconds.²⁶² On October 13 the S-IC-D arrived at MSFC's Saturn V dock after leaving Michoud dock aboard the barge Poseidon October 6, the Poseidon's first trip. Two days later technicians at MSFC began Saturn V dynamic testing of the S-IU-200D/500D.

The S-II-T, first "live" launch vehicle stage at MTF, arrived October 17 for start of stage all-systems testing. S&ID personnel at MTF placed S-II-T into Test Stand A-2 on October 19.²⁶³ The S-IU-201 arrived at KSC on October 20 aboard the Palaemon; workmen unloaded it and took it to hangar AF for prelaunch checkout. Five days later technicians at KSC erected the S-IU-201 atop the S-IVB-201 stage on Launch Complex 34. That same day, October 25, Apollo Command Module 009, part of the payload for the AS-201 vehicle, arrived at KSC and entered checkout.

Douglas technicians on October 26 completed the S-IVB-202 pre-static firing checkout at SACTO. On this date S-IB-3 successfully performed a 2.5-minute static firing in the S-IB static test stand at MSFC in Huntsville.²⁶⁴

261



262




260 S-IC-D being unloaded from barge Poseidon

261 S-II-T arriving at S-II-A2 stand at MTF

262 Installation of S-II-T in MTF test stand A-3

263 S-IVB-202 installed in Test Stand Beta 3 at SACTO

263



264. H-1 engine

265. S-II common bulkhead test tank (CBTT)

264



265



On October 28 Rocketdyne delivered to Chrysler at Michoud the first two H-1 engines uprated from 200K to 205K. Eight of the uprated engines would add about 40,000 pounds thrust to the S-IB stage and increase the total thrust of the stage to 1,640,000 pounds.²⁶⁵

Difficulties experienced with the stage electric power system at SACTO terminated the first S-IVB-202 acceptance firing attempt on October 29.²⁶⁶ Also on October 29, the S-IVB stage contractor shipped S-IVB-203 to SACTO.

During October construction of the Launch Complex 39 pad A ended at KSC.

NASA on November 1 increased Chrysler's contract NAS8-4016 some \$18,909,000 to cover additional systems engineering. In the Saturn V program on this date the Propulsion and Vehicle Engineering (P&VE) Laboratory at MSFC began the first series of S-IU-200S/500S-II tests.

On November 2 the second S-IVB-202 acceptance firing attempt ended at SACTO after 0.41 seconds of mainstage because of a component malfunction in the J-2 engine combustion stability monitoring system.²⁶⁷ SACTO activated Test Stand Beta I on November 3 with installation of S-IVB-203.

The final scheduled test of the S-II common bulkhead test tank (CBTT) ended at Santa Susana on November 6. The CBTT was tested to 1.4 times the limit burst pressure. Completion of these tests, which verified the integrity of the common bulkhead, the liquid hydrogen tank, and the forward skirt, was a major milestone in the S-II stage program.²⁶⁸

On November 8 the Saturn IB stage S-IB-3 arrived at Michoud from Huntsville to undergo post-static checkout and modification. The next day the S-IVB-202 stage performed a long-duration (307 seconds mainstage) acceptance firing at SACTO;

SATURN ILLUSTRATED CHRONOLOGY


a malfunctioning liquid hydrogen mass sensing unit in the propellant utilization (PU) subsystem prevented completion of the test to full duration.²⁶⁹ Pre-static checkout of S-IB-4, completed at Michoud on this date, revealed no significant problems.

Workmen at Seal Beach completed all S-II-1 major subassemblies on November 25 with assembly of the aft LOX bulkhead.

There was a November 30 automatic LOX loading test of the S-IB-1 at KSC to verify the automatic LOX loading and replenish systems and the LOX drain systems. The stage withstood a LOX load of 100 percent; during the loading all stage systems functioned normally.²⁷⁰ On this date Chrysler technicians completed assembly of S-IB-5 and moved it into the checkout station for pre-static checkout.

266

266. Major components of J-2 engine



- | | |
|--|---|
| 1 OXIDIZER TURBOPUMP | 9 EXHAUST MANIFOLD |
| 2 PROPELLANT UTILIZATION VALVE | 10 ANTI-FLOOD CHECK VALVE |
| 3 HIGH-PRESSURE OXIDIZER DUCT | 11 AUXILIARY FLIGHT INSTRUMENTATION PACKAGE |
| 4 ELECTRICAL CONTROL PACKAGE | 12 CUSTOMER CONNECT LINES (ELECTRICAL) |
| 5 PRIMARY FLIGHT INSTRUMENTATION PACKAGE | 13 ACCESSORY DRIVE PAD |
| 6 HIGH-PRESSURE FUEL DUCT | 14 G _{H2} START BOTTLE |
| 7 FUEL MANIFOLD | 15 CUSTOMER CONNECT LINES (PNEUMATIC) |
| 8 THRUST CHAMBER | 16 OXIDIZER INLET DUCT |

NOVEMBER - DECEMBER 1965

In November NASA announced that the J-2 engine contract would be amended to add 48 engines. NASA in addition asked Rocketdyne to provide 52 additional J-2 engines for delivery in 1967 and 1968.²⁷¹ November also saw the completion at Seal Beach of all engine deliveries for S-II-1 and S-II-2.


On December 1 the S-IVB-202 stage successfully achieved all test objectives during its full-duration (463.8 seconds mainstage) acceptance firing at SACTO. Cutoff occurred automatically when the PU system indicated less than one percent LOX.²⁷²

MSFC and Boeing on December 3 negotiated a supplemental agreement establishing Schedule III (Saturn V launch operations support) effective December 31, 1965. In the Saturn V program on December 16, the final captive test firing of the S-IC-T in original automatic configuration occurred at MSFC.²⁷³

The S-IB-4 stage departed Michoud on December 7 aboard the NASA barge Palaemon for the MSFC test site at Huntsville. MSFC workmen on December 14 unloaded the stage from the Palaemon, moved it to the MSFC static test tower,

267. *Apollo capsule*

267



10 01332 B

SATURN ILLUSTRATED CHRONOLOGY

and completed its installation in the tower. The following day, also in the Saturn IB program, Douglas completed Phase I of the S-IVB-204 pre-static checkout and successfully performed a simulated flight test before beginning preparations for shipping the stage to SACTO.


Qualification testing of the J-2 engine at the 200K level, which began on December 2, ended successfully at SSFL on December 17.²⁷⁶

Technicians at KSC erected Apollo Spacecraft 009 atop the SA-201 launch vehicle at Launch Complex 34 on December 26. With the addition of the spacecraft the vehicle became the Apollo/Saturn 201 (AS-201).²⁷⁷

On December 29 MSFC forwarded to NASA Headquarters for approval a supplement providing for conversion of the Boeing S-IC stage contract to cost plus incentive fee; the cost-effective date of this change was July 2.

During December MSFC initiated negotiations with Rocketdyne for a combined J-2 research and development contract NAS7-190 from a CPFF to a CPIF contract. In December preliminary data from the three Pegasus flights indicated that the Saturn Apollo spacecraft structure as designed would be adequate to resist meteoroid penetration.²⁷⁸ Two F-1 turbopump explosions occurred, one at SSFL and one at Edwards.

MSFC announced on January 3, 1966, its negotiation of two nine-month study contracts to determine the feasibility of using an improved J-2 rocket engine in the S-II and S-IVB stages of the Saturn V launch vehicle: (1) a \$148,000 contract to North American Aviation, developer of the S-II stage, and (2) a \$225,000 modification to an existing contract with Douglas Aircraft Company. MSFC's Propulsion and Vehicle Engineering Laboratory was seeking to simplify the J-2 and give it and the stages it powered more flexibility.²⁷⁹



268. *Studies on reusable transport system*

On January 4 MSFC announced the awarding of seven new Saturn contracts, five of them to Saturn prime stage contractors for continuation of studies aimed at improving S-IB and Saturn V launch vehicles. North American, Boeing, and Chrysler each received one of the contracts. Douglas received two. The remaining two of the seven contracts were for continuation of engineering studies relating to a manned reusable transport system: (1) a nine-month \$237,000 contract to Lockheed Aircraft Corporation to study possibilities of developing a reusable transport system based on presently approved launch and space vehicles and (2) a six-month \$51,000 contract to Martin-Marietta Corporation for a comparison study of launch modes for reusable launch vehicles. Both contracts would be under MSFC's direction.²⁷⁴


NASA announced on January 7 the award of a \$7,837,500 contract to the Radio Corporation of

SATURN ILLUSTRATED CHRONOLOGY

269



270



269. S-II battleship firing,
Santa Susana

270. S-IC-D erected in S-IC
test stand MSFC

America, Aerospace Systems Division, Van Nuys, California, effective December 1, 1965, for logistic support of Saturn ground computer check-out systems. Under the two-year contract, managed by MSFC, RCA would provide spare parts, logistic management, maintenance support, and report services for the Saturn ground computer checkout systems. On this same date MSFC announced that the Air Force's Arnold Engineering Development Center (AEDC) near Tullahoma, Tennessee, was being expanded for test of a third stage (S-IVB battleship) of NASA's Saturn V launch vehicle.²⁷⁵


A ground-test (battleship) version of S-II, second stage of the Saturn V, was static fired at Santa Susana, for 354 seconds in a successful January 12 test of its engine-gimballing and LOX cutoff systems.

Saturn V milestones on January 13 involved the first stage and instrument unit. The S-IC-D booster went into the Dynamic Test Stand at MSFC on this date, and NASA awarded a \$4,183,066 modification to its existing Saturn V instrument unit contract with IBM's Federal Systems Division, Rockville, Maryland. The modification was for manufacturing "redundant switch selectors."

At Michoud on January 14 a Saturn V launch vehicle first stage went aboard the barge Poseidon

271. Barge Poseidon used
to move Saturn stages

271




SATURN ILLUSTRATED CHRONOLOGY

for shipment to KSC. On this same date NASA invited aerospace industries to propose definition studies of integrating experiment equipment in spacecraft that could be utilized for manned Apollo Applications missions. Two or more firms would be selected for negotiations of parallel nine-month study contracts.²⁸⁰

Workmen completed horizontal assembly of the second Saturn V first stage S-IC-2, on January 17, at MSFC's Manufacturing Engineering Laboratory,

272



272. S-IC-1 (right) and S-IC-2 (left) in transit at MSFC

273. S-IC-T removed from test stand at MSFC

273




and the stage was moved to Quality Assurance Laboratory for post-manufacturing checkout. On this date technicians completed vibration testing of General Dynamics' S-IU-500V instrument unit. The unit went from Wyle Laboratories to the Manufacturing Engineering Laboratory for disassembly.²⁸¹

Removal of the S-IC-T from the static test tower on January 20 at MSFC concluded the S-IC-T planned test program at Huntsville. MSFC moved the booster to Manufacturing Engineering building for storage and later conversion to the functional configuration of S-IC-4. NASA announced on January 20 that the hydrogen-fueled J-2 rocket engine had successfully completed a series of

qualification tests to demonstrate performance over its design operating range. These qualification tests ended when a single engine operated successfully 30 times for a total firing time of 470 seconds. This accumulated duration was approximately eight times as long as the engine would be required to operate in flight.

A full-duration (2.5-minute) test for the fourth S-IB booster (S-IB-4) occurred at MSFC's East Test Area facility on January 21. Chrysler had conducted an earlier test of the engine, but for only 35 seconds.

274



274. Moving of S-IVB-501
after post-manufacturing
checkout

275. MSFC dock activity

275



Douglas personnel at Huntington Beach ended post-manufacturing checkout of the Saturn V S-IVB-501 third stage on January 28. Structural fabrication and assembly of the S-IU-501 ended at IBM Huntsville on this date. Early in 1966 MSFC formally redesignated the S-II all-systems stage (S-II-T) as the all-systems test/dynamics test stage (S-II-T/D).²⁸²

MSFC announced on February 2 that two S-IB flight boosters were aboard barges, one en route to the


SATURN ILLUSTRATED CHRONOLOGY

Michoud Assembly Facility and the other one to the Kennedy Space Center. NASA's second Saturn IB flight booster S-IB-2 was due to arrive at KSC within a few days aboard the barge Promise. The first S-IB vehicle, AS-201, meanwhile, was awaiting launch at KSC.

Workmen at MTF completed integrated checkout of the GSE for S-II-T/D of February 3. ²⁸³

Rehearsal countdown at KSC for the S-IB/Apollo mission was delayed 24 hours on February 5 because of "minor problems and resulting crew fatigue." NASA spokesman said that it was not yet known if the delay would affect the rescheduled February 22 launching. Meanwhile the S-IB stage for AS-202 arrived at KSC via barge where it was unloaded and transported to hanger AF for receiving inspection and installation of three fins.

277



On February 14 the MSFC Quality and Reliability Assurance Laboratory completed, as scheduled, the checkout of S-IU-500FS, a ground version of the Saturn V instrument unit. ²⁸⁴

MSFC continued to emphasize testing. It announced on February 15 that the first stage of the Saturn IB launch vehicle prior to its maiden flight had been "time tested" in more than 5000 single-

276



276. AS-201 awaits launching, KSC

277. Instrument unit configuration


engine tests. In addition to these single engine tests of the H-1 rocket engines, there had been 72 vehicle tests.²⁸⁵

Technicians at MSFC successfully test-fired the S-IC-1 on February 17. The firing, lasting 40.7 seconds, met all the main test objectives.²⁸⁶

NASA's Saturn S-II facility stage (S-II-F) left Seal Beach, on February 20 for KSC aboard AKD Point Barrow. S-II-F, a nonflight version of the stage, would serve as second stage of the Saturn V facilities checkout vehicle, and would test and verify launch facilities, techniques, handling procedures, and operations. In a space hardware

278. H-1 engine
279. Transfer of S-II-F and
interstage from dock to
VAB, KSC

278



279




SATURN ILLUSTRATED CHRONOLOGY

movement on the following day, the instrument unit for the second S-IB launch vehicle (S-IU-202) arrived at KSC from MSFC aboard the Promise. A booster for this S-IB was already at the KSC launch site.


On February 24 and 25 MSFC technicians continued captive-firing tests of the first stage Saturn V launch vehicle (S-IC-1). MSFC scheduled the February 25 static firing for 125 seconds but had to terminate it after 83.2 seconds when a red-line observer received an incorrect reading from a faulty transducer. However, MSFC scientists determined that in this second static firing in two days all criteria for the second S-IC-1 static firing were met and that no additional static firings were required.²⁸⁷

After postponement on three consecutive days because of continuing bad weather, NASA on February 26 launched with its Saturn vehicle, SA-201, the Apollo Spacecraft 009 payload from KSC Launch Complex 34. The vehicle performed throughout the powered and coast phases of flight. No major system malfunctions occurred in this unmanned suborbital Apollo flight. In lifting the spacecraft, SA-201's first stage had generated 1.6 million

283



280



281




280. S-IU-202 moving to KSC

281. S-IC development test stand, Huntsville

282. AS-201 launch, KSC

283. Upgraded Saturn I launch vehicle configuration

282



pounds of thrust. After burning 2 minutes and 26 seconds, propelling the Apollo to 37 miles altitude, the booster's eight H-1 engines, fueled with kerosene and LOX, shut down and the stage separated from the S-IVB. Four seconds later, a 200,000-pound thrust S-IVB (second) stage engine, burning liquid hydrogen and liquid oxygen, ignited.²⁸⁸


On February 28 at MSFC workmen moved the S-IB-5 into a static test stand in preparation for captive firings.

MSFC shipped the S-IU-500F to KSC on March 1. On this same date assembly of the S-IVB-503 and S-IVB-504 continued at Douglas in Huntington Beach, California, and workmen began factory checkout of the S-IVB-502.²⁸⁹

NASA signed with the Boeing Company a March 4 supplemental agreement converting the Saturn V first stage (S-IC) contract from a fixed fee to an incentive fee contract. It was the first Saturn stage contract to be converted to an incentive type. At the time of this conversion the Boeing contract was valued at \$850, 114, 303.²⁹⁰ Also on March 4 the S-II-F stage and its interstage arrived at Port Canaveral, Florida.

On March 10 MSFC shipped a Saturn V instrument unit (S-IU-500FS) aboard the Super Guppy aircraft to Huntington Beach, for testing with an S-IVB stage in a simulated space environment.

284



284. S-II-F stage arrival,
KSC

285. S-IVB facilities at
Huntington Beach

285



SATURN ILLUSTRATED CHRONOLOGY


The following day the S-IVB-501 stage left Huntington Beach for Sacramento where it would undergo acceptance firing. Meanwhile at KSC workmen erected and mated the S-IVB stage and instrument unit of the AS-202.²⁹¹

Douglas Aircraft Corporation successfully conducted a March 18 acceptance test of the fourth flight Saturn S-IVB-204 stage at its Sacramento Test Center. Technicians fired the stage for about 455 seconds.²⁹²

NASA announced March 24 that it would negotiate incentive contracts with two major aerospace firms for the procurement of five additional Saturn V first stages (S-IC) and 33 F-1 rocket engines. NASA would negotiate with the Boeing Company for the stages and with Rocketdyne for the F-1 engines for these stages. The five S-IC stages would cost in excess of \$165 million. These contracts were in line with NASA's plan to launch 15 Apollo/Saturn V space vehicles by the end of 1970.²⁹³

Mating of the S-II-F with the S-IC-F stage occurred at KSC, March 28. On the following day workmen mated the S-IVB-500F with the S-II-F, and the day after they erected the S-IU-500F.


On March 30 the S-IVB-500-ST flew from California to MSFC aboard the Super Guppy.



286



287



286. S-IVB facilities at SACTO

287. F-1 engine

288. S-IVB aboard Super Guppy


288

MARCH 1966


On March 31 there were major Saturn headlines at MSFC. Chrysler Corporation personnel captive fired the S-IB-5 for about 2.5 minutes, the second and longest duration firing for the booster.²⁹⁴

289. S-IB stage erection
in test stand, Huntsville
290. J-2 production at
Rocketdyne

289



290





SATURN ILLUSTRATED CHRONOLOGY

April 1 NASA announced that project management of its first hydrogen-fueled engine, the RL10, was being transferred to Lewis Research Center at Cleveland, Ohio. A cluster of six RL10 engines had powered the Saturn I's S-IV second stage before the conclusion of MSFC's Saturn I program the previous year.

In an April 4 release NASA announced a change in sequence of the S-IB-202 and the S-IB-203 launches. Up-rated S-IB-202 was rescheduled to follow the AS-203 mission. The purpose of the sequence change was to provide additional time for checkout of Apollo spacecraft to be flown in the AS-202 mission. AS-203 was a launch vehicle development mission and would not carry an Apollo spacecraft.²⁹⁵

NASA announced on April 6 the purchase under a \$7,634,742 modification to an existing contract of 22 additional H-1 engines for the S-IB launch vehicle. In addition to the engines the contract with North American Aviation's Rocketdyne Division called for three years of support services, including training, field engineering, and supply support.

The third S-IB booster (S-IB-3) departed Michoud for KSC on April 7. The S-IB stage for AS-203 arrived at KSC via barge Promise where it was



THRUST - 15,000 LB (ALTITUDE)
THRUST DURATION - 470 SEC
SPECIFIC IMPULSE - 433 SEC
ENGINE WT DRY - 298 LB
EXIT-TO-THROAT AREA RATIO -
40 TO 1
PROPELLANTS - LOX & LH₂
PROPELLANT FLOW RATE -
35 LB SEC

CONTRACTOR -
PRATT & WHITNEY
SYSTEM - SAT I S-IV (6 ENGINES)
CENTAUR (2 ENGINES)

1-62-0 100 04-100

- 291. RL10 engine
- 292. Final check of H-1 engines before shipment
- 293. Barge Promise


292



293



294



DIMENSIONS		SPECIFICATIONS (APPROXIMATE)	
WING SPAN	136 ft 3 in	EMPTY WEIGHT	110,000 LBS
FUSELAGE LENGTH	141 ft 2 in	PAYLOAD (APPROXIMATELY)	45,000 LBS
TAIL HEIGHT	46 ft 5 in	TAKEOFF WEIGHT (MAXIMUM)	175,000 LBS
FUSELAGE HEIGHT	36 ft 6 in	CRUISE SPEED	250 MPH
CARGO COMP (DIAMETER)	300 in		
CARGO COMP LENGTH	94 ft 6 in		
LENGTH CARGO COMP 25 ft DIA	30 ft 8 in		IND 820258

unloaded and moved into hangar AF on April 12. Six days later workmen erected the S-IB stage on Launch Complex 37B. Meanwhile, MSFC loaded the S-IB instrument unit for AS-203 aboard the Super Guppy for flight to KSC. As preparations continued for erecting AS-203, KSC technicians continued propellant tests of the nearby AS-202.


From April 19 to April 21 nine NASA astronauts visited MSFC for briefings on the S-IB-1 launch vehicles to be used in the initial manned Apollo missions. Briefing areas included tours, hardware descriptions, and design philosophy.²⁹⁶

MSFC announced on April 21 that NASA had awarded \$50,000 60-day fixed-price contracts to Douglas Aircraft Company, McDonnell Aircraft Corporation, and Grumman Aircraft Engineering Corporation to perform definition and preliminary design studies and evaluate a plan to make spent Saturn V S-IVB stage hydrogen tanks habitable for manned space missions up to 30 days in duration. MSFC would manage the contracts.²⁹⁷

On April 23 workmen at MTF successfully captive-fired for 15 seconds S-II-T, the Saturn V second stage all-systems test vehicle. This was the first test of a flight-weight S-II stage. The stage, largest and most powerful liquid oxygen-liquid hydrogen stage known, developed one million

294 Super Guppy
295. S-IVB stage hydrogen tanks
296. S-IVB stage in Test Stand Beta 1, SACTO

295




296



SATURN ILLUSTRATED CHRONOLOGY

297



pounds of thrust from its five J-2 engines. This test also marked the first operational use of MTF.

MSFC announced on May 6 that the first uprated J-2 rocket engine had arrived at MSFC from Rocketdyne. Inuprating the J-2, Rocketdyne had increased the thrust for a new thrust capability of 230,000 pounds. NASA schedules called for use of the higher thrust J-2 in the second stage of the S-IB, beginning with vehicle AS-208 and, in the second and third stages of the Saturn V, beginning with vehicle AS-504.²⁹⁸

Technicians at SACTO Test Stand Beta 1 completed the S-IVB-501 integrated systems checkout on May 9.²⁹⁹

Helium-bottle trouble on May 10 resulted in termination of the second S-II-T firing at MTF. The following day, in a second attempt to complete a static firing of the S-II-T, the engine fired about 47 seconds. Premature cutoff occurred because of a gas generator problem.

A 154-second static firing of S-II-T, the all-systems version of Saturn V's second stage, occurred at MTF on May 17. This was a successful test of the nation's most powerful hydrogen-oxygen engine. Technicians made 1100 measurements and gimballed four of the five engines. These engines in flight would provide stability and control of the stage.³⁰⁰

297. S-II-T static firing at MTF

298. First duration firing of an S-II flight stage

299. Saturn V in movement at KSC

298



299



On May 19 MSFC announced the following nomenclature changes as recommended by NASA Headquarters Officials, Dr. Seamans, Dr. Mueller, and Mr. Scheer:


"Lunar Excursion Module to be called Lunar Module; the Saturn IB to become 'the Uprated Saturn I.' At first the changes will be noted as 'the Uprated Saturn, the Saturn IB' gradually dropping reference to the Saturn IB as the new name becomes more familiar. This would enable us to continue the string of Saturn I successes. Realistically the Uprated Saturn I is what we have anyway; in general public releases we should begin referring to Saturn stages simply as the first, second, or third stages, and, where helpful, to semi-technical press and in press kits follow with the technical nomenclature, i. e., 'the third stage of the Saturn V (S-IVB),' etc.; future releases and announcement should make use of the new nomenclature."

The first full-duration firing of the S-II flight stage occurred May 20 at MTF when S-II-T test-fired for 354.5 seconds. LOX cutoff sensors initiated cutoff automatically. The firing passed all major test objectives with the exception of the propellant utilization system. This was the fourth static firing of the S-II-T. The stage developed one million pounds of thrust from its five hydrogen-oxygen-powered J-2 engines.³⁰¹

"Rollout" of the SA-500F occurred at KSC May 25. The 500,000-pound facility test vehicle, 365 feet long, moved from the Vehicle Assembly Building (VAB) on its 3000-ton diesel-powered steel-link crawler transporter to Pad A to verify launch facilities, train launch crews, and develop test checkout procedures. Also on May 25 technicians at MTF attempted the second full-duration firing of the S-II-T but terminated the firing after 198 seconds as a result of fire on engine No. 5. The fire burned an electrical cable to cause the cutoff. This was the fifth static firing of the S-II-T.³⁰²

SATURN ILLUSTRATED CHRONOLOGY

300



300 S-IVB-302 acceptance
firing at SACTO

On May 26 at Sacramento Beta 1 test stand there was a second successful firing of S-IVB-501. This test of S-IVB-501 consisted of a 151-second mainstage first burn, a 106-minute simulated orbital coast period, and a 301-second mainstage burn after restart.³⁰³

NASA announced on May 27 the selection of two firms for negotiations of parallel one-year study contracts for integration of experiments and experiments support equipment in space vehicles and spacecraft involving manned Apollo Applications missions. Estimated value of each contract was approximately \$1 million.


A static test version of the Saturn V second stage S-II-T ruptured during pressure tests at MTF on May 28, and five North American Aviation technicians monitoring the test received minor injuries. The accident occurred when the hydrogen fuel tank of the one-million-pound thrust stage failed under pressure. S-II-T, which had five hydrogen-oxygen J-2 engines capable of generating one million pounds of thrust, had been tested

301. Destroyed S-II-T/D
due to overpressurized
liquid hydrogen tank
302. Loading sequence of
Super Guppy
303. Saturn V and mobile
launcher on crawler emerg-
ing from VAB, KSC


301



302



303



May 25 in ground firing but stopped firing after 195 seconds when a hydrogen leak caused automatic cutoff. At time of the explosion, technicians were trying to determine cause for the hydrogen leak. No hydrogen was in the tank when the explosion occurred. Under the direction of MSFC, a Board of Inquiry headed by Dr. Kurt H. Debus, Director of Kennedy Space Center, convened on the night of May 28. Immediate investigation revealed that the second shift crew, not knowing that the liquid hydrogen pressure sensors and switches had been disconnected, had attempted to pressurize the tank. Believing that a liquid hydrogen vent valve was leaking, the technicians closed the facility by blocking valves. This had caused the vehicle tank to become over-pressurized and burst.³⁰⁴

On May 30 the board released its findings after two days of inquiry. The fuel tank of the S-II stage had been pressurized beyond design limits. There was a need for tighter controls over MTF test procedure.

On June 1 the Saturn V third stage (S-IVB-502) flew aboard the Super Guppy aircraft from the Huntington Beach to SACTO for static testing. A 33,000-pound stage, 59 feet long and 21.5 feet in diameter, this was the second Saturn V upper stage to arrive at the Douglas test site.

At Redstone Arsenal MSFC successfully static fired the second S-IC stage (S-IC-2) of the flight Saturn V launch vehicle for 126.3 seconds and recorded 1200 measurements of the stage's performance. The five F-1 engines, four of which were gimbaled during this June 7 test, generated 7.5 million pounds of thrust.³⁰⁵

Because Hurricane Alma approached Kennedy Space Center on June 8, it was necessary to interrupt the processing and test activities of SA-500F and move the vehicle back to the VAB. The hurricane threat passed, and two days later the vehicle was again back on Pad A.³⁰⁶

SATURN ILLUSTRATED CHRONOLOGY

On June 27 NASA announced the conversion of its contract with Douglas Aircraft Company for development of the Saturn's S-IVB stage to a CPIF agreement. Under the revised contract, the company's fee would be increased or decreased depending upon attainment of the incentive for cost, schedule, and performance. The original contract was a CPFF arrangement. Estimated cost of the total effort under both portions of the contract was about \$700 million plus fee. To date about \$595 million had been funded.


On June 29 MSFC captive fired both an uprated Saturn I first stage and an F-1 engine at Redstone Arsenal. At MSFC's East Test Area technicians fired for a full duration the sixth flight Saturn booster (S-IB-6). It had previously been tested for 35 seconds on June 22. At the West Test Area MSFC technicians captive fired the F-1 engine on a first run for about 40 seconds. The S-IB, powered by eight Rocketdyne H-1 engines, produced 1.6 million pounds of thrust.³⁰⁷

Following the destruction of S-II-T during a test at MTF, NASA extended the S-II battleship program until July of 1967. Also during June there were changes in the launch schedule for the Apollo/Saturn 203 launch. Previously scheduled for June 30, NASA rescheduled it for June 29 because of the scheduled launch of a lunar-anchored interplanetary monitoring platform Explorer. But by June 29 NASA had rescheduled SA-203 launch because of electrical problems, so that it would come no earlier than July 5.

At Kennedy Space Center technicians on July 2, 1966, erected and mated the AS-202 spacecraft. Three days later the twelfth Saturn vehicle, AS-203, flew from KSC Launch Complex 37B. After one hour, 53 minutes, and 17 seconds of countdown holds, the vehicle lifted off the pad to begin the second unmanned flight of the uprated Saturn I. The vehicle's second stage (S-IVB), instrument unit, and nosecone, weighing 58,500 pounds, com-

304. AS-203 in flight, showing shock wave forming around nose cone

304



prised the heaviest U. S. satellite ever placed in orbit. Primary mission of this July 5 flight was an engineering study of liquid hydrogen fuel behavior during orbit.^{308, 309}

MSFC technicians installed the S-IC-T stage in the S-IC test stand at Redstone Arsenal on July 7. Tentative plans called for static firings, including fuel and LOX loading tests,³¹⁰


On July 8 NASA announced the award of a contract to Federal Electric Corporation (FEC) of International Telephone and Telegraph Corporation for technical support of the Saturn launch vehicle reliability program at MSFC. The cost-plus-award-fee contract would be for one year at an estimated cost of \$1.8 million, with a provision for two additional one-year periods. The FEC would perform test program analysis, failure mode and effects analysis, hardware and software failure analysis, and maintainability in human engineering analysis for MSFC's Quality and Reliability Assurance Laboratory. Most of the work would be in Huntsville.³¹¹

Acceptance firing of the S-IVB-502 stage occurred at Sacramento, California, on July 28. The captive firing, conducted by Douglas Aircraft Company, prime contractor, simulated the operation of the propulsion system during the burn portion of the flight. The stage burned 150 seconds, shut down for one and one-half hour simulated coast period, and then reignited and operated 291 seconds. Such performance would be required in lunar missions. A J-2 hydrogen-oxygen engine made by Rocketdyne Division of North American Aviation Company powered the stage.³¹²

NASA Headquarters unconditionally approved J-2 engine program contract NAS8-19 on July 29. This contract established the provision for production support effort through December 1968, and for delivery of the 155 J-2 engines required for the Apollo program. The contract combined what had been two major J-2 contracts.³¹³ Also on

SATURN ILLUSTRATED CHRONOLOGY

305



305. Acceptance firing of the S-IVB-502 at Sacramento

July 29, technicians at Seal Beach made hydrostatic tests of the S-II-3 stage for SA-503. And at Santa Susana technicians conducted a 40-second mainstage test of the S-II battleship stage. Automatic cutoff initiated from engine number 5, but data revealed that cutoff occurred erroneously.


S-II-1, the first flight S-II stage scheduled for static firing at MTF, left Seal Beach on July 31.

NASA announced on August 1 the signing of a \$339 million supplemental agreement with Chrysler Corporation's Space Division which increased the contract value by \$14 million and converted the uprated Saturn I first stage production contract from a CPFF to a CPIF contract. The contract, to continue through February 1969, would involve Chrysler's assumption of design responsibility and implementation of a total qualification and reliability testing plan. Under this contract managed by MSFC, Chrysler would manufacture, assemble, and test 12 stages.³¹⁴


MSFC announced on August 5 the award of a \$23.4

JULY 1966

306



307



306. S-II facilities at Seal Beach

307. Transfer of the S-II-1 from the Point Barrow to the Pearl River at Michoud en route to MTF from Seal Beach


SATURN ILLUSTRATED CHRONOLOGY

million modification to an existing contract with North American Aviation Space and Information Systems Division for additional work in building and testing the Saturn V launch vehicle's second stage. The contract modification included several engineering changes, many of which were already completed or under way.


NASA decided to change the Sacramento-to-KSC shipping date of the S-IVB-501 from August 2 to August 12. This would meet the KSC required date and allow additional time for closeout of all open work prior to shipment. Stage turnover to NASA came in a ceremony at Sacramento on August 9. On August 11 technicians completed installation of flight vehicle instrumentation and tank purge operations. The stage then went aboard the Super Guppy aircraft and departed Sacramento on August 12, as scheduled, arriving at KSC on August 14, after a one-day delay because of weather. At KSC the stage went into the VAB low bay where receiving inspection began immediately.³¹⁵

308


308. General view of S-IVB-501 aboard Super Guppy



309



310



309. Complex 34, Launch
KSC

310. Fourth Uprated Saturn
I, S-IB-4, in first stage of
journey to KSC

NASA announced on August 10, 1966, the rescheduling of the Apollo/Uprated Saturn I (AS-202) from August 20 to August 22. During checkout operations technicians had discovered leaks in liquid hydrogen fuel line fittings leading to the three fuel cells in the spacecraft service module. The fuel cells would supply electrical power to the spacecraft during flight. Later, NASA decided to fly the mission with the two remaining fuel cells which were capable of providing sufficient power for the one and one-half hour suborbital flight. AS-202 would fly from Launch Complex 34 at KSC.³¹⁶

The fourth Uprated Saturn I (S-IB-4), the first scheduled to launch a manned Apollo spacecraft, departed Michoud for KSC, on August 10.

SATURN ILLUSTRATED CHRONOLOGY


NASA announced on August 11 that MSFC would begin negotiations with the Chrysler Corporation and Douglas Aircraft Company for procurement of long-lead-time items for additional Up-rated Saturn I launch vehicles. Cost of the long-lead-time items was estimated at \$5 million to \$10 million.

The first flight model (S-II-1) of the Saturn V vehicle's second stage arrived August 13 at MTF completing its 4000-mile voyage from Seal Beach. Workmen immediately moved the stage into the S-II stage service and checkout building for inspection and preparation for static firing.

On August 19 NASA selected McDonnell Aircraft Corporation of St. Louis, Missouri, for negotiations toward a fixed-price contract estimated at \$9 million to provide an S-IVB airlock. The airlock would permit astronauts access to the empty hydrogen tank of spent uprated Saturn I second stages.

311



*311. S-II-1 arriving at MTF
for acceptance testing*



312


312. IU-501 arrives at KSC
aboard Supper Guppy
313. AS-202 rises from KSC
on August 25, 1966

313



A LOX line leading to the Saturn V launch pad at KSC ruptured on August 19, spilling more than 800,000 gallons of LOX. The incident occurred during the first-stage tanking test when the pipeline ruptured spilling the 800,000 gallons of LOX; vacuum created inside the tank had caused a depression in the tank's 2.5-inch-thick dome.³¹⁷

The S-IU-501 arrived at KSC on August 24. Apollo/Saturn vehicle AS-202, the third vehicle to fly in the Uprated Saturn I series, rose from Launch Complex 34 at Cape Kennedy on August 25. AS-202 was the thirteenth Saturn vehicle in a row to fly successfully through space. This was the second successful flight test of the Apollo spacecraft command and service modules before earth orbital manned missions. The flight proved the Apollo command module ablative heat shield by subjecting it to extended high heat loads during



314. S-IC-1 stage arrival,
KSC

On August 26 MSFC shipped the first Saturn V flight booster (S-IC-1), scheduled to be launched early in 1967, to the Kennedy Space Center via the barge Poseidon.

NASA announced on August 28 that the August 19 rupture of the 900,000 gallon stainless steel storage tank for the Saturn V booster's LOX would delay the booster's first flight, scheduled for the first quarter of 1967, by at least 45 days.³²⁰

MSFC announced on September 7 that four barges carrying 400,000 gallons of vitally needed liquid oxygen were en route to KSC after being dispatched from the MTF. The shipment, together with 40,000 gallons brought into KSC by truck and rail tank cars, would replenish the liquid oxygen lost on August 19 when a line ruptured below the LOX storage tank serving Saturn V's Launch Complex 39. Schedules called for propellant loading tests to resume September 20, 1966.

The S-IC-1 arrived at KSC on September 11. Chrysler personnel at the Test Laboratory in Huntsville captive fired the seventh Uprated Saturn I flight booster for its full two and one-half minute test on September 13. After this successful test, schedules called for MSFC to return the booster to Michoud for post-static test checks.

Chrysler Corporation built the stage at the New Orleans facility.³²¹

Last of the S-IVB-503 factory checkout tests occurred at Huntington Beach on September 14. The following day at MSFC's P&VE Laboratory in Huntsville technicians completed all test conditions for the S-IU-200S/500S-3 structural test unit. The final test condition for the unit was the application of a 140 percent maximum limit compression load on part of the unit.³²²

On September 23 the first Saturn V flight booster built at MAF (S-IC-3) departed aboard the barge Poseidon for MSFC to undergo static firing tests. According to plans technicians would later static-fire the boosters at MTF.³²³

MSFC announced on September 29 that it had awarded three new study contracts totalling \$400,000 to investigate the launch vehicle needs and best methods for sending manned spacecraft on planetary flyby trips; North American Aviation, Inc., received \$100,000 to study feasibility of modifying the Saturn V second stage, S-II, for use as an orbital ejection stage; Douglas Aircraft Company received \$100,000 to study the feasibility of using Saturn V third stage, S-IVB, as part of a planetary vehicle; and TRW Systems, Inc., received \$200,000 for study of alternate mission modes for manned Mars and Venus orbital and landing missions.³²⁴


315



315. S-IU-200S/500S during structural test, MSFC

316. S-IC-3 being loaded on barge Poseidon for shipment to MSFC

316



SATURN ILLUSTRATED CHRONOLOGY

After successful completion of post-manufacturing checkout at the Michoud Booster Checkout Facility, the S-IC-3 stage left Michoud on September 23 and arrived at MSFC on October 1. Unloading operations began on October 3, and on that same date workmen erected the stage in the test stand.³²⁵

The S-IVB-503 stage went from Los Alamitos to Sacramento via the Super Guppy aircraft on October 11. The stage moved to the Vertical Checkout Laboratory on October 12, and into the test stand on October 14. The SA-500F vehicle arrived at KSC on October 15.

On October 17 MSFC shipped its S-IC all-system test booster, S-IC-T, to MTF for use in checkout of a static test stand and for use in static firings. Workmen loaded the huge booster aboard the barge Poseidon for the 1000-mile river journey. Six days later the S-IC-T reached MTF. Meanwhile on October 25, after leaving Michoud a week earlier, the eighth Uprated Saturn I first stage (S-IB-8) reached the MSFC dock for static firing at MSFC by Chrysler Corporation personnel. Also at MSFC on October 25, NASA awarded the University of Wisconsin a \$679,101 contract to develop sensors for a galactic X-ray mapping experiment to be flown on an Uprated Saturn I launch vehicle in 1968. The sensors would explore X-ray sources other than the sun and Crab Nebula.

NASA announced on October 26 the award to North American Aviation of a \$37 million contract supplement for launch preparation and checkout of ten Saturn V second stages (S-II). Two days later NASA awarded a \$4.5 million contract modification calling for the Boeing Company to assume design and procurement responsibilities for certain structural components and instrumentation of Saturn V first stages built at Michoud. The components, previously provided by the Government, included propellant ducts and valves and pressurization switches and gauges.³²⁶

On November 2 KSC workmen stacked the S-IU-154

317. S-IC-3 being erected in the static test stand at MSFC


317



318




320



318. Buildup of the SA-501 vehicle using the H7-17 fit-up fixture as a spacer to replace the S-II-1 at KSC
 319. S-II-F stage being unloaded at MSFC
 320. S-IC test stand at MTF

319



501. The following day technicians at MSFC completed systems checkout of the S-IU-502.³²⁷

The S-II-F/D stage arrived at MSFC on November 10.

Technicians at MSFC successfully acceptance-fired the S-IC-3 on November 15 for 121.7 seconds mainstage. This was the last planned firing of the S-IC stage at MSFC. Future firings would be accomplished at the B-2 stand at MTF.³²⁸ On November 16 at MSFC technicians successfully static fired the eighth Up-rated Saturn I booster for 35 seconds.³²⁹

On November 17 NASA announced several Apollo/Saturn manned space flight schedule changes because of launch vehicle and spacecraft development problems. The principal change called for rescheduling a manned earth orbital mission, Apollo/Saturn 205, which was to have followed the first manned Apollo flight, AS-204.³³⁰

On November 18 NASA approved F-1 engine contract NAS8-18734 CPIF. This contract provided for 30 F-1 engines needed in the Apollo program and continued production support and GSE through June 1970. These 30 F-1 rocket engines furnished by Rocketdyne Division of North American Aviation would complete the number of engines (106) required by the 15 scheduled Saturn V vehicles, plus spares. The cost would be about \$141 million.


SATURN ILLUSTRATED CHRONOLOGY

The delivery of 30 engines would begin in November, 1967, and continue through October 1968.³³¹

On November 29 a forward bulkhead of the liquid hydrogen tank for the S-II-3 flight stage suffered damage while the stage was in the horizontal position. The damage occurred at North American Aviation's Seal Beach Plant as workmen were removing a work ladder from the tankage interior. The stage was in position when a 10-foot section of the ladder dropped, striking the forward bulkhead and causing cracks. The fall resulted from a weld failure in the ladder retracting mechanism. NASA anticipated no impact on the S-II-3 delivery date.³³²

Technicians at MSFC on November 30 static fired the eighth Up-rated Saturn I booster successfully in its second test for 145 seconds. The first stage performed as expected, developing 1.6 million pounds of thrust.³³³

At MTF on December 1 North American Aviation conducted a successful 384-second captive firing of the first flight hydrogen-fueled engines, developing a total one million pounds of thrust. During the test, number 2 and 4 engine SLAM arms did not drop, resulting in the successful gimbaling of engines 1 and 3 only. The test included the recording of about 800 measurements of the stage's




322

321



321. F-1 engine checkout
322. Cracks in the liquid hydrogen tanks for the S-II-3

323



323. Dynamic vehicle stacked in the Saturn V Dynamic Test Tower at MSFC

performance, including propellant tank temperatures, engine temperatures, propellant flow rates, and vibrations.³³⁴

Workmen at MSFC completed stacking of the SA-500D vehicle on December 3.

Factory checkout of the S-IVB-504 flight stage ended on December 9 at Huntington Beach.

On December 13 a two-stage Up-rated Saturn I launch vehicle was shipped to KSC. NASA would launch the vehicle in 1967 in an unmanned flight of the Apollo spacecraft lunar module. The booster stage, S-IB-6, for the AS-206 left Michoud near New Orleans on this date aboard the barge Palaemon. The Palaemon would deliver its cargo to KSC on December 19. The second stage, S-IVB-6, went aboard the Super Guppy aircraft at Mather Air Force Base. Douglas built the S-IVB stage, at Huntington Beach, California, and tested it at SACTO. Schedules called for the vehicle's instrument unit to fly on December 19 from MSFC to KSC aboard the Super Guppy.³³⁵

An all-systems test version of Apollo/Saturn V first stage, S-IC-T, went into the B-2 test stand at the Mississippi Test Facility on December 17. Stage electrical and mechanical hook-up to the test stand began immediately. Static firing would occur in early 1967 to demonstrate the facility checkout system.

MSFC announced on December 20 the award of a \$7.2 million contract modification to Chrysler Corporation to begin procurement of long-lead-time items for additional Up-rated Saturn first stages (S-IB). Under this agreement to be completed by June 30, 1967, Chrysler would procure the materials, components, and engineering support necessary to maintain its capability to assemble four Up-rated Saturn I boosters per year. Chrysler was currently under contract to assemble and test 12 of the 1.6 million-pound first stages at Michoud.³³⁷

SATURN ILLUSTRATED CHRONOLOGY

MSFC announced on December 28 that NASA had signed a \$6,383,720 contract modification with the missile and Space Systems Division of Douglas Aircraft Company for long-lead-time items for the upper stages of Uprated Saturn I vehicles. The contract, to be managed by MSFC, was extended through June 1967. The object of the procurement action was to maintain the option of ordering additional S-IVB stages for the Uprated Saturn I in the future, without suffering a delay in certain areas where considerable time might be required for material acquisition and/or manufacturing.

On December 30, 1966, MSFC technicians at the MTF test stand conducted a static firing of the first flight version of the Saturn V second stage, S-II-1. This second test firing, like an earlier firing, lasted more than six minutes. Normal procedure called for the stage to undergo post-static firing inspection or checkout next at the test site before being moved to KSC, but in a change of procedure MSFC began preparations at once to ship the stage to KSC for these checks. Project officials hoped to gain seven or eight days by performing much of the checkout and modification work at KSC.³³⁸


On January 5 MSFC established an S-II Special Task Team to be located at the contractor site in California and at MTF. The organization of such a team became necessary when emergence of technical difficulties resulted in the S-II stage becoming the pacing element in Saturn V development. MSFC gave this team priority to assure solving S-II technical problems so that schedule commitments could be met. The Center named Col. Sam Yarchin, S-II Stage Manager, to head this 18-man team.³³⁹

IBM began S-IU-503 checkout and systems testing on January 10.³⁴⁰

On January 11 initial post-static checkout of the S-II-1 stage ended at MTF.³⁴¹

324. S-IU-503 during installation of retro-fit kit to umbilical quick disconnect mechanism, IBM facility, Huntsville

324



DECEMBER 1966 - JANUARY 1967


A successful S-IVB-208 stage acceptance firing occurred at Sacramento on January 12. Main-stage duration was 424.3 seconds, with automatic cutoff initiated because of LOX depletion. All test objectives were achieved.³⁴²

The first flight version of a rocket stage to undergo captive firings at MTF, the S-II-1 stage, left Bay St. Louis, Mississippi, on January 16 en route to KSC, where it would become a part of the first Apollo/Saturn V flight vehicle, scheduled for launch during the second quarter of 1967.³⁴³ On this same date, MSFC announced the award to Sanders Associates, Inc. of a \$2,149,548 contract for logistic support of Saturn V operational display systems used to present information on vehicle status during simulated and actual launch preparations.³⁴⁴

On January 19 the S-IB-9 stage left the CCSD facility at MAF aboard the Palaemon barge on its trip to MSFC in Huntsville for static testing.³⁴⁵

325. S-IB-7, S-IB-9,
S-IB-5, and S-IB-6 in
final assembly area,
Michoud


325



SATURN ILLUSTRATED CHRONOLOGY

A Saturn V third stage, S-IVB-503, exploded shortly before it was scheduled to be ignited in a January 20 test at SACTO. The explosion completely destroyed the stage at Test Stand Beta III. Post-accident investigation revealed that one of the eight ambient temperature helium storage spheres located on the engine thrust structure exploded because of weld weakness resulting from use of the wrong weld material.³⁴⁶

327



At MSFC's ME Lab, technicians completed a device to adapt the S-IC Test Stand to receive stages other than the S-IC. This S-IC test stand adapter ring consisted of approximately 90,000 pounds of welded stainless steel approximately 33 feet in diameter and 6 feet in height.

The S-II-1 stage arrived on the dock at KSC on January 21. Already at KSC were the SA-501 flight vehicle sections S-IC-1, S-IVB-501, and S-IU-501.³⁴⁷ Noteworthy about the arrival of the S-II-1 stage was that it arrived at KSC without having undergone final post-static checkout and modification at MTF, thus eliminating duplicate checkout at MTF and KSC. NASA officials hoped by this action to save NASA seven to eight days in the Apollo Saturn 501 launch vehicle erection schedule in the VAB.³⁴⁸

326




326. Saturn V third stage (S-IVB)

327. AS-503 third stage (S-IVB) explosion

328. S-II stage arrival at KSC

328



329. Saturn V first stage (S-IC), Boeing Co., prime contractor


330. Overall view of S-IVB fuel tank relief valve undergoing test at General Dynamics (sub-contractor for Douglas) in San Diego

331. Assembly area, Huntington Beach, California. S-IVB-507 left, S-IVB-506 middle, and S-IVB-212 right

332. S-IVB-505 and S-IVB-211 in vertical checkout tower at Huntington Beach

MSFC awarded a \$100,000 six-month contract to Bell Aerosystems Company on January 20 for flight testing Bell's "pogo stick" one-man flying vehicle at Langley Research Center's (LaRC's) gravity test facility. The vehicle would be evaluated for possible use in an Apollo lunar surface mission.³⁴⁹


329




330



331



332



Following the loss of the S-IVB-503 stage during testing on January 20, NASA officials amended identification numbers of subsequent S-IVB stages

SATURN ILLUSTRATED CHRONOLOGY

to fill the vacancy created. The S-IVB-504 became the S-IVB-503N, S-IVB-505 became S-IVB-504N, and S-IVB-506 became S-IVB-505N. A replacement stage using an old S-IVB-507 tankage became S-IVB-506, and S-IVB-507 and subsequent stages retained the old identification.³⁵⁰ (The N at the end of the stage identification stands for the word "New," a designation that became necessary after an earlier stage version exploded, necessitating the use of a substitute stage.)

A board to investigate the destruction of S-IVB-503 was organized at the Sacramento Test Center on January 23. Board members included Dr. Kurt Debus, Chairman; Karl Heimburg, MSFC Test Laboratory Director; and T. J. Gordon, Douglas Aircraft representative. On this same date KSC technicians erected the S-IVB-206 stage atop the S-IB-6 stage on LC-37. Stage subsystem check-out began promptly as technicians prepared for the first integrated tests of the Uprated Saturn 206 vehicle.³⁵¹

The S-IVB-503N stage, a replacement for the destroyed S-IVB-503, arrived at SACTO from DAC's Space Systems Center on January 25, approximately one week later than scheduled because of engine difficulties in the Super Guppy aircraft.³⁵²

The ninth Uprated Saturn I booster to be assembled at Michoud arrived at MSFC on January 26 aboard the barge Palaemon. After captive firing at MSFC, S-IB-9 would, according to schedule, return to Michoud for post-firing checkout before shipment to the KSC launch site. On this same date, as part of the post-static checkout, workmen completed liquid hydrogen tank inspection of the S-II-1 stage positioned in the VAB at KSC. At Huntington Beach, workmen completed factory checkout of S-IVB-209 and readied the stage for airlift to SACTO.³⁵³

333



333. Michoud, aerial view with plant in background

The three-man crew for NASA's first manned Apollo space flight (AS-204) died, apparently instantly, when flash fire on January 27 swept their Apollo I spacecraft mated to the Uprated Saturn 204 vehicle. This accident, killing Virgil I. Grissom, Edward H. White II, and Roger B. Chaffee, was the worst in the history of the U. S. space program. It occurred at KSC's LC-34 during the first major rehearsal for the February 21 mission.

JPL issued to industry a January 27 request for proposals on contracts for preliminary design and definition studies of an unmanned Voyager landing capsule. Two identical Voyager spacecraft would be launched by a single Saturn V booster in 1973 and in 1975, according to the proposals. Purpose of the mission to Mars would be to conduct scientific studies of Mars and search for extra-terrestrial life. From the industrial proposals, due in March, two to four contractors would be chosen.³⁵⁴

Also on January 27 the S-II-2 stage left Seal Beach, California, to pass through the Panama Canal and on to MTF. After its journey lasting 16 days, the S-II would arrive at MTF for two static tests. At SACTO on this historic date, workmen completed installation of the S-IVB-503N stage on the Beta I Test Stand.

334



334. Route used to transport the S-II stage from Seal Beach complex to the Seal Beach dock

335. S-II Seal Beach Facilities, looking east

335



336. Saturn V/S-IC-T
stage test program


[illegible]

TEST NAME	TEST DATE	TEST TIME	TEST RESULT
1. 100% PASS	10/10/10	10:10:10	100%
2. 100% PASS	10/10/10	10:10:10	100%
3. 100% PASS	10/10/10	10:10:10	100%
4. 100% PASS	10/10/10	10:10:10	100%
5. 100% PASS	10/10/10	10:10:10	100%
6. 100% PASS	10/10/10	10:10:10	100%
7. 100% PASS	10/10/10	10:10:10	100%
8. 100% PASS	10/10/10	10:10:10	100%
9. 100% PASS	10/10/10	10:10:10	100%
10. 100% PASS	10/10/10	10:10:10	100%


In the first statement concerning Apollo flight missions since the AS-204 accident, NASA Associate Administrator for Manned Space Flight, Dr. George E. Mueller, announced on February 3 that NASA would proceed with launching of three unmanned Apollo flights scheduled for 1967: AS-206, AS-501, and AS-502. NASA meanwhile was postponing indefinitely manned Apollo missions pending the outcome of the Apollo 204 Review Board's investigation.³⁵⁵

Also on February 3 NASA signed an incentive contract modification with the Boeing Company for five additional Saturn V first stages. As a result of this modification, Boeing was now under contract to fabricate and assemble 15 of the 7.5 million-pound-thrust boosters, thereby completing the S-IC stage requirements for the previously announced scheduled launching of 15 Saturn V space vehicles in the Apollo manned lunar landing program. The \$120 million supplemental agreement awarded by MSFC extended the Boeing contract through June 1970. This modification increased the total estimated value of the Boeing contract to \$977 million.³⁵⁶

338. Saturn V vehicle configuration



338




On February 17 the first full-duration test of a cluster of uprated J-2 engines, S-II Battleship Test No. 041, lasted 360 seconds. On this same

SATURN ILLUSTRATED CHRONOLOGY

date requalification of the SA-204 vehicle following de-erection of the Apollo spacecraft consisted of two tests, the Launch Vehicle (LV) Emergency Detection System test and the LV Systems Plugs-In test; both were accomplished successfully with no problems. At Huntington Beach three days later, after completion of J-2 engine installation, the stage checkout of S-IVB-505 began. The next day, February 21, the S-IVB-502 left SACTO for KSC.³⁵⁸

339



339. Saturn V instrument unit

340. Saturn V specifications


Erection of the AS-501 stages at KSC began on February 23 and was completed with the stacking of the IU on February 25. Schedules called for the launch vehicle "power on" to begin three days later.³⁵⁹

On February 25 workmen at MTF completed construction of the S-II A-1 Test Stand, and the Corps of Engineers accepted beneficial occupancy with exceptions.³⁶⁰

MSFC personnel static fired the Uprated Saturn I first stage S-IB-9 at Huntsville for approximately 35 seconds on February 27. It had been static-fired for 13.5 seconds on February 24.³⁶¹

On February 27 the S-II stage prime contractor, NAA, gained beneficial occupancy of three newly

340



constructed buildings at the contractor's Seal Beach Complex. These buildings were the Station I Subassembly Building, the Multi-purpose Building 81, and the Warehouse and Maintenance Building 86. Meanwhile, overall construction of an eight-story Administrative Office Building No. 80 was progressing on schedule.³⁶²


Following an extensive systems, subsystems, and total integrated systems checkout of the B-2 Test Stand at MTF on March 3, workmen successfully fired the S-IC Battleship/All Systems state (S-IC-T) for 15 seconds. This S-IC-T test, the first MTF S-IC firing, proved the total compatibility of stage, mechanical support equipment, and S-IC test facilities.³⁶³

341

341. J-2 injector tests at Vertical Test Stand One, Santa Susana Field Laboratory

342. S-IVB-206 on transporter in VAB, Sacramento

342




The second Saturn V launch vehicle flight booster, S-IC-2, left MSFC for KSC by barge on March 3. This was the start of a month of travel in the Saturn program, exemplifying the program's far-flung activities. Included in the

SATURN ILLUSTRATED CHRONOLOGY

March travel in the Saturn program were two Saturn boosters riding side by side on separate barges from New Orleans en route up the Mississippi River to MSFC. On one of the dual barges rode the Saturn V test stage, S-IC-T, after its successful 15-second firing on this March 3 date. The other barge brought the tenth Uprated Saturn booster, S-IB-10, from Michoud to MSFC for static tests. And at KSC the stages of the sixth Uprated Saturn, SA-206, were leaving or preparing to leave LC-37 for return to various sites for storage. The S-IB-9 stage was leaving MSFC by barge. The second stage for SA-206 (S-IVB-206) would make better triptime, leaving two weeks later aboard the Super Guppy aircraft from KSC to Huntington Beach for storage at the DAC plant. Also in March the instrument unit for SA-206 left by aircraft for the IBM plant in Huntsville for storage. These various movements came because SA-206 was to have launched an unmanned lunar module on its first space test, but subsequent scheduling redesignated SA-204 for that mission. SA-206 would remain in storage for use in a subsequent mission.³⁶⁴

343



343. S-IC-3 parts inside
Point Barrow

On March 7, an erroneous Beckman Digital Data System cutoff at 3.080 seconds ended the first attempt to fire S-IB-9 in a long-duration test. Approximately 2 1/2 hours later, however, technicians at MSFC fired the stage for long duration (145.4 seconds) achieving all test objectives.³⁶⁵ During the first week in March, NASA also signed an incentive contract with the Boeing Company for Saturn V Systems Engineering and Integration (SE&I) requirements as Schedule II, NAS8-5608, for target costs and target fees of \$720.4 million. This requirement extended the SE&I effort through December 1968.

On March 9 DAC airlifted S-IVB-209 from Huntington Beach to SACTO to undergo acceptance firing.³⁶⁶

SA-500D Configuration I testing ended March 11 with a special test to verify the flight control system. The Configuration I test program included roll testing completed January 16, pitch testing completed January 23, yaw testing completed February 15, and longitudinal testing completed February 26.³⁶⁷

After MSFC completed the series of acceptance test firings of S-IB-9 at Huntsville, the stage left Huntsville by barge on March 14. During this same week, the S-IC-2 stage arrived by barge at KSC. Also during this week scientists at Arnold Engineering Development Center (AEDC), Tullahoma, Tennessee, started and restarted a J-2 rocket engine in simulated altitude tests, a significant accomplishment in improving the engine's readiness for restart missions in space. Such tests duplicated the extreme temperatures and other environmental factors of 100,000 feet above earth. Earlier tests at Tullahoma had confirmed the J-2 engine performance for the Up-rated Saturn I vehicle.³⁶⁸

A second S-IC-T firing lasted for 60 seconds on March 17. This firing validated the flame-bucket-water-flow pattern of the B-2 Test Stand

SATURN ILLUSTRATED CHRONOLOGY

and ended the facilities checkout test series at MTF.³⁶⁹ Also on March 17 technicians fired the S-II battleship stage for a mainstage duration of 29 seconds.³⁷⁰

During the third week in March, two major pieces of Saturn hardware were intransit. On March 18 the S-IB-9 stage arrived at MAF from MSFC to undergo post-static modification. And transportation personnel at Redstone Airport successfully loaded S-IU-502 into the Super Guppy aircraft on March 20 after a delay of four days because of high winds. The aircraft carried its cargo to KSC.³⁷¹

Also on March 20 NASA scheduled use of the AS-204 booster to launch the first Apollo LM on an unmanned flight in the summer of 1967. It was the last booster equipped with full R&D instrumentation. Original plans had been to use the AS-206 booster. Purpose of the first LM mission would be to obtain data on ascent and descent propulsion systems, including a restart; verify LM structure; and evaluate staging.³⁷²

On March 20 MSFC announced assignment of Karl Heimburg, Director, Test Division, as Acting Director of Test and Evaluation at MTF for an indefinite period. In this assignment Mr. Heimburg would be the principal member of MTF management for test plans and procedures, for operation of test facilities, for overall test safety and success, and for NASA direction of test programs carried out by the on-site contractors. This assignment was not construed as a change in current assignments or the organization structure at MTF even though Mr. Heimburg would have MTF personnel and a small augmentation group of his own selection from the MSFC Laboratory assisting him.³⁷³

Also on March 20 MSFC awarded Bendix Corporation a \$7.4 million cost-plus-award-fee contract for development and production of the ATM pointing control system (PCS). By this contract


Bendix would produce three units by August. The ATM system would permit Apollo astronauts to point a telescope to selected regions of the sun during a period of maximum solar flare activities beginning in late 1968. American Optical Company, under a \$740,460 contract, would build a dynamic simulator for use in developing the PCS.³⁷⁴

Boeing personnel removed the S-IC-T from Test Stand B-2 at MTF on March 24, following post-static checkout, test stand refurbishment, and facilities modification. Preparation began for shipment of the stage to Huntsville.³⁷⁵

On this same date MSFC Director, Dr. Wernher von Braun, announced NASA's selection of Lee B. James, Manager of the Saturn I/IB Program, to serve as NASA's Deputy Program Director of the Apollo Program, Office of Manned Space Flight. Dr. von Braun also announced appointment of William Teir, Deputy Manager, Saturn I/IB Operations, to replace Mr. James as Saturn I/IB Program Manager, and appointment of William F. LaHatte, Deputy Manager, Saturn I/IB Management, as the new Deputy Manager, Saturn I/IB Program.³⁷⁶


344

344. Saturn IB second stage/Saturn V third stage (S-IVB), McDonnell Douglas Co., prime contractor



SATURN ILLUSTRATED CHRONOLOGY

345



On March 31, failure of a prevalue to close caused program officials at MTF to scrub the first attempt to static fire the S-II-2 stage.³⁷⁷ On this same date the S-IC-T traveled from MTF to its destination at MAF aboard the barge Pearl River. After its arrival at Michoud, dockhands transferred the stage aboard the covered barge Poseidon for shipment to MSFC in Huntsville.³⁷⁸

a.

b. 347

DATE	DURATION - SEC		RESULTS
	PLANNED	ACTUAL	
*NOV 9 64	IGNITION	IGNITION	SUCCESSFUL
*NOV 21 64	TRANSITION	TRANSITION	SUCCESSFUL
*NOV 26 64	10	12	PREMATURE CUTOFF TEMP OVER LIMIT
*DEC 11 64	10	10	SUCCESSFUL
*APR 24 65	IGNITION	IGNITION	SUCCESSFUL
MAY 1 65	10	10	PREMATURE CUTOFF FALSE SIGNAL
MAY 5 65	10	12	PREMATURE CUTOFF FALSE SIGNAL
MAY 7 65	10	10	SUCCESSFUL
JUN 9 65	25	8	LOST PREP COMPLETE SIGNAL
JUN 15 65	25	5	LOST PREP COMPLETE SIGNAL
JUN 17 65	25	TRANSITION	PREMATURE CUTOFF SLAM PRESS SWITCH
JUN 20 65	25		PREMATURE CUTOFF GAS GEN OVERHEAT
JUL 13 65	25	2 86	MANUAL CUTOFF FAULTY CONNECTION
JUL 13 65	25	27	SUCCESSFUL
JUL 16 65	150	34	MANUAL CUTOFF FALSE INDICATION
JUL 20 65	150	150	SUCCESSFUL
JUL 27 65	FULL	IGNITION	IGNITION CUTOFF FAULTY PROBE
JUL 27 65	FULL	60	MANUAL CUTOFF FALSE SIGNAL
JUL 30 65	FULL	65	MANUAL CUTOFF FALSE SIGNAL
AUG 3 65	FULL	5	SOLENOID SIGNAL
AUG 9 65	FULL		PREMATURE CUTOFF OVER TEMP #2 ENG
AUG 12 65	FULL	FULL	SUCCESSFUL 392 SEC
DEC 22 65	15	104	MANUAL CUTOFF ENGINE FIRES
DEC 28 65	15	103	AUTOMATIC CUTOFF FAULTY INDICATION
DEC 29 65	15	108	AUTOMATIC CUTOFF FAULTY WIRING
DEC 29 65	15	53	MANUAL CUTOFF OBSERVER ERROR
DEC 29 65	15	18	SUCCESSFUL
JAN 12 66	350	354	SUCCESSFUL
FEB 3 66	350	14	AUTOMATIC CUTOFF FAULTY GENERATOR
FEB 7 66	200 350	335	SUCCESSFUL
FEB 22 66	350	69	AUTOMATIC CUTOFF FAULTY GENERATOR
FEB 24 66	350	360	SUCCESSFUL
MAR 4 66	350	350	SUCCESSFUL
MAR 15 66	350	360	SUCCESSFUL
			TOTAL ACTUAL FIRING - 2749 67 SEC
			*SINGLE ENGINE TEST

346



345. Michoud, aerial view of engineering building and manufacturing area

346. Saturn V second stage (S-II), North American-Rockwell, prime contractor

347a. Testing of S-II Battleship test stage
b. test results of S-II Battleship test stage

348. S-IC-8, S-IC-4, and
S-IC-6 in manufacturing
building, Michoud
349. S-IC test stand at
MTF



348



349

Battleship testing of the S-II Battleship test stage equipped with five uprated J-2 engines ended with Test 043, a full-duration test of approximately 360 seconds mainstage operation.³⁷⁹

In March NASA gave approval to rebuild the Beta III Test Stand at SACTO, which was severely damaged January 20 when the S-IVB-503 exploded.³⁸⁰

On April 1, the S-IB-10 stage departed Michoud for MSFC onboard the barge Palaemon.³⁸¹

The S-IB-6 stage departed KSC on April 3 aboard the Promise en route to Michoud for storage. Also on April 3 the Apollo Boilerplate (BP-30) service and command modules arrived at MSFC where they would be modified for use as a backup payload for AS-501 and AS-502 missions.³⁸²

The S-IC-4 stage arrived at MTF on April 4 aboard the barge Pearl River. The following day Boeing personnel placed the stage in the MTF S-IC static test stand.³⁸³


MTF personnel, on April 6, conducted a successful 368-second firing of the S-II-2 stage.³⁸⁴ At this same time NASA revised designations for Apollo and AA missions as follows: (1) All Apollo missions would be numbered sequentially in the order flown, with the next Apollo mission to be designated Apollo 4, followed by Apollo 5, etc.; (2) AA missions would be designated sequentially as AAP-1, AAP-2, etc. Number designations would not differentiate between manned and unmanned Uprated Saturn I and Saturn V missions.³⁸⁵

The S-IB-6 stage arrived at MAF from KSC on April 7 for storage pending rescheduling of Uprated Saturn I flights.³⁸⁶ Two days later the S-IB-10 stage, shipped by barge from MAF on April 1, arrived at MSFC's Huntsville dock.³⁸⁷

SATURN ILLUSTRATED CHRONOLOGY

350

350. S-IC flight stage,
Huntsville



And again on April 9, the S-IC-T stage which left Michoud aboard the Poseidon barge on April 1 arrived at MSFC where it was stored in the ME Laboratory to await use in research and development tests.³⁸⁸

The S-IVB-206 stage, de-erected from LC-37 following reassignment of the LM-1 mission to the AS-204 vehicle, was shipped from KSC on April 13 via the Super Guppy aircraft to SACTO where it would be stored.³⁸⁹

On April 15, technicians at MTF successfully static fired the second flight stage (S-II-2) of the Saturn V space vehicle.³⁹⁰

Also on April 15 MSFC completed award of one-year, cost-plus-incentive award-fee (CPIF) contract extensions totaling more than \$57 million for engineering, fabrication, and institutional support services for the Saturn launch vehicle program. Recipients: Sperry Rand Corporation, \$12,695,727; Vitro Corporation, \$5,344,159;

Brown Engineering Company, \$12,350,140; Spaco, Incorporated, \$5,971,638; Northrop Corporation, \$3,905,000; Hayes International Corporation, \$4,969,277; Management Services Incorporated, \$5,560,941; Rust Engineering Company, \$599,090; and RCA Service Company, \$5,749,907.³⁹¹

On April 19, a J-2 engine set a record with the completion of 103 tests lasting a total of 20,094 seconds. This length of testing was longer than for any other large rocket engine produced by the Rocketdyne Division of North American Aviation, Inc. This record-breaking series of tests was conducted on research and development engine J022-1 on test stand Delta 2A at the Santa Susana Field Laboratory between December 9, 1966, and April 19, 1967, with no major hardware changes. The total run duration was more than five times the designated qualification test time, and the number of tests was more than triple the number required for qualification. At the time of this test completion Rocketdyne had delivered 109 J-2 production model engines to MSFC, responsible for technical direction of the engine development.³⁹²


The S-IC-D stage arrived at MTF from Huntsville on April 23. Workmen at MTF placed the stage in storage pending its use in the early fall.³⁹³

351



351. MTF, laboratory and engineering complex, looking north

352




352. Installation of S-IC-D in S-IC-BI test stand at MTF

SATURN ILLUSTRATED CHRONOLOGY

353

353. S-IVB production area, Huntington Beach



On April 27, the Saturn upper stage model outfitted as a manned orbital workshop arrived at MSFC aboard the Super Guppy aircraft. Built by Douglas Aircraft at its Space Systems Center, Huntington Beach, California, the mockup depicted the S-IVB stage as it would be used in the Apollo Applications Program.³⁹⁴ MSFC announced on April 27 that it had asked industry for proposals concerning a study to determine the feasibility of developing large television broadcast satellites to be launched as manned or unmanned Saturn V payloads. Such satellites might be capable of broadcasting directly to home receivers. The study would concern itself primarily with satellite technology.³⁹⁵

Also on April 27 MSFC completed a review of three previous Saturn IB improvement studies and confirmed that it would be feasible to increase the payload capability of the Saturn IB by use of solid rocket motor (SRM) strap-ons or by use of SRM's as the first stage booster.³⁹⁶

On April 29 the contractor for research and development of S-IVB stages, the Douglas Aircraft Company, merged with McDonnell Aircraft Corporation to form McDonnell Douglas Corporation.³⁹⁷

In April NASA awarded CCSD Contract NAS8-21107 in the amount of \$113,400 for the purpose of CCSD's continuing for eight months a Saturn IB Improvement Study. Object of the study was to provide more detailed data on a projected Saturn IB system with a 120-inch SRM having 7 1/3 segments. The contractor would also investigate the option of launching the vehicle with four, two, or no SRM's depending on mission requirements. The study would end in December 1967.³⁹⁸ In still another April contract NASA awarded Contract NAS8-21076 to IBM in the amount of \$222,000 to perform a companion and supporting study to CCSD's Saturn IB Improvement Study. IBM's effort lasting seven months would involve definition of astrionics systems required to implement selected vehicle configurations.³⁹⁹

Thirteen astronauts attended the Saturn V launch vehicle systems and performance briefing April 27 and 28 at MSFC. Representatives of various MSFC laboratories made presentations to the astronauts. The Astrionics Laboratory presented material on navigation and guidance control. The Aero-Astrodynamic Laboratory presented information on profiles and made presentations on propulsion systems and engine restarts.⁴⁰⁰

Twelve astronauts visited MSFC from May 2 through May 5 and evaluated modifications proposed for converting the S-IVB liquid hydrogen tank into a space station. The astronauts practiced some of the tasks they would perform while orbiting in 10,000 cubic feet of living and working space. Workmen disassembled the mockup, about 60 feet long and 22 feet in diameter, and the astronauts, dressed in space suits, practiced

354. Installation of optical system in S-IVB space chamber, Huntington Beach

354



SATURN ILLUSTRATED CHRONOLOGY

putting it back together in much the same manner as if they had to do it in space. Such a converted S-IVB stage would provide space in which the astronauts could live and work for an initial 28 days in space. Then the astronauts would "store" the workshop in space for reuse later for longer periods. Douglas Aircraft assembled the mockup at its Huntington Beach, California, facility and airlifted it to MSFC aboard the Super Guppy aircraft.⁴⁰¹

Meanwhile, at SACTO technicians successfully acceptance-fired the S-IVB-503N stage for 446.9 seconds.⁴⁰² After the successful firing of S-IVB-503N, technicians transferred the stage to the Vertical Checkout Laboratory for post-firing modifications and preparations for checkout. The stage's All-Systems Checkout would come approximately 60 days later.⁴⁰³

On May 9 technicians at Huntsville successfully acceptance-fired the S-IB-10 stage a short duration of 35.424 seconds.⁴⁰⁴

NASA, on May 10, awarded Douglas Aircraft a \$4,665,000 modification to an existing contract for reliability and verification testing of Saturn S-IVB stage components.⁴⁰⁵

On May 15 MSFC asked Boeing, General Electric, and TRW Systems to submit proposals for parallel contracts for further project definition work in Voyager interplanetary exploration. Proposals would be due May 19. Boeing, General Electric, and TRW Systems had been conducting parallel Voyager project definition study contracts since early 1965 for Jet Propulsion Laboratory, Pasadena, California, and this would be a continuation of that effort.⁴⁰⁶

At MTF on May 16 there was a successful 125-second-duration acceptance firing of the S-IC-4 stage. After an engine alignment optical check, the stage, the first flight S-IC to be tested at

355. MTF, industrial complex

356. MTF, meteorology lab

355



356




MAY 1967

MTF, would be returned to MAF for post-static modification and checkout.⁴⁰⁷

The S-II-2 stage, aboard the barge Poseidon, left MTF on May 20 en route to KSC.⁴⁰⁸

357



357. MTF, barges — hurricane precautions

358. MTF, Saturn V test complex, looking northwest

358



Vice-President Hubert Humphrey visited MSFC on Monday afternoon, May 22. After the Vice President spoke to employees and guests in front of Building 4200, his motorcade traveled to Building 4755 where Dr. von Braun described to him several mockups related to the Apollo Applications Program and conducted a tour of space vehicle engineering models and test "hardware." The Vice-President and his party later watched a static firing of an Uprated Saturn I first stage from the East Observation Bunker. The full-duration test lasted 145.6 seconds.⁴⁰⁹

NASA announced on May 24 that the second stage of the first Saturn V launch vehicle would be dismantled at KSC to check for any "hairline" cracks. NASA made this decision after finding similar cracks in an identical stage of the vehicle at the North American Aviation, Seal Beach, California, plant. The space agency did not expect additional checks to delay the first Saturn V flight — an unmanned mission scheduled for mid-August — by "more than a week or so."⁴¹⁰

359



359. Seal Beach complex

The S-II Battleship transition and full-duration testing during the first half of 1967 ended with the seventh test, May 26, 1967. Firings had included a 1.8-second transition test on February 18; the first full-duration test (360 seconds) on February 17; four full-duration tests of 355 or more seconds on March 17, March 31, April 26, and May 26; and another transition test of 50 seconds duration May 12.⁴¹¹

During May the highlight of the orbital workshop design progress was the intensive three-day S-IVB orbital workshop design review held at MSFC early in May with more than 200 engineering and management representatives participating. Organizations represented at the preliminary design review included NASA Headquarters, Manned Spacecraft Center, Kennedy Space Center, MSFC, and Douglas Aircraft Company, manufacturer of the S-IVB stage. The review featured an S-IVB mockup built by Douglas and shipped recently to MSFC. Made of non-flight S-IVB hardware, the mockup was outfitted according to the preliminary design of the manned orbital workshop.⁴¹²

June began with considerable movement of Saturn stages. On June 2, technicians at Cape Kennedy de-stacked the SA-501 to check for imperfections in the propellant tanks of the S-II stage. They made X-rays and, after finding twelve imperfections, they instigated repairs by burnishing.⁴¹³ On June 6 the S-IC-4 flight stage returned to Michoud aboard the barge Pearl River. Upon its arrival, workers unloaded it and transported the stage to the Stage Test Building for refurbishment and post-static checkout.⁴¹⁴ One day later workmen removed the S-IB-10 stage from the MSFC Static Test Tower and prepared the stage for return shipment to MAF on June 8.⁴¹⁵


NASA changed the charter on June 8 to reflect the change of the name of the Michoud Operations to Michoud Assembly Facility.⁴¹⁶

SATURN ILLUSTRATED CHRONOLOGY

On June 13 the S-IB-10 stage arrived at MAF aboard the Palaemon barge from MSFC where it had undergone acceptance tests.⁴¹⁷

The Center announced on June 14 that successful F-1 engine tests had reached the 4,000 mark in number of tests. This 4,000th test occurred when an F-1 engine at Edwards Field Laboratory, California, ran 165 seconds at 1,542,000 pounds of thrust. The total of 4,000 firings included 2,035 engine firings and 1,965 thrust chamber injection assembly firings. Rocketdyne Division of North American Aviation, Inc., developed the engine. Engine number 103-1 made the 4,000th run, almost 7 years after the first F-1 firing at Edwards.⁴¹⁸


360



360. F-1 test facilities,
Edwards AFB

S-IVB-504N arrived at the Sacramento Test Center via the Super Guppy aircraft on June 16.⁴¹⁹ Also on June 16 NASA and Boeing signed a \$20-million letter contract extending the scope of Boeing's work with NASA to include integration of the Apollo spacecraft's three modules with the Saturn V launch vehicle. Under terms of this contract Boeing would: (1) assist and support NASA and its three manned spaceflight centers — MSC, MSFC, and KSC — in performance of certain technical tasks for Apollo missions AS-501

361




361. Saturn V flight vehicle in VAB-KSC

362. Apollo Saturn V, AS-501 rollout, transfer from VAB to LC 39A

through AS-515; and (2) be responsible for supporting the Apollo Program Office in integrating the Saturn V booster with the Apollo CM, SM, and LM.⁴²⁰

Technicians at KSC completed erection of the AS-501 spacecraft and electrical mating of AS-501 on June 20, as the payload, Apollo Spacecraft 017, went atop the rocket. This first flight vehicle, known as AS-501, was scheduled for launch in the third quarter of 1967. It would be an unmanned test in which the complete vehicle would be "live." The spacecraft would re-enter following a flight of several thousand miles from earth.⁴²¹

362




The S-IVB-209 stage was successfully static-fired for a mainstage duration of 456 seconds on June 20 in the Beta I Test Stand at SACTO. The firing was terminated by LOX depletion cutoff as planned.⁴²²

SATURN ILLUSTRATED CHRONOLOGY

On June 21 the Pearl River barge transported the S-IC-5 stage from MAF's Stage Test Building, where it had undergone post-manufacturing checkout and modification, to MTF for additional changes and static tests.⁴²³

363



363. S-IC-5 on Pearl River

364. S-IC-5 passing through Bascule Bridge leaving MTF

364



MSFC announced on June 22 that the Bendix Corporation and the Boeing Company had received contract extensions for further study of lunar surface vehicles. Bendix would receive \$149,914 for the extension and Boeing would receive \$149,485. The two firms would perform specified design study tasks on the vehicle, called a Local Scientific Survey Module (LSSM). MSFC had awarded the two firms parallel six-month contracts, totaling \$350,000 each, on June 29, 1966. These new modifications extended the contract through August 1967.⁴²⁴

The first flight model of the Apollo LM arrived at KSC on June 23 aboard the Pregnant Guppy aircraft. This was the payload for SA-204, then on the pad at LC-37. The lunar module would be in KSC's industrial area for about 45 days before installation atop the launch vehicle.⁴²⁵

Officials at NASA's rocket engine test site at Edwards Air Force Base, California, held brief ceremonies on June 28, marking the delivery of the millionth ton of cryogenic rocket propellants and pressurants. NASA had used the liquid oxygen and liquid nitrogen to test F-1 rocket engines during the past six years. (The first engine test had been in 1961.) Peak testing was in 1965 when as many as 35,300 tons were delivered in a single month.⁴²⁶

NASA announced on June 30 that it had signed a two-month extension of a contract modification with the Chrysler Corporation for procurement of long-lead-time items for additional Uprated Saturn I first stages. The \$2.4 million extension, to continue in force through August 31, 1967, enabled Chrysler to continue procuring the materials, components, and engineering support necessary to maintain its capability for assembling four Uprated Saturn I boosters per year. The initial long-lead-time supplemental agreement, valued at \$7.2 million, had been awarded in December 1966. At the time of this extension

SATURN ILLUSTRATED CHRONOLOGY

award, Chrysler was under contract to assemble and test twelve 1.6 million-pound-thrust stages at the MAF in New Orleans.⁴²⁷

MSFC announced also on June 30 the award by NASA of a \$14,811,540 fixed-price-incentive-fee contract to North American Aviation for 60 additional H-1 rocket engines for use on first stages of Up-rated Saturn I vehicles. This order increased the total number of engines purchased to 322. Delivery would continue through September 1968.⁴²⁸

During June special tests to determine the best way to recover and reuse the Saturn V first stage (S-IC) were being conducted at MSFC. In these tests 1/10 scale models of the S-IC were dropped from altitudes of as much as 156 feet into a 20-foot-deep water tank to simulate descent of the stage through the earth's atmosphere and into the ocean. Purpose of the tests was to study a "soft splash" concept designed to bring back the S-IC with minimal damage. MSFC engineers said a workable recovery method would save "millions of dollars" in future years.⁴²⁹

Four test firings of the S-IVB battleship stage occurred at MSFC in the January to June 1967 period as follows: Test S-IVB-042 on April 21, for 235.8 seconds; Test S-IVB-043 on May 2, for 150 seconds; Test S-IVB-044 on May 18, for 4.7 seconds; and Test S-IVB-045 on June 26, for 199 seconds.⁴³⁰

Records at the end of June indicated that during the first six months of 1967 Rocketdyne conducted 1,838 R&D F-1 engine tests for a total firing time of 149,483 seconds. The tests were performed at Edwards Field Laboratory and at MSFC's West Area F-1 Test Stand. Rocketdyne delivered 11 F-1 production engines to Boeing during the same six-month period: one for the S-IC-7 stage, five for the S-IC-8 stage, three for the S-IC-9 stage, and two as S-IC flight stage spares.⁴³¹

365. Seal Beach, S-II facilities, looking west
365



Records at the end of June also indicated that during the January to June 1967 period Rocketdyne conducted 103 J-2 engine R&D tests at Santa Susana Field Laboratory (SSFL) for a total firing time of 18,904.5 seconds; conducted 66 J-2 engine production tests for a total duration of 10,443 seconds; and continued J-2 engine environmental testing at AEDC, including S-IVB-501 verification tests proving restart capability and S-II-501 verification tests. In this same period NASA accepted 19 J-2 production engines, allocated 17 of these as government furnished equipment to NAA for S-II flight stages and one as an S-II spare, and provided the other engine to DAC as an S-IVB flight stage engine.⁴³²


366



366. S-IU-503 leaving IBM facility, Huntsville

367. S-IC-8 horizontal installation at Michoud


367



SATURN ILLUSTRATED CHRONOLOGY


MSFC awarded McDonnell Douglas a \$496,024 contract on July 1 to study advanced versions of the Saturn S-IVB orbital workshop. Under terms of this contract, the contractor would explore concepts for a follow-on workshop for the Up-rated Saturn I program and several more sophisticated versions of the Saturn V, with initial emphasis on uses of the stage in the AA program.⁴³³

NASA began the last half of 1967 with Saturn IB stages for SA-205, SA-206, and SA-208 in storage. SA-209 was in various stages of development. For example, post-static checkout of S-IB-9 and also S-IVB-209 was continuing. The S-IVB-209 stage had undergone a successful static firing the previous month, on June 20, as scheduled for a mainstage duration of approximately 456 seconds. S-IU-209 assembly previously scheduled for completion on June 26 was delayed to July 10 because of shortage of assembly supplies, including lack of some distributors. At this same time the later Saturn IB vehicle, SA-210, was under development. S-IB-10 was undergoing post-static modification and repair. S-IVB-210 was in storage at Huntington Beach awaiting availability of Beta 3 Test Stand at SACTO. Fabrication of S-IU-210 had been completed June 21, 1967, and assembly operations were in process.⁴³⁴



369

368



368. Overall view of high bay east, IBM Huntsville, S-IU-210 in fabrication, S-IU-504 in assembly, S-IU-503 in storage, and S-IU-209 in systems test

369. S-IVB-211 in storage, S-IVB-507 being painted, background: S-IVB-510 aft skirt, S-IVB-510 forward dome, and S-IVB-506 aft interstage, left/right foreground - Huntington Beach assembly building

370

370. S-IVB-211, Huntington Beach fabrication area

371. MTF, laboratory and engineering complex, looking north



On July 11 the first and second stages of the second Saturn V booster were mechanically mated at KSC in preparation for the AS-502 unmanned mission to test the Apollo spacecraft's reentry heat shield. The third stage was added on July 13 and instrument unit on July 14.⁴³⁵

371




Saturn transportation personnel found themselves unusually busy in the middle of July. The second stage of the third Saturn V flight vehicle (S-II-3) departed its manufacturing site at Seal Beach, California, on July 12 for a 13-day trip to MTF. The one-million-pound-thrust S-II made the voyage aboard the U.S. Naval Ship Point Barrow which NASA used for transporting the stages from the West Coast. Schedules called for the S-II-3 to reach MTF July 26 where it would be ground-fired by NAA, and later shipped to KSC for mating with the other stages of the Saturn V. Meanwhile, MSFC announced on July 12 that F-1 engines for Saturn V rockets were now being transported from Canoga Park, California, to New Orleans, Louisiana, by highway instead of air. The MSFC announcement stated that the first engine was already en route to New Orleans. Previous shipments of the engines had been made by specially adapted aircraft.⁴³⁶

SATURN ILLUSTRATED CHRONOLOGY

372

372. S-IC stages in horizontal area, Michoud




On July 24, MSFC awarded Astro Space Labs., Inc., a \$93,136 contract for further development and testing of a remotely controlled device to handle tools, equipment, and men in space. It consisted of links connected by powered hinges, which could be remotely controlled from either end of the device. One end would be connected to the spacecraft, and one would be free. Small versions of the device could be powered by hand pump or batteries; larger versions, by electric motors.⁴³⁷

MSFC announced on July 26 that NASA had awarded a \$2.275 million contract to the Boeing Company for procurement of long-lead-time materials for two additional Saturn V flight Boosters. The CPFF contract was the first Saturn V procurement in support of NASA's Apollo Applications program. Boeing, prime contractor for the 7.5 million-pound-thrust first stage (S-IC) of the Saturn V launch vehicle, was manufacturing 12 stages at MAF, for the Apollo manned lunar exploration program. Boeing would begin acquiring such items as propellant ducts, liquid oxygen tunnels, and fuel tank components for the 16th and 17th stages. The contract would expire on January 1, 1968.⁴³⁸

Also on July 26 NASA selected Martin Marietta Corporation to negotiate a 27-month, \$98-million CPIF contract for payload integration of experiments and experiment support equipment on AA spacecraft. Tasks would be performed at NASA's three manned spaceflight centers: (1) MSFC work would involve the orbital workshop at ATM; (2) MSC work would involve the meteorological and earth resources payloads, and (3) KSC work would involve the test integration planning and support for launch operations.⁴³⁹

373

373. S-II-5 in S-II A-2 test stand at MTF



The S-II-3 stage for SA-503 arrived at MTF on July 27, where it would become the first flight S-II to be static fired in the A-1 Test Stand, a third stand to be completed at MTF and the second operational as of that date for testing of S-II stages. Begun in December 1964, the A-1 Test Stand was built by a division of the Koppers Company, Inc., at a cost of more than \$8 million. MTF personnel static-fired the first and second flight versions of the S-II in the previously completed A-2 Test Stand December 1 and 30, 1966, and April 6 and 15, 1967. After checkout of the A-1 stand and the S-II-3 stage, schedules called for the rocket to be static-fired for the normal "burntime" of six minutes. During that time the

SATURN ILLUSTRATED CHRONOLOGY

stage's five rocket engines were expected to develop one million pounds of thrust as they would in space. Schedules called for 12 more stage rockets to be tested at MTF as part of the Apollo Program.⁴⁴⁰

MSFC and KSC on July 31 signed a formal Memorandum of Agreement concerning "KSC Use of Selected MSFC Personnel." The agreement laid the ground rules for use of MSFC personnel by KSC to (1) support the AS-501 launch scheduled for September 1967, and (2) to support projects of mutual interest and importance to both Centers which would require additional specialized personnel for temporary periods of time.⁴⁴¹

The S-IC-T Battleship/All Systems stage fired for 41.74 seconds in Test No. 22 on August 3, the third attempt in two days to complete a 40-second captive firing at MSFC's S-IC Test Complex. The test demonstrated the operational readiness of the test complex, the S-IC-T stage, and the ground support equipment. It also provided training for KSC launch crews and demonstrated the launch integrity of the Saturn V liftoff switch.⁴⁴²

MSFC announced on August 3 the successful completion of a dynamic test program of the Apollo/Saturn V, in effect giving "the green light" for the launch of the first Apollo/Saturn V later in the year as far as dynamics and structures were concerned. Boeing conducted the test program at MSFC under the direction of MSFC engineering personnel, the latter providing test criteria and monitoring of effort. Initial dynamic tests had started with the first stage of the Saturn V. Subsequent tests included the second and third stage, instrument unit, and the Apollo spacecraft. MSFC made several slight modifications to the space vehicle as a result of the dynamic program. These tests included determination of the bending and vibration characteristics of the complete vehicle. Tests were carried out in a 400-foot-high tower in the Center's Test Laboratory.⁴⁴³


On August 7 NASA issued three modifications totaling \$30.9 million to the NAA contract for the Saturn V second (S-II) stage. The first modification, valued at \$5.5 million, provided for equitable adjustment of second stage changes previously ordered; the second modification, valued at \$5.8 million, covered seven changes involving KSC ground support equipment; and the third modification, valued at \$19.4 million, was for 12 changes covering alterations of selector switches and insulation of the entire second stage.⁴⁴⁴

MSFC announced on August 10 that NASA had converted the systems integration portion of the Chrysler Corporation's Up-rated Saturn I to a cost-plus-incentive-fee agreement. With this \$22 million conversion, the total value of the systems integration segment of Chrysler's six-part Up-rated Saturn I contract was \$35.5 million. Under this arrangement Chrysler's fee was judged according to the quality and timeliness in which Chrysler accomplished its work. Chrysler's major responsibilities also included flight technology, guidance and control, and propulsion systems engineering. Chrysler would also provide systems analysis, and documentation services. In addition Chrysler personnel would perform their assignments at both MSFC and Michoud. The contract would be effective through April 1969.⁴⁴⁵

The S-IVB-505N stage was loaded aboard the Super Guppy aircraft at Huntington Beach on August 17 and transported to SACTO for acceptance testing.⁴⁴⁶

An MSFC August 18 announcement stated that NASA had awarded a \$1.4 million contract to the Rocketdyne Division of North American Aviation, Inc., for continued technological investigation of the advanced aerospike rocket engine. In the aerospike engine a doughnut-shaped combustion chamber discharges gases against the surface of

374



374. Lowering S-IC-5 onto barge at MTF

SATURN ILLUSTRATED CHRONOLOGY

a short center cone. This contrasts with conventional rocket engines in which gases are expanded inside long, bell-shaped nozzles. The concept for the aerospike engine resulted from studies of unconventional engines undertaken by MSFC. Early designs called for the engine to be about eight feet in diameter and four and one-half feet high, about 50 percent shorter than conventional bell nozzle engines. Work on the aerospike engine was at Rocketdyne's Canoga Park, California, plant and at field laboratories. Contract completion date was scheduled for May 31, 1968. The chamber was first tested in May of 1967.⁴⁴⁷

On August 23 indication of "fire" in the J-2 engine caused termination of the S-IVB-504N acceptance firing at 51.23 seconds. Post-test investigation revealed that there had been an inadvertent indication of "fire" caused by improper wiring of fire detection monitor.

On August 25 S-IC-5 underwent a full-duration acceptance firing test at MTF. Despite several problems, the test was considered satisfactory with all major objectives having been achieved. The following day in the Beta I Stand at SACTO the S-IVB-504N stage successfully underwent an acceptance firing of approximately 438 seconds duration.⁴⁴⁸

"Rollout" of AS-501 occurred August 26 at Kennedy Space Center. Representatives from MSFC and other NASA organizations, and newsmen, were present when a huge door of the Vehicle Assembly Building was raised to allow passage of this first flight vehicle. The rocket and its portable launch platform and tower, weighing 12.2 million pounds, crept to the launch mound 3.5 miles away at a top speed of less than 0.5 mile an hour. Workmen secured AS-501 over the flame trench within approximately four hours after it had reached the launch site. Then on August 28 workmen at KSC placed the nine-million-pound mobile service structure around the 363-foot-tall vehicle, providing work platforms and

other access during the seven weeks prior to launch date.⁴⁴⁹

On September 18 the NASA procurement officer executed a contract modification (supplemental agreement 813) for five additional S-II flight stages (S-II-11 through S-II-15) to become effective on October 3. Authorization and funding to procure long-lead-time hardware for these stages had been given previously, during the first quarter of 1967. This was a \$159,716,477 contract modification for the fabrication of the five Saturn V second stages. Purchase of these five stages completed the S-II requirements for the 15 Saturn V launch vehicles approved for development in the Apollo program. Schedules called for the first of the stages to be delivered to NASA in February 1969. The total value of the S-II stage contract with North American was approximately \$1.2 billion.⁴⁵⁰

The S-II-3 stage fired for approximately 65 seconds during its first acceptance test, September 19. Primary objectives that were achieved included qualification of the A-1 Test Stand flame bucket and demonstration of the stage, stand, and control room compatibility. Special objectives that were accomplished included evaluation of the slow chill of the LH₂ tank, achievement of a 3800-gallon-per-minute maximum LOX fill rate in the fast-fill mode, and verification of the LH₂ fast-fill and over-fill sensors.⁴⁵¹

The major S-II stage contractor, North American Aviation, Inc., merged with Rockwell-Standard Corporation on September 22 to form the North American Rockwell (NAR) Corporation.⁴⁵²

The S-II-3 stage underwent a full-duration (358 seconds) static firing on September 27 with termination automatically initiated by LOX depletion. The firing demonstrated the functional integrity of the stage under static firing conditions and verified that the stage met specified acceptance test requirements.⁴⁵³

SATURN ILLUSTRATED CHRONOLOGY

NASA announced on October 4 that in support of the Saturn V program it was purchasing nine additional S-IVB stages from the McDonnell Douglas Corporation for \$146.5 million, fulfilling requirements for currently approved 15 Saturn V and 12 Up-rated Saturn I launch vehicles. Delivery would begin in April 1968 and end in May 1970. The purchase brought the total S-IVB contract value for both vehicles to \$957,182,093 and the total number of stages purchased to 27. McDonnell Douglas also received a \$24 million cost-plus-fixed-fee (CPFF) contract extension for S-IVB launch services at KSC, which increased the total value of the contract to \$34 million. Included were stage receipt, checkout, launch, and launch evaluation.⁴⁵⁴

Also on October 4 NASA informed the Boeing Company that it was terminating procurement of 10 S-IC stages, S-IC-16 through S-IC-25. Boeing had submitted a proposal on July 3 and an adjusted proposal on September 20 covering the necessary supplies and services for fabrication and delivery of the stages.⁴⁵⁵

NASA announced, also on October 4, that MSFC had used AEDC facilities to investigate preparation of a spent rocket stage for human occupancy in space. The investigation involved dumping 840 gallons of super-cold liquid nitrogen (LN) through a "dead" or inactive J-2 rocket engine. Conducted at a simulated 100,000-foot altitude, this dumping experiment would pave the way for astronauts to move inside an orbiting stage and use tanks as living quarters for a space station.⁴⁵⁶

A NASA spokesman announced on October 10 that the planned launch of the Saturn V-Apollo 4 vehicle AS-501, scheduled for October 17, would be postponed until early November. Troubles with ground support equipment had stalled the countdown rehearsal. Once rehearsal was finished, engineers would evaluate results and set the date for the unmanned launch.⁴⁵⁷

OCTOBER — NOVEMBER 1967

The countdown rehearsal for Apollo 4 (AS-501) ended on October 14; final flight preparations were to be completed for scheduled launch in about three weeks.⁴⁵⁸

Maj. Gen. Samuel C. Phillips, Apollo Program Director, announced on October 26 that the first flight test of Saturn V, designated Apollo 4, could be scheduled no earlier than November 7. "This is a target date," he said. "We are in a very complex learning process and we are going to take all the time we need on this first launch." Key objective of the flight planned for November 7 would be evaluation of Apollo command module heat shield under conditions encountered on return from the moon mission. The Apollo 4 flight plan would call for Saturn V to place the spacecraft and launch vehicle third stage (S-IVB) into 117-mile circular orbit. After completing two orbits, the third stage would be re-ignited to place spacecraft into orbit with apogee of 10,800 miles. After separation from the third stage, the service module propulsion system would be fired to raise the spacecraft apogee to 11,400 miles.⁴⁵⁹

On November 1 NASA selected Bendix Corporation to negotiate a contract for design, development, qualification, and delivery of long-duration, cryogenic gas storage tanks for the first 56-day manned flight in the AAP. The tanks would be a critical pacing item for long-duration manned flights in AAP. Completion of negotiations would permit an early award if the project were continued by NASA as programmed.⁴⁶⁰

NASA Associate Administrator for Manned Space Flight, Dr. George Mueller, announced on November 4 a revised Apollo mission schedule that called for six flights in 1968 and five in 1969 using the "200-series" (Uprated Saturn I) and the "500-series" (Saturn V) launch vehicles to test and qualify Command, Service, and Lunar Modules (C&SM and LM). The schedule for 1968 would

SATURN ILLUSTRATED CHRONOLOGY

include: Apollo/Saturn 204 (AS-204), first unmanned test of LM in earth orbit; AS-502, second unmanned flight test of Saturn V and Apollo C&SM; AS-503, third unmanned test of Saturn V and C&SM; AS-206, second unmanned flight test of LM in earth orbit; AS-205, first manned Apollo flight, a 10-day mission to qualify C&SM for further manned operations; and AS-504, first manned Apollo flight on Saturn V, to provide experience with both C&SM and LM, including crew transfer from C&SM to LM and rendezvous and docking. The schedule for 1969 would include five manned flights (AS-505 through AS-509) with the first four programmed as lunar mission development flights or lunar missions simulations — AS-509 being that flight in which the lunar landing would be made.⁴⁶¹

375. Apollo lunar landing mission, typical profile


376. Aerial view of LC-39, KSC

377. Mobile service structure arriving at LC-39A for Apollo Saturn 501

378. Saturn 501 from top of mobile service structure, Pad 39A

379. AS-501 launch


375




376



377



378



379



Also on November 4 came the start of the first part of the two-part terminal countdown for the AS-501 launch, a countdown known as the launch vehicle pre-count.⁴⁶²

The second part of the terminal countdown for the AS-501 launch progressed normally through all scheduled holds on November 6.⁴⁶³

NASA reached a critical point in the Apollo Program with the Apollo 4 flight (AS-501) on November 9, an "all-up" launch from LC-39 at KSC. The flight, termed "perfect" based on evaluation of flight data, demonstrated that the spacecraft, heat shield, and lunar rocket met program requirements. S-IC stage LOX depletion sensors signaled S-IC outboard engine cutoff at 150.8 seconds after launch. The second burn, lasting 300 seconds, injected the spacecraft into an orbit with an apogee of 9,301 nautical miles. Spacecraft reentry occurred at 400,000 feet, at a flight path angle of -7.077 degrees with an internal velocity of 36,537 feet per second. The CM landed upright within nine nautical miles of the planned landing point in the Pacific Ocean, 8 hours 37 minutes 8 seconds after launch. The CM was recovered by divers from the carrier USS Bennington 2 hours 14 minutes after splashdown. Post-launch examination revealed that the aft heat shield was heavily charred but that crew-compartment-heat-shield charring was less than expected. The spacecraft windows were undamaged, but moisture existed between the micrometeoroid and heat shield panels of the rendezvous window, and the spacecraft contained approximately two quarts of sea water taken through the relief valve. Apollo 4's flight was the first of two to three missions designed to qualify Saturn V for manned flight, and the first test of the structural integrity and compatibility of launch vehicle and spacecraft. Heat shield design, S-IVB restart, structural/thermal integrity, compatibility of launch vehicle and spacecraft, and ground support had been proven.⁴⁶⁴

SATURN ILLUSTRATED CHRONOLOGY


The blastoff of Saturn V at KSC produced one of the loudest noises in history, natural or man-made, according to a November 9 announcement by Columbia University's Lamont Geological Observatory, located at Palisades, New York. Observatory physicist Dr. William Donn labeled U.S. and U.S.S.R. nuclear explosions as the only louder manmade sounds, and the 1883 fall of the Great Siberian Meteorite as the only louder natural sound on record.⁴⁶⁵

On November 20 NASA named crews for the first two manned Saturn V/Apollo flights. As prime crew for AS-504 (first mission), scheduled for 1968, it named: James A. McDivitt, commander; David R. Scott, CM pilot; and Russel L. Schweickart, LM pilot. Backup crew would be Charles Conrad, Jr., commander; Richard F. Gordon, CM pilot; and Alan L. Bean, LM pilot. Prime crew for AS-505 (second mission), scheduled for 1969, would be: Frank Borman, commander; Michael Collins, CM pilot; and William A. Anders, LM pilot. Backup crew would be Neil A. Armstrong, commander; James A. Lovell, CM pilot; and Edwin E. Aldrin, LM pilot. A three-astronaut support team was named for each flight crew: for AS-504 — Edgar D. Mitchell, Fred W. Haise, Jr., and Alfred M. Worden; and for AS-505 — Thomas F. Mattingly II, Gerald P. Carr, and John S. Bull.⁴⁶⁶

The S-II-4 stage, more powerful and somewhat lighter than previous S-II flight stages, arrived at MTF on November 26 from the NAR Corporation, Seal Beach, California. Each J-2 engine of this stage had been uprated to produce 5,000 more pounds of thrust than had been developed by previous J-2 engines. The lighter weight resulted from the use of thinner propellant tank walls and lighter weight structures.⁴⁶⁷

NASA announced on December 3 that evaluation of the Apollo 4 mission data continued to confirm initial reports that Spacecraft 017 met all flight objectives without problems. Detailed systems

380



380. Installation of S-II-4 in test stand at MTF

analyses were still in process, but evidence to date indicated that the spacecraft systems operated properly during the November 9 mission and met all specifications.⁴⁶⁸

On December 5 IBM received a supplement of \$1,292,218, bringing the IU contract total to \$200,644,441. IBM received the supplement for configuration management of 27 IU's for use on the Up-rated Saturn I and Saturn V.⁴⁶⁹

Erection of the spacecraft atop the SA-502 vehicle occurred in the VAB High Bay 3 at KSC on December 9.⁴⁷⁰

Approximately 100 representatives of Government and industry attended an Orbital Workshop design meeting at MSFC December 11-14 to discuss structures, mechanical systems, propulsion, instrumentation, communications, crew station, and electrical systems. At this workshop members formulated plans for a five-day Orbital Workshop mockup review to be held in late January 1968 with a McDonnell Douglas Corporation mockup containing the most recent design concepts on display.⁴⁷¹

President Lyndon B. Johnson, accompanied by NASA Administrator and Mrs. James E. Webb, other officials from NASA Headquarters, MSFC officials, and Louisiana's Governor John J. McKeithen, toured the Michoud Assembly Facility on December 12. While at MAF the President spoke to some 2,600 spectators, stating: "We Americans are the first to really enter and the first to understand the Twentieth Century. We will never evacuate the frontiers of space to any other Nation. We will be — we must be — the pioneers who lead the way to the stars."⁴⁷²

NASA Administrator James E. Webb and other officials of NASA stopped briefly at MSFC on December 13 on their way back to Washington, D. C., from Michoud. During his stopover Mr. Webb

381. Underwater neutral buoyancy test using foot restrainer for Saturn I workshop, Huntington Beach

381



SATURN ILLUSTRATED CHRONOLOGY

toured the AAP mockup area and received a briefing, by Dr. von Braun and other MSFC executives, on various aspects of the work.⁴⁷³

The Boeing Company completed an eight-month study on December 17 to define performance growth potential of the Saturn V and to determine alternate uprating methods to meet future missions of the Saturn program.⁴⁷⁴

Chrysler Corporation personnel at MSFC successfully static-fired the uprated Saturn I booster (S-IB-II) for 35 seconds on December 19. The stage would be shipped to Michoud Assembly Facility for post-firing checkout upon completion of a 145-second, full duration captive firing.⁴⁷⁵

On December 21 the S-IC-3 stage was loaded on-to the barge Poseidon at Michoud for shipment to KSC⁴⁷⁶ and the S-II-3 stage departed MTF aboard the barge Point Barrow, en route to KSC.⁴⁷⁷

On December 29 MSFC announced start of negotiations with CCSD for an extension to the S-IB stage contract to cover four additional S-IB flight stages and related services at an estimated cost of \$2.5 million. This would bring to 16 the total number of S-IB flight stages to be developed by CCSD for MSFC.⁴⁷⁸


The S-IVB-503N stage, shipped from SACTO via the Super Guppy aircraft, arrived at KSC on December 30.⁴⁷⁹

NASA announced on December 31 that in the final six months of 1967 Rocketdyne conducted 100 J-2 engine R&D tests accumulating 14,675 seconds firingtime at SSFL and also conducted 35 production engine tests having a total firing duration of 4,449 seconds.⁴⁸⁰ During this same time Rocketdyne conducted 122 R&D F-1 engine tests at Edwards Field Laboratory (EFL) for an accumulated firingtime of 13,254 seconds; and at MSFC's West Area Test Stand it conducted eight F-1 engine R&D tests that totaled 340 seconds of firing

time. Rocketdyne meanwhile conducted 36 production engine tests at EFL totalling 2,983 seconds firing time and delivered 11 production engines to NASA.⁴⁸¹

During December NASA extended for one year the fixed-price contract of AeroSpacelines, Inc., for air cargo services. The \$2,725,000 extension brought the total value of the contract to \$11,591,633 and provided air transport service for oversized cargo of the Saturn I and Saturn V launch vehicles through November 1968.⁴⁸²

NASA began 1968 with work in process on the AS-502 launch vehicle, preparatory to the launch that would take place in April. Meanwhile, during the first week in January all SA-503 stages were on dock at KSC.⁴⁸³



382. S-IC stage load test
at MTF


MSFC announced on January 10 that the Center was entering 1968 with firm plans to support as many as six Apollo/Saturn launches during the year. It also announced plans for supporting the goal of a lunar landing by 1970 with static tests of eight Saturn V stages (five S-II's and three S-IC's) during the year at the MTF. While this would be going on, MAF personnel would be applying the finishing touches to the 12th Up-rated Saturn I booster and forging ahead with the assembly of Saturn V boosters through S-IC-15. Meanwhile, at KSC NASA would attempt to chalk up the 15th consecutive Saturn launch no earlier than January 18 with the flight of the fourth Up-rated Saturn I. A week later, on January 24, the schedule called for the roll-out of the second Apollo/Saturn V to the launch pad. AS-502 would carry several minor modifications that were recommended by MSFC as a result of data provided by the first Apollo/Saturn V, which had flown in November of 1967.

In addition to the previous announcement at the start of 1968, MSFC also noted that other Saturn

SATURN ILLUSTRATED CHRONOLOGY


383

383. AS-501 mission
sequence



vehicles in various phases of preparation included the Apollo/Saturn 206 and another unmanned flight vehicle scheduled to fly after 204 in the Uprated series. S-IB-12, last of the original order, was in final assembly and checkout at Michoud at the start of 1968. Also, S-IVB stages for Uprated Saturn I's 205 through 209 were in storage at the Sacramento Test Facility. S-IVB stages 210 through 212 were in various stages of readiness at Huntington Beach and had not yet been static fired. The Uprated Saturn I instrument units — 205 through 209 — were stored in the IBM plant in Huntsville. Saturn V S-IVB stages 504 and 505 were at Sacramento, where post-static checks were underway. The S-IVB-506 was in post-manufacturing checkout at Sacramento and was awaiting a static test. All others were in manufacturing. The 504IU had been completed at IBM/Huntsville. S-IU-505 was in post-manufacturing checkout and others were being assembled.⁴⁸⁴

384 a.




b.



c.




d.



384a. S-IC thrust structure shear webs, Michoud, b. S-IC engine installation, Michoud, c. S-IC tank ring baffles, Michoud, d. S-IC engine fairing fitup, Michoud
385. S-IC flight stage, Michoud


385



SATURN ILLUSTRATED CHRONOLOGY

NASA announced on January 5 that it had exercised the second of three one-year renewal options with the Range Systems Division of Ling-Temco-Vought (LTV) to provide computer services for the major contractors operating at the NASA-Michoud Assembly Facility in New Orleans. The new \$2,704,349 extension of LTV's basic cost-plus-award-fee contract was awarded by MSFC for Michoud. The contract, to continue in force until January 8, 1969, would increase the total value of the LTV's contract to \$7,641,584. NASA had originally selected the Dallas-based firm on December 1965, to provide computer services at the Michoud installation in New Orleans and at its Computer Operations Office in nearby Slidell, Louisiana.⁴⁸⁵

386



386. S-II-4 removal from vertical checkout building at MTF


An indication of NASA's varied activities in the Saturn Program can be gained by a glance at the Saturn V Weekly Report for January 10 as follows: AS-502 Flight Vehicle (final package) was scheduled for delivery to KSC January 26, 1968; also for the AS-502 flight the final LVDC (flight program tapes) and SLCC (ground tapes) were scheduled for delivery to KSC by February 5, 1968. Status of the AS-503 Flight Vehicle was as follows: all three stages were in the VAB-KSC undergoing inspection and checkout; as for the S-IU-503 for AS-503, adverse weather conditions and mechanical problems with the Super Guppy had delayed the delivery of the IU on-dock KSC from December 29, 1967, to January 4, 1968. Status of the AS-504 Flight Vehicle was: S-IC-4 Stage was in test cell at Boeing-Michoud undergoing mod incorporation; the stage was scheduled on-dock at KSC April 15, 1968; S-II-4 Stage for AS-504 was at test stand at MTF undergoing mod work prior to LOX/LH₂ tanking test with captive firing scheduled for January 26, 1968, and then the stage was scheduled on-dock KSC March 31, 1968; the S-IVB-504 stage for AS-504 was in the VCL-SACTO and the stage was scheduled for transfer onto Beta I Test Stand for deferred post-firing checkout after completion of Korotherm rework, after which the stage was scheduled on-dock KSC March 31, 1968; the S-IU-504 Unit for AS-504 was in storage at IBM-Huntsville, scheduled on-dock KSC April 15, 1968. Status of AS-505 Flight Vehicle was: S-IC-5 Stage was in storage at Boeing-Michoud, scheduled on-dock KSC June 29, 1968; S-II-5 Stage for AS-505 was undergoing shakedown inspection preparations at NAA/SD-Seal Beach, prior to on-docking MTF February 9, 1968, and then on-docking KSC June 29, 1968; S-IVB-505 Stage for AS-505 was in storage at VCL-SACTO, scheduled for on-dock KSC June 29, 1968; and S-IU-505 Unit for AS-505 was in component assembly at IBM-Huntsville, scheduled on-dock KSC June 29, 1968.⁴⁸⁶

NASA announced on January 11 that it would negotiate with CCSD, New Orleans, for assembly

SATURN ILLUSTRATED CHRONOLOGY

and delivery of four additional S-IB stages at a rate of two per year. Earlier, NASA had contracted with Chrysler for production of long-lead-time materials, parts, and components for these stages. Work related to this effort would be performed at New Orleans under direction of MSFC. Chrysler presently was under contract with NASA to furnish 12 Saturn IB flight stages.⁴⁸⁷

387



387. MTF. S-IC, S-II
booster storage and har-
bor area

NASA announced also on January 11, 1968, that it would negotiate with McDonnell Douglas, Huntington Beach, California, for assembly and delivery of four additional Up-rated Saturn I launch vehicle second (S-IVB) stages at a rate of two per year. The negotiations were expected to result in a contract valued in excess of \$48 million. Earlier NASA had contracted with Douglas for production of long-lead-time materials, parts, and components for these stages. Work related to this effort would be performed at Huntington Beach under direction of MSFC.⁴⁸⁸


On January 16 NASA announced the award to Rocketdyne Division, North American Rockwell Corporation, of a contract valued at \$14,796,400 for engineering support services for H-1 engines. The H-1 engines would be used to power the first stage of the Saturn IB launch vehicles. Under this cost-plus-incentive-fee agreement, Rocketdyne would be responsible for engineering support services for engine manufacturing, testing, delivery, application, reliability, and flight performance evaluation. The major portion of the work would be at Rocketdyne's Canoga Park, California, plant. Minor segments would be performed at MAF, where the H-1 engines would be installed on the Saturn IB's first stage, and at the Kennedy Space Center's launch complex. The contract would cover the period July 1967 through June 1971.⁴⁸⁹

NASA announced on January 17 that the Apollo 5 flight, the first test in space of an unmanned lunar module, was being rescheduled for no earlier than Monday, January 22. Reason for the rescheduling was that some launch operations being done for the first time required more time than expected for completion, including the loading of hypergolic propellants aboard the spacecraft. The new schedule would be dependent upon the success of several additional ground tests, including the launch countdown demonstration test, scheduled for completion on January 19.⁴⁹⁰

A mockup of the S-IVB stage to be used as a manned orbital workshop was flown to MSFC on January 17. The full size model arrived from the West Coast aboard the giant Super Guppy aircraft. The mockup would be used later in the month for a crew station design review. NASA plans called for launching the flight orbital workshop as the second stage of the Saturn IB launch vehicle. Once in space, astronauts would convert the stage's large fuel tank into living and working quarters for a 28-day stay. The orbital workshop mockup had recently been modified by McDonnell Douglas, manufacturer of the Saturn

SATURN ILLUSTRATED CHRONOLOGY

388



388. Simulated weightlessness activity in S-IVB Orbital Workshop mockup at Huntington Beach

upper stage for MSFC. This was the mockup's second trip to MSFC. The previous spring engineers had used the model at MSFC in its original configuration for design studies.⁴⁹¹


The Saturn IB (AS-204) launch vehicle and the lunar module it orbited on January 22 performed satisfactorily. This Apollo 5 mission began at 4:48 p.m. (CST) January 22 when the Saturn lifted off Launch Complex 37 at Cape Kennedy after ground support equipment caused a delay of three hours 50 minutes. The liftoff came at sundown on a day so clear that both stages were visible to the unaided eye long after stage separation. The S-IB could be seen falling and the S-IVB going on toward orbit when tracking equipment indicated that the second stage was almost 90 miles up and 168 miles downrange. The Saturn hurled the lunar module into space to begin a series of tests of the LM's ascent and descent propulsion systems, the first such test in the vacuum of space.⁴⁹²

MSFC announced on January 30 that an orbital workshop engineering mockup simulating the flight vehicle was being readied for an extensive five-day crew station review February 12-16 at

MSFC. During the review, several astronauts were scheduled to "walk through" many tasks on the ground that would later be done in orbit under zero gravity conditions. These tasks would include experiment installation and operation. Lighting tests were being conducted during the week in the orbital workshop mockup by engineers of the MSFC Propulsion and Vehicle Engineering Laboratory. P&VE was the lead laboratory for the development of the workshop.⁴⁹³

NASA announced on January 30 that shipment of the second Apollo spacecraft lunar module and the fifth Saturn IB rocket to KSC would be postponed pending further evaluation of Apollo 5 mission results. Initial evaluation of the first lunar module flight on January 22-23 had indicated that a second unmanned flight, launched by the Saturn IB, might not be required to qualify the spacecraft for flight with men aboard. Further detailed review of flight data and deliberations by a NASA design certification review board in March would determine the final decision. Meanwhile, the Lunar Module 2 and the Saturn IB rocket stages would be maintained ready for shipment to KSC on three- and 14-day notices, respectively. Refurbishment of LC 37B would proceed for a second unmanned lunar module flight. The Mission Control Center, Houston, and tracking ships Coastal Sentry Quebec and Rose Knot Victor would maintain the operational capability to support another unmanned lunar module flight.⁴⁹⁴

During January NASA Headquarters affirmed several project name changes. The intermediate Saturn launch vehicle formerly called "Uprated Saturn I" was officially designated IB. The ground-outfitted orbital workshop, sometimes called the "dry workshop," would henceforth be known as the Saturn V Workshop. The workshop to be launched by the Saturn IB, formerly referred to as "Orbital Workshop" and "wet workshop," would be officially named Saturn I Workshop.⁴⁹⁵



389. S-II stage on transporter, Seal Beach

The S-II second stage for the fifth Apollo/Saturn V mission left Seal Beach, California, on February 2 aboard the USNS Point Barrow en route to the MTF, where the stage would undergo static testing before shipment to KSC. Also on board the ship was an F-1 rocket engine. This combination load saved an estimated \$6,000 in transportation charges. The F-1 would be unloaded for inspection at MAF, where the stage would be transferred to a barge for the remainder of the trip to MTF.⁴⁹⁶


MSFC announced on February 6 that 12 scientist-astronauts, appointed to the space program six months earlier, would visit the Center February 12-14. Purpose of the meeting, the first such at MSFC, would be to acquaint the new group with Marshall Center work, including development of the Saturn vehicles. They would also see an engineering mockup of an orbital workshop — a vehicle that would some day house astronauts for extended stays in space. The astronauts who would visit the Center, all of them with doctoral degrees, would be Robert A. Parker, Brian T. O'Leary and Karl G. Henize, astronomers; John A. Llewellyn, chemist; Joseph P. Allen, Philip K. Chapman, and Anthony W. England, physicists; William B. Lenoir, engineer; F. Story Musgrave, physiologist; and William E. Thornton and Donald L. Holmquest, medical doctors.⁴⁹⁷

The AS-502 transfer to Pad A of Launch Complex 39 occurred on February 6 at KSC. However, the scheduled transfer of the Mobile Service Structure (MSS) to the pad was delayed because of high winds. Reschedule was planned for February 9. No structural or water damage was reported on AS-502 because of movement to the pad.⁴⁹⁸

Also on February 6 NASA announced the negotiation of an additional one-year contract with the Boeing Company for operation of the Saturn V Development Facility at MSFC. The \$5,782,750 incentive contract would continue through September 1968. The original award was made in September 1964. The Saturn V Development Facility, often called the "Saturn V breadboard," would electrically simulate the operation of the Saturn V and its ground and electrical support equipment. Each step at the launch site, through lift-off and flight of each stage, could be computer-simulated at the facility.⁴⁹⁹

NASA announced on February 7 that it had added a \$3,226,374 supplemental clause to the Boeing Company's Saturn V systems engineering and integration contract. The contract extension would be effective through December 1969. Under this contract Boeing would be responsible for providing NASA with Saturn V propulsion systems pre-flight and post-flight performance analysis for the first 10 Saturn V launch vehicles. Boeing would study all of the propulsion systems data recorded during the vehicles' test firings and launches for a complete analysis of Saturn V propulsion systems performance. All work would be conducted at Boeing facilities in Huntsville. This extension brought the systems engineering and integration portion of Boeing's three-part Saturn V contract to a total of \$194,845,024. Meanwhile, under separate agreements, Boeing remained responsible for Saturn V booster production at MAF and for launch support services at KSC.⁵⁰⁰

390. Removal of S-II-4
from A2 stand at MTF
390



SATURN ILLUSTRATED CHRONOLOGY

Transfer of the Mobile Service Structure for AS-502 to the pad, scheduled for February 6 but delayed because of high winds, occurred on February 9.⁵⁰¹

The first full-duration captive rocket firing at MTF in 1968 was successfully completed on Saturday, February 10, ushering in the busiest year to date for the rocket testing center. Space engineers and technicians static-fired the fourth flight version of the Apollo/Saturn V second stage (S-II-4) for its full duration of six minutes. The huge liquid-hydrogen-fuel rocket developed an equivalent thrust of more than one million pounds. A North American Rockwell crew conducted the captive firing with the rocket locked in a 200-foot-tall tower. The captive firing was one of a series of special checkouts the stage would go through at the Mississippi proving ground before it would be certified for later flight from KSC in the manned lunar landing program. NASA engineers and scientists would carefully evaluate approximately 1,000 separate measurements taken from the rocket before a flight worthiness certificate would be issued. MTF was scheduled to test-fire, check, and flight-certify eight more Apollo/Saturn space vehicles in 1968 — four of the S-II second stages and four S-IC first stage rockets.⁵⁰²


By the middle of February NASA had announced that the first Americans on the moon would land in one of five three-by-five-mile landing areas selected by NASA's Apollo Site Selection Board. Each of the areas would satisfy criteria in which astronaut safety was the paramount consideration. The first two sites selected by NASA were in the Sea of Tranquility, the third was in the Central Bay, and the fourth and fifth were in the Ocean of Storms. The sites were selected from eight under study from a choice of 30 original sites. Selection of the five permitted scientists and engineers to concentrate on fewer areas in preparing data on the specific sites. The site selection


board studied material obtained by unmanned Lunar Orbiters and soft-landing Surveyor spacecraft. Lunar Orbiter returned high resolution photographs of all the sites and Surveyor provided close-up photos and surface data of the general areas in which they were located. The criteria considered by the board included smoothness of the area, desirability in terms of amount of propellant necessary for the lunar module propulsion systems, lighting as it concerned the best visibility by astronauts, and the general slope of the landing area.

Mississippi Test Facility began the month of March 1968, with considerable test activity. S-IC-2 arrived at MTF on March 1. It had been assembled nearby at the Michoud Assembly Facility. Upon arrival of the booster at MTF, workmen promptly began preparations for placing it

391. Stage at base of
S-IC stand at MTF

391



*392. S-IC firing, MTF*


in a test stand for a static firing in late April. In addition, S-II-4 would be placed in a separate test stand, where it would undergo a newly incorporated cryogenic proof pressure test late in March. This test would call for the LH_2 tank to be filled with cryogenic propellant and pressurized to simulated maximum flight loads. It would be a test designed to assure high reliability of Saturn V second stages and would be scheduled for all proposed manned Saturn V vehicle second stages. Meanwhile, at MTF preparations proceeded for placing a fifth S-II second stage in another test stand at MTF on March 7, where it would undergo similar cryogenic proof pressure tests in April before static testing.⁵⁰³

MSFC announced on March 7 the award of an \$11.1 million contract extension until February 28, 1969, to Sperry Rand Corporation for engineering support in applied research, testing, and design at MSFC's Astrionics Laboratory.⁵⁰⁴

393. AS-502 mission sequence


394a. Installation of S-IC-6 in test stand at MTF, b. Installation of S-II-5 into A-1 stand at MTF

393




Dr. von Braun commented on March 12: "If AS-502 is successful, there will be no need for a third unmanned Saturn V flight."⁵⁰⁵

394 a.



b.



NASA announced on March 12 that Chrysler Corporation had received a contract modification totalling \$5, 779, 884 for ground support and engineering equipment related to the Saturn IB program. The contract, awarded by MSFC, covered services at Huntsville through December 1968. It was a cost-plus-fixed-fee agreement. Chrysler's assignment covered program integration management, test integration and engineering of ground support, operation of the Saturn IB Development (Breadboard) facility, logistics responsibility, and telemetry systems engineering. As a result of this March 12 contract, Chrysler's contract for ground support and engineering equipment now totaled \$14, 701, 868.⁵⁰⁶

By the middle of March all three static test stands at the Mississippi Test Facility were filled with Apollo/Saturn V flight stage for the first time. Two of the stands contained second stages for the fourth and fifth Apollo/Saturn V rockets. A third was holding the 7.5 million pound thrust booster that would lift the sixth Apollo/Saturn V off its KSC launch pad.⁵⁰⁷


SATURN ILLUSTRATED CHRONOLOGY

MSFC announced on March 18 that more than 100 engineers and scientists would participate in a two-day Saturn I workshop design review board meeting on the following two days at MSFC. The engineers would discuss results of previous workshop reviews including the original engineering design review in May 1967, a documentation study in December, and a week-long crew station review February 12-16 at MSFC. Meeting participants would represent the Manned Spacecraft Center, Kennedy Space Center, NASA Headquarters, and the McDonnell Douglas Corporation, manufacturer of the Saturn S-IVB stage. A workshop mockup had been used at MSFC for earlier design work. Chairman of the design review board was Leland Belew, manager of Marshall's Saturn/Apollo Applications Office.⁵⁰⁸

On March 19 NASA released the findings of the Investigating Board appointed to examine and report on the June 8, 1967, rupture of a test tank at MSFC in Huntsville which resulted in the deaths of two employees of Brown Engineering Company of Huntsville, a NASA subcontractor. NASA's release said in essence that the rupture of the test tank was apparently caused by pressure which exceeded the tank limits. The tank which ruptured was on loan to MSFC from the McDonnell Douglas Corporation. It was to have been used to test a quick-release manhole cover designed by MSFC for the liquid hydrogen tank of the S-IVB. The board concluded that the tank burst at a pressure between 60 and 67 psig (pounds square inch gauge). The tank had withstood a pressure of 60 psig in a test conducted on May 24, two weeks before the accident. The investigation disclosed a misunderstanding concerning the tank received from McDonnell Douglas. A blueprint supplied by McDonnell Douglas was interpreted as indicating the tank had been designed to withstand 150 psig. In fact, the tank in the form received at MSFC had a design limit of only 50.7 psig.⁵⁰⁹

NASA decided during the third week in March that a second unmanned flight of the lunar module

395. S-1B-6 in preparation to ship area at Michoud



would not be necessary. The first manned LM flight would be made later in the year, launched by a Saturn V vehicle. The decision to cancel the repeat flight of an unmanned LM followed a detailed evaluation of the first LM flight, flown January 22 atop a Saturn IB launch vehicle. Data from a comprehensive examination of the LM's structural and ground test results were also thoroughly analyzed.⁵¹⁰

Workmen at MTF conducted a cryogenic proof test of the S-II-4 stage on March 23. The purpose of the test was to certify the integrity of the S-II stage's LH_2 tank. Evaluation of early data indicated that the test was successful. The stage was put through this important pressure test by a team from NAR, manufacturer of the stage for MSFC. Engineers filled the stage with about 273,000 gallons of super-cold liquid hydrogen (at -423°F .) and pressurized the tank five percent above the expected maximum flight pressure. Preliminary readings indicated that the liquid hydrogen tank pressure during the test was 36.18 psig. Instrument calibration checks were conducted to verify the results of the test. Liquid nitrogen was used in the liquid oxygen tank. The

SATURN ILLUSTRATED CHRONOLOGY

tank was filled to approximately 80 percent of capacity with 65,000 gallons of nitrogen and pressurized to normal flight pressure. This was the first cryogenic proof test conducted in the S-II program. All S-II stages scheduled to be used on manned launch vehicles would undergo the cryogenic proof test at MTF to further certify the structural capability of the stage. The S-II-4 stage was the first of the so-called lightweight stages, being about 3,000 pounds lighter than the first three.⁵¹¹

The schedule for launch of the AS-502 vehicle slipped 13 days during March, primarily because of a problem with the A7-64 propellant disconnect. Two days of slippage were attributed to problems with the S-II-2 stage.⁵¹²

On March 28 MSFC decided that "it would be in the best interest" of the space program to transfer S-IC and S-IB stage procurement responsibilities from the Michoud Assembly Facility to Huntsville.⁵¹³

The countdown demonstration test for AS-502 (Apollo 6), scheduled to be launched April 4, was completed March 31.⁵¹⁴

By the end of March, 11 S-IVB stages had been delivered to Kennedy Space Center/MSFC (Dynamics stage, S-IVB-500F Facility Checkout Stage, S-IVB-500-ST MSFC stage simulator, S-IVB-201 through S-IVB-204, S-IVB-206, and S-IVB-501 through S-IVB-503N).

MSFC began April 1, 1968, with announcement of the following contract awards: \$2.1-million contract modification to RCA for continued support of RCA 110A computers for use in checkout and launch of Saturn IB and Saturn V launch vehicles, bringing total contract value to \$12.7 million; and \$1.8-million follow-on contract to Sanders Associates, Inc., to provide logistics and engineering support to Saturn V operational display systems at MSFC, bringing total value of the contract to \$3.9 million.⁵¹⁵

On April 3 MSFC awarded IBM's Space Guidance Center a \$1.3 million contract for spare parts and logistic support of instrument units that guided Saturn IB and Saturn V launch vehicles.⁵¹⁶

NASA successfully launched Apollo 6 (AS-502) from KSC's Complex 39A at 7:00 a.m. (EST) on a mission to qualify the Saturn V launch vehicle for future manned space flights. Primary objectives were to demonstrate structural and thermal integrity and compatibility of launch vehicle and spacecraft; confirm launch loads and dynamic characteristics; demonstrate S-II/S-IC and S-IVB/S-II stage separations; verify operation of propulsion (including S-IVB restart), guidance and control (optimum injection), and electrical systems; evaluate performance of Emergency Detection System (EDS) in closed-loop configuration; and demonstrate mission support facilities and operations required for launch, mission conduct, and CM recovery.⁵¹⁷ The launch vehicle second-stage performance was near nominal, but two of the five second-stage J-2 engines shut down prematurely, causing the remaining second- and third-stage engines to burn longer than planned.⁵¹⁸ As a result, the spacecraft and third stage entered elliptical parking orbit with 223.1-mile (395.1-kilometer) apogee, 107-mile (172.1-kilometer) perigee. When the third stage failed to re-ignite on command after two orbits as planned, NASA switched to an alternate mission, firing the Service Propulsion System (SPS) to place the spacecraft into trajectory with a 13,823-mile (22,225.4-kilometer) apogee.⁵¹⁹ Since insufficient propellant remained after the extended burn, a second SPS burn was not attempted and the CM reentered at 22,376 miles per hour, just under the planned 25,000-mile-per-hour rate. The spacecraft splashed down 50 miles off target in the Pacific Ocean 9 hours 50 minutes after launch and was recovered in good condition by the U.S.S. Okinawa. Preliminary assessment indicated that four of the five objectives were attained, even though the launch vehicle performance of the S-IVB restart and guidance control (optimum injection) were not fully successful.⁵²⁰

SATURN ILLUSTRATED CHRONOLOGY

During the second week in April MSFC completed a report containing preliminary results of the Apollo 6 flight. Although the basic source of the difficulties had not yet been determined, scientists and engineers speculated that wires carrying cutoff commands to the malfunctioning engines were interchanged. The first stage had performed as planned and stage thrust was near that predicted during the first portion of flight. The second stage had performed satisfactorily through the first-stage boost, second-stage ignition, and early portion of second-stage powered flight. First indications of anomaly were the decreasing temperatures on the main oxidizer valve and its control line on the fifth engine and steady decrease in second engine's yaw actuator pressure. The third stage performed satisfactorily through the first burn and orbital coast. Although engine and stage prestart conditions had appeared normal, the engine receiving the start signal and the valves opening properly, the engine did not restart. Initial data suggested that a leak in one of the two propellant lines to the engine's augmented igniter may have caused insufficient or inadequately mixed propellant for the proper start condition. Investigations were continuing on longitudinal oscillation of the vehicle. Guidance and other instrumentation functions, telemetry performance, and onboard TV camera operation were satisfactory. An intensive evaluation of ground systems support during the AS-502 launch indicated no major problem areas, although many areas reported nominal launch damage, typical for such a blast-off. Considerable damage, and not typical, involved both Mobile Launchers (ML) elevators in the Apollo Emergency Ingress/Egress System (PAD & ML). The damage occurred at ignition and/or during liftoff.⁵²¹

A technical review of Saturn launch vehicles, attended by about 140 scientists, engineers, and administrators, was held at MSFC April 20-21. The participants investigated the status and flight schedule of Saturn launch vehicles.⁵²²

The S-IU-205 Unit was loaded aboard the Super Guppy at MSFC on the morning of April 10; however, weather conditions delayed the departure of the Super Guppy from MSFC for KSC until the following morning. The Unit arrived at KSC on April 11, and offloading of the stage from the Super Guppy was completed that same morning.⁵²³

By the middle of April SA-205 had been erected at the launch facility at KSC. Also, by the middle of April the AS-503 Launch Vehicle was stacked in the VAB at Kennedy Space Center.⁵²⁴


Michoud personnel gave an April 22 S-IC program briefing at Michoud to newly appointed Deputy Administrator for NASA, Dr. Thomas O. Paine, along with Dr. von Braun, General O'Connor, and other NASA representatives.⁵²⁵

The 11th Saturn IB booster (S-IB-11) was successfully fired by Chrysler on April 23 at MSFC's Test Laboratory. The 1.6 million-pound-thrust booster was test-fired for a planned 145 seconds. The booster would be returned to the Michoud Assembly Facility the following month for a post-static check. Meanwhile, another booster (S-IB-12) was en route to MSFC by barge for static firing at MSFC.⁵²⁶

NASA announced on April 27 that the AS-503 launch vehicle would be manned and that the launch would be scheduled for the fall. The manned flight would occur in the fourth quarter of 1968. Two previous flights of the Saturn V had been unmanned. But on the basis of data thus far obtained from the second unmanned flight, on April 4, NASA decided to plan and work toward a manned flight with the third Saturn V vehicle. "However, we will retain the option of flying another unmanned mission if further analysis and ground testing indicate that it is the best course," said Maj. Gen. Samuel C. Phillips, Apollo program director. Before NASA made its decision, NASA and industry engineers worked virtually around the clock to determine the causes, effects, and

SATURN ILLUSTRATED CHRONOLOGY

396




396. Apollo 8 lunar mission sequence, orbital mission (AS-503)

solutions of several problems experienced in the April 4 flight. These included: premature shutdown of two J-2 engines in the second stage (S-II) of the Saturn V; failure of the third stage J-2 engine to re-ignite in orbit; a longitudinal oscillation or "pogo effect" caused by synchronous vibration of the five F-1 engines in the first stage; and an indication that some material fell away from the area of the spacecraft/lunar module adapter. Information developed by the time of the NASA April 27 announcement indicated that the early shutdown of the two second stage engines began with the failure of a small fuel line in the Number 2 engine ignition system. "We are confident that we know the cause, effects, and solutions involving the J-2 engine failure and the launch vehicle longitudinal vibration problems," said Gen. Phillips. "Analysis and ground testing will continue to achieve an even more complete understanding of all aspects of Saturn V performance and operation."⁵²⁷


397. Saturn V achievements
398. Saturn V
399. Saturn V major contractors

398




397

SATURN V ACHIEVEMENTS



On April 29 NASA awarded a \$25.8-million, one-year, cost-plus-fee contract to Bendix Field Engineering Corporation for continued maintenance and operation of the major portion of NASA's Manned Space Flight Network, including 11 facilities of the 14-station unified 8-band network for Apollo. The contract extended the original two-year agreement.⁵²⁸

399




PRECEDING PAGE BLANK NOT FILMED

ACKNOWLEDGMENTS

Various personnel have contributed generously to the preparation of this chronology. In the past eleven years, first one organization and then another has had a variety of responsibility for its preparation. Therefore, seekers of more detailed information may well appreciate the names of people who have contributed to various versions. At MSFC Mr. Robert Sampson of Research and Development Operations and Mr. Harold Price of Industrial Operations were pioneers in preparing the chronology's early versions. Later Mrs. Evelyn Falkowski, Mrs. Rowene Dunlap, Miss Ruth Jarrell, Mrs. Lois Ford, Mrs. Betty Davis, and Mr. Leo L. Jones, all of Management Services Office, Historical Office, have helped much in either writing, editing, or researching for the document. Of help throughout has been Mr. Bill Ziak of the Scientific and Technical Information Division, Management Services Office. For other assistance, including layout, we are also indebted to personnel of RCA, support contractor for Management Services Office. These people most closely identified with the project are Miss Teresita Sellers, Mrs. Kay Parrish, Mrs. Pat Vidler, Mr. Dan Wise, and Mr. Fagan Thompson. Of unusual assistance in preparing the 1968 edition has been Mrs. Ann Henley, editor at RCA. Much credit for the Index, that appears for the first time in this 1968 edition, must go to Mrs. Henley and also to MSFC summer student, Miss Rosemary Zarsous, who spent much of the summer of 1970 working on it.

PRECEDING PAGE BLANK NOT FILMED

APPENDIX A. SATURN MISSIONS



PROPOSED MISSIONS

- APOLLO SPACECRAFT DEVELOPMENT
ORBITAL QUALIFICATION OF COMPLETE SPACECRAFT
LEM QUALIFICATION
RE-ENTRY AND RECOVERY
- APOLLO SPACECRAFT ORBITAL MANEUVERS
- APOLLO CREW TRAINING IN LM RENDEZVOUS AND DOCKING
- ADVANCE LARGE BOOSTER TECHNOLOGY IN SUPPORT OF SATURN V
- DEVELOPMENT AND TESTING OF LH₂ & LOX STAGE(S-IVB) FOR SATURN V
- LARGE SCIENTIFIC SATELLITE PAYLOADS (UP TO 40,000 LBS)

SATURN V LAUNCH VEHICLE

CHARACTERISTICS

TOTAL LENGTH 363 FT
WT. AT LIFTOFF 6,400,000 LBS
PAYLOAD APPROX
ESCAPE 100,000 LBS
EARTH ORBIT 285,000 LBS


STAGES

FIRST STAGE (S-IC) 33 X 138 FT
ENGINE (LOX & RP-1) 5 F-1
THRUST 501 THRU 503 7,500K LBS
S04 AND SUB 7,610K LBS

MIDDLE STAGE (S-IV) 33 X 81 FT
ENGINE (LOX & LH₂) 5 J-2
THRUST 501 THRU 503 1,125K LBS
S04 AND SUB 1,150K LBS

UPPER STAGE (S-IVB) 22 X 59 FT
ENGINE (LOX & LH₂) 1 J-2
THRUST 501 THRU 503 225K LBS
S04 AND SUB 230K LBS

INSTRUMENT UNIT 22 X 11 FT



PROPOSED MISSION

EARTH ESCAPE


- APOLLO MANNED LUNAR LANDING
- CIRCULUNAR FLIGHT
- LUNAR LOGISTICS
- PLANETARY PROBES

EARTH ORBITAL

- MANNED SPACE STATIONS
- MULTI-MISSION UNMANNED SCIENTIFIC SATELLITES
- EQUATORIAL ORBITS
- SYNCHRONOUS ORBITS
- POLAR ORBITS


APPENDIX B. SATURN CHARACTERISTICS

SATURN I LAUNCH VEHICLE




CHARACTERISTICS	
LAUNCH VEHICLE	
LENGTH	124 FT
WEIGHT AT LIFTOFF	1,139,000 LBS
PAYLOAD CAPACITY	22,500 LBS
STAGES	
S-I	
SIZE	21.5 X 80 FT
THRUST	1,500,000 LBS
ENGINES	8 H-1
PROPELLANT	LOX & RP-1
S-IV	
SIZE	18.3 X 41 FT
THRUST	90,000 LBS
ENGINES	6 RL10
PROPELLANT	LOX & LH ₂
INSTRUMENT UNIT	
SIZE	12.8 X 3 FT
GUIDANCE SYSTEM	INERTIAL
TOTAL LENGTH	
(INCLUDING SPACECRAFT & LES)	190 FT

SATURN IB LAUNCH VEHICLE






CHARACTERISTICS	
LENGTH (VEHICLE)	142 FT
LENGTH (VEHICLE, SPACECRAFT, LES)	224 FT
WEIGHT AT LIFTOFF	1,297,000 LBS
EARTH ORBIT PAYLOAD	40,000 LBS
STAGES	
FIRST (S-IB)	
SIZE	21.5 X 80 FT
ENGINES	8 H-1
THRUST (201 THRU 203)	1,600,000 LBS
(206 AND SUB)	1,640,000 LBS
PROPELLANT	LOX & RP-1
SECOND (S-IVB)	
SIZE	22 X 59 FT
ENGINE	1 J-2
THRUST (201 THRU 207)	200,000 225,000 LBS
(208 AND SUB)	205,000 230,000 LBS
PROPELLANT	LOX & LH ₂
INSTRUMENT UNIT	
SIZE	22 X 3 FT
GUIDANCE SYSTEM	INERTIAL

SATURN V LAUNCH VEHICLE




CHARACTERISTICS	
LENGTH VEHICLE	281 FT
LENGTH VEHICLE, SPACECRAFT, LES	363 FT
WEIGHT AT LIFTOFF	6,400,000 LBS
PAYLOAD CAPABILITY APPROXIMATE	
TRANS LUNAR TRAJECTORY	100,000 LBS
EARTH ORBIT	285,000 LBS
STAGES	
FIRST (S-IC)	
SIZE	33 X 138 FT
ENGINES	5 F-1
THRUST (501 THRU 503)	7,500,000 LBS
(504 AND SUB)	7,610,000 LBS
PROPELLANTS	LOX & RP-1
SECOND (S-II)	
SIZE	33 X 81 FT
ENGINES	5 J-2
THRUST (501 THRU 503)	1,125,000 LBS
(504 AND SUB)	1,150,000 LBS
PROPELLANTS	LOX & LH ₂
THIRD (S-IVB)	
SIZE	22 X 59 FT
ENGINE	1 J-2
THRUST (501 THRU 503)	225,000 LBS
(504 AND SUB)	230,000 LBS
PROPELLANTS	LOX & LH ₂
INSTRUMENT UNIT	
SIZE	22 X 3 FT
GUIDANCE SYSTEM	INERTIAL

APPENDIX C. SATURN MAJOR CONTRACTORS



APPENDIX D. LAUNCH SUMMARY

SATURN I LAUNCH SUMMARY



RESEARCH AND DEVELOPMENT FLIGHTS

- SA-1 1. LAUNCHED OCT. 27, 1961
2. S-I STAGE PROPELLSION SYSTEM TEST FLIGHT
- SA-2 1. LAUNCHED APR. 29, 1962
2. PROJECT HIGHWATER NEPA
- SA-3 1. LAUNCHED NOV. 16, 1962
2. 2ND PHASE PROJ. HIGHWATER
3. FULL PROPELLANT LOADING
- SA-4 1. LAUNCHED MAR. 28, 1963
2. ENGINE OUT CAPABILITY DEMONSTRATION
- SA-5 1. FIRST BLOCK II LAUNCHED JAN. 22, 1964
2. FIRST LIVE S-IV STAGE AND NO. 1 ENGINE
- SA-6 1. LAUNCHED MAY 28, 1964
2. FIRST ACTIVE GUIDANCE FLIGHT
3. FIRST FLIGHT APOLLO BOILER STEAMER
4. ENGINE OUT UNPLANNED


OPERATIONAL FLIGHTS

- SA-7 1. LAUNCHED SEPT. 16, 1964
2. COMPLETELY ACTIVE ST 124
- SA-9 1. LAUNCHED FEB. 16, 1965
2. FIRST PEGASUS METEOROID
3. FIRST UNPRESSURIZED INSTRUMENT
- SA-10 1. LAUNCHED MAY 15, 1965
2. ORBITED SECOND PEGASUS
- SA-11 1. LAUNCHED JULY 1, 1965
2. ORBITED THIRD PEGASUS
3. COMPLETED SATURN I PROGRAM

SATURN IB LAUNCH SUMMARY



- AS-201 1. LAUNCHED FEB. 26, 1966
2. SHORT LOB-LAUNCH VEHICLE AND CSM DEVELOPMENT
- AS-203 1. LAUNCHED JULY 5, 1966
2. ORBITAL LIQUID HYDROGEN EXPERIMENT
- AS-202 1. LAUNCHED AUG. 25, 1966
2. LONG LOB-LAUNCH VEHICLE AND CSM DEVELOPMENT
- AS-204 APOLLO 5
1. LAUNCHED JAN. 22, 1968
2. ORBITAL LUNAR MODULE DEVELOPMENT



APPENDIX E: SEQUENCE FOR SATURN V MANNED LUNAR VOYAGE

GLOSSARY

A

AA	Apollo Applications program
AAP	Apollo Applications Program
ABMA	Army Ballistic Missile Agency
AEC	Atomic Energy Commission
AEDC	Arnold Engineering Development Center
AEROJET	Aerojet General Corporation
AF	Air Force
All-Systems Vehicle	Non-flight stage used to checkout flight-worthiness of systems
AIAA	American Institute of Astronautics and Aeronautics
AMR	Atlantic Missile Range
AOMC	Army Ordnance Missile Command
Apollo	Project designation for manned lunar landing, also spacecraft for manned lunar landing
AS	Apollo/Saturn (Specific payload and vehicle with a number as AS-203)
ATM	Apollo Telescope Mount

B

Battleship Stage	Non-flight stage replica for engine tests
BP	Boilerplate

"Bug"	Lunar excursion module, landing unit of the Apollo Spacecraft
C	
C & SM	Command and Service Modules
C-1	Saturn C-1, early nomenclature for Saturn I
C-3	Saturn C-3, Saturn configuration considered but not used
C-5	Saturn C-5, configuration adopted for lunar landing Apollo flights (renamed Saturn V in February 1963)
C-IB	Saturn C-IB, vehicle selected in 1962 for manned earth orbital flights with full Apollo spacecraft (renamed Saturn IB)
Cape Canaveral	Launch site, name changed to Kennedy Space Center in 1963.
CCSD	Chrysler Corporation Space Division
CBTT	Common bulkhead test tank
Chance-Vought	Saturn tank manufacturer, Dallas, Texas
Centaur	Vehicle for support of unmanned moon probes and other missions
CM	Command Module
<u>Compromise</u>	Later changed to <u>Promise</u> - barge transporter for Saturn boosters
CPFF	Cost-plus-fixed-fee contract
CPIF	Cost-plus-incentive-fee contract

D

DAC	Douglas Aircraft Corporation
DOD	Department of Defense
Downey	S&ID S-II stage component fabrication and testing facility location
Douglas	Douglas Aircraft Corporation
Dyna Soar	Air Force spacecraft for earthn orbital flight featuring "glider re-entry"
DX rating	Highest national priority

E

EDS	Emergency Detection System
EFL	Edwards Field Laboratory
ESE	Electrical Support Equipment
EST	Eastern Standard Time

F

FAA	Federal Aviation Agency
Fairchild Stratos	Meteoroid satellite contractor
F-1 Engine	Saturn V booster (S-IC stage) engine
FRT	Flight Rating Tests

G

GSE	Ground Support Equipment
-----	--------------------------

H

H-1 Engine	Saturn I booster (S-I stage) engine
High Water Project	SA-2 and SA-3 flight experiment in which water from the Dummy second stage was released into the ionosphere.
Huntington Beach	DAC S-IVB assembly facility in California

I

IBM	International Business Machine Corporation
IO	MSFC Industrial Operation organization
IU	Instrument Unit

J

J-2	Liquid hydrogen engine for S-IVB and S-II stages
JPL	Jet Propulsion Laboratory

K

K	Thousands of pounds of thrust
KSC	Kennedy Space Center, was Cape Canaveral until November 28, 1963.
Kiwi-B	Nuclear reactor

L

LaRC	Langley Research Center
LC	Launch Complex

LH ₂	Liquid hydrogen
LM	Lunar Module
LN	Liquid Nitrogen
LOC	Launch Operations Center
LOX	Liquid Oxygen
Lockheed	Lockheed Aircraft Company
LR-115	First Liquid hydrogen type engine (Pratt & Whitney), early designation of RL 10-A3 engine.
LR-119	Proposed uprated LR-115 engine (project was cancelled)
LSSM	Local Scientific Survey Module
LTV	Ling-Temco-Vought
LV	Launch Vehicle
LVDC	Launch Vehicle Digital Computer
M	
McDonnell Douglas Corporation	Douglas Aircraft Company merged with McDonnell Aircraft Corporation, April 1967, to become McDonnell Douglas Corporation
MAF	Michoud Assembly Facility (formerly Michoud Operations)
Martin	Martin Company
ME	MSFC's Manufacturing Engineering Laboratory

Michoud	NASA's Michoud Operations
Minneapolis-Honeywell	Minneapolis-Honeywell Incorporated name changed to Honeywell Incorporated
ML	Mobile Launcher
MSC	Manned Spacecraft Center
MSFC	George C. Marshall Space Flight Center
MSS	Mobile Service Structure
MSTS	Military Sea Transport Service
MTF	Mississippi Test Facility (at one time MTO) in Hancock County, Mississippi
N	
NAA	North American Aviation, Inc.
NAR	North American Rockwell Corporation (name resulting from merger of NAA, Inc. and Rockwell-Standard Corp., Sept. 22, 1967)
NASA	National Aeronautics and Space Administration
NERVA	Nuclear engine for RIFT stage
NOVA	Moon direct flight vehicle deferred in favor of Saturn V
P	
P&VE	Propulsion and Vehicle Engineering Laboratory at MSFC
PCS	Pointing control system

Pegasus

Meteoroid detection satellite

PFRT

Preliminary Flight Rating Test

P&W

Pratt & Whitney Company

R

R&D

Research and Development

RCA

Radio Corporation of America

Rocketdyne

Division of North American Aviation

RIFT

Reactor-in-flight test stage (nuclear power)

RP-1

A kerosene-type fuel

RL10-A3

Reactor-in-flight test stage (nuclear power)

S

S&ID

Space and Information Systems Division of North American Aviation

SA

Saturn (with number signifies a specific vehicle as SA-501) that does not have the Apollo command module attached.

S-I

Saturn I originally Saturn C-1 first stage

S-II

Saturn V second stage

S-IVB

Saturn V third stage

S-IC

Saturn V first stage

S-IV

Saturn I second stage

SACTO	Douglas Aircraft's Sacramento Test Facility
Santa Susana	Test Site for S-II and S-IVB stage and J-2 engine
Santa Monica	Douglas Aircraft's fabrication facility at Santa Monica, California
Saturn I	A two-stage vehicle, with eight H-1 engines propelling first stage and six RL-10 engines propelling second stage
Saturn IB	A two-stage vehicle with eight H-1 engines propelling first stage and a single J-2 engine propelling second stage
Saturn V	A three stage vehicle, with five F-1 engines propelling first stage, five J-2 engines propelling second stage, and a single J-2 engine propelling third stage
Seal Beach	North American Aviation Assembly plant at Seal Beach, California
SLCC	Saturn Launch Control Computer
Slidell	A computer center that serves Michoud in Slidell, La.
SM	Service Module
SPS	Service Propulsion System
SRM	Solid Rocket Motor
SSFL	Santa Susana Field Laboratory
SSO	Saturn Systems Office
Sverdrup Parcell Company	Mississippi Test Facility design contractor

U

Upgraded Saturn

Nomenclature used for S-IB for a short period of time.

V

VAB

Vertical Assembly Building

VCL

Vehicle Checkout Laboratory

PRECEDING PAGE BLANK NOT FILMED

REFERENCES

1. ABMA TO DOD, "Proposal: A National Integrated Missile and Space Vehicle Development Program," Dec. 10, 1957.
2. ARPA, ARPA Order 14-59, Aug. 15, 1958, p. 1.
3. AOMC, Quarterly Progress Report on ARPA Orders 14-59 and 47-59: For First Quarter CY 1959, Apr. 7, 1959.
4. ARPA, ARPA Order 47-59, Dec. 11, 1958.
5. U.S. Congress, House, Comm. on Science and Astronautics, Hearing on H. R. 9675, 86th Cong., 2d Sess., Washington, GPO, 1960, testimony of Mr. Roy W. Johnson.
6. MSFC, Project Saturn: Development and Funding Plan FY - 1961, July 1, 1960, p. 2. Hereafter cited as MSFC, Saturn D & F Plan FY 61.
7. Eugene M. Emme, Aeronautics and Astronautics: An American Chronology of Science and Technology in the Exploration of Space: 1915-1960 (Washington: NASA HHR-3, 1961), p. 109. Hereafter cited as Emme, Aeronautics and Astronautics, 1915-1960.
8. AOMC, Semiannual Technical Summary Report on ARPA Orders 14-15 and 47-59 from 1 July - 31 December 1959, Feb. 15, 1960, p. 2.
9. MSFC, Saturn D & F Plan FY 61, p. 2.
10. President Dwight D. Eisenhower, Exec. Order 10870, Mar. 15, 1960.
11. Emme, Aeronautics and Astronautics, 1915 - 1960, p. 121.
12. David S. Akens, MSFC Historian, Historical Origins of Marshall Space Flight Center, Dec. 1960, p. 63.
13. ABMA Historical Office, History of Army Ballistic Missile Agency: 1 January - 30 June 1960.

14. Morton J. Stoller, Asst. Dir. for Satellite and Sounding Rocket Programs, NASA, "The U. S. National Aeronautics and Space Administration's Space Flight Program," Sept. 12, 1960, pp. 4-5.
15. Emme, Aeronautics and Astronautics: 1915-1960, p. 129.
16. MSFC Saturn Systems Office, Saturn Quarterly Progress Report (January - March 1961), May 8, 1961, p. 42. Hereafter cited as MSFC SSO, Saturn QPR, Jan. - Mar. 61.
17. MSFC SSO, Saturn QPR, Jan. - Mar. 61, p. 37-38.
18. MSFC SSO, Saturn QPR, Jan. - Mar. 61, p. 32 and 66.
19. MSFC SSO, C-1 Development Plan, p. 139.
20. MSFC SSO, Saturn QPR, Jan. - Mar. 61, p. 42.
21. MSFC Test Division, Test Division's Contributions to Saturn Semiannual Technical Report (January 1 through June 30, 1961), unpub. rpt., pp. 16-17.
22. MSFC SSO, Saturn QPR, Apr. - June 61, p. 25.
23. MSFC SSO, Saturn QPR, Apr. - June 61, p. 25.
24. MSFC SSO, Saturn QPR, Apr. - June 61, p. 26.
25. MSFC SSO, Saturn QPR, Apr. - June 61, p. 63.
26. MSFC SSO, Saturn QPR, Apr. - June 61, p. 38.
27. MSFC Historical Office, History of the George C. Marshall Space Flight Center, July - December 31, 1961, p. 29. Hereafter cited as MSFC Hist. Office, Hist. of Geo. C. Marshall Space Flight Center, July 1 - Dec. 31, 1961.
28. MSFC SSO, Saturn QPR, July - Sept. 61, p. 11.

29. MSFC SSO, Saturn QPR, July - Sept. 61, p. 9.
30. MSFC SSO, Saturn QPR, July - Sept. 61, p. 2.
31. MSFC SSO, Saturn QPR, July - Sept. 61, pp. 94-96.
32. MSFC SSO, Saturn QPR, July - Sept. 61, p. 49.
33. MSFC Test Division, "Test Division's Historical Report: July 1, 1961 - December 31, 1961," p. 1, in Volume Two of this report (Supporting Documents). Hereafter cited as MSFC Test Div., "Test Division Hist. Report, July 1 - Dec. 31, 1961.
34. NASA News Release 61-236, Oct. 25, 1961.
35. NASA News Release 61-242, Oct. 31, 1961.
36. Propulsion Project Office, P&VE Division, MSFC, to Chief, Engine Mgmt. Off., P&VE Div., MSFC, memo, subj.: "Weekly Report of Significant Events," Nov. 11, 1961.
37. Interview with Joe M. Jones, PIO, MSFC, Feb. 8, 1962.
38. MSFC Test Div., "Test Division's Hist. Report, July 1 - Dec. 31, 1961." in Volume Two of this report (Supporting Documents), p. 1.
39. Col. W. Scott Fellows, Chief, Nuclear Vehicle Proj. Off., MSFC, "The RIFT Program" (Draft), Jan. 25, 1962, p. 1.
40. MSFC Press Release, Dec. 15, 1961.
41. MSFC Press Release, Dec. 15, 1961.
42. NASA News Release 62-4, Jan. 10, 1962.
43. MSFC SSO, Saturn QPR, Jan. - Mar. 62, p. 4.
44. MSFC SSO, Saturn QPR, Jan. - Mar. 62, p. 35.
45. MSFC SSO, Saturn QPR, Jan. - Mar. 62, p. 23.

46. MSFC SSO, Saturn QPR, Jan. - Mar. 62, pp. 10-11; MSFC Test Div., "Test Division Hist. Report, Jan. 1 - June 30, 1962," p. 1.
47. MSFC SSO, Saturn QPR, Jan. - Mar. 62, p. 27.
48. MSFC SSO, Saturn QPR, Jan. - Mar. 62, p. 38.
49. MSFC SSO, Saturn QPR, Jan. - Mar. 62, p. 4.
50. MSFC SSO, Saturn Monthly Progress Report (April 12, 1962 - May 12, 1962) p. 5. Hereafter cited as MSFC SSO, Saturn MPR, Apr. 12 - May 12, 1962, p. 5.
51. MSFC SSO, Saturn MPR, Apr. 12 - May 12, 1962, pp. 12-13; May 14 - June 12, 1962, p. 11.
52. MSFC SSO, Saturn QPR, Jan. - Mar. 62, p. 38.
53. NASA, Priorities and Requirements Branch, to All Field Installations, letter, subj.: "Apollo Program Priority," Apr. 18, 1962.
54. Dr. Kurt Debus, NASA LOD Dir., to Dir., MSFC, et al., teletype, subj.: "Post Firing Report, Saturn Vehicle SA-2," Apr. 25, 1962; MSFC SSO, Saturn MPR, Apr. 12 - May 12, 1962, pp. 2-3; MSFC P&VE Div., Saturn SA-2 Data Book, SA-2 Flight Report Supplement (MTP-P&VE-E-61-5), May 11, 1962; MSFC, Chief Vehicle Systems Integration Office to Distribution, memo, subj.: "Saturn SA-2 Flight Report Supplement," May 11, 1962.
55. MSFC Test Div., Test Division Monthly Progress Report, May 12, 1962 - June 12, 1962, p. 1. Hereafter cited as MSFC Test Div., Test Division MPR, May 12 - June 12, 1962.
56. MSFC Test Div., Test Division MPR, May 12 - June 12, 1962, p. 1.
57. Claude J. Bowen, MSFC SSO, interviewed June 13, 1962.
58. MSFC SSO, Saturn MPR, May 14 - June 12, 1962, p. 12.
59. MSFC Test Div., Test Division Hist. Report, Jan. 1 - June 30, 1962," p. 1.

60. Dr. Wernher von Braun, Director, MSFC, "Statement before Subcommittee on Manned Space Flight, Committee on Science and Astronautics, House of Representatives," Mar. 18, 1963.
61. NASA News Release, July 11, 1962.
62. MSFC Test Div. , Test Division MPR, July 12 - Aug. 12, 1962, p. 1
63. MSFC Sat. Office, Summary of C-5 Development Plan, Jan. 15, 1963, p. 42.
64. MSFC Test Div. , Test Division MPR, July 12 - Aug. 12, 1962, p. 12.
65. MSFC Michoud Operations, Historical Report, Michoud Operations, July 1, 1962 - December 31, 1962. Hereafter cited as MSFC Michoud Op. , Hist. Report, July 1 - Dec. 31, 1962.
66. MSFC Sat. Off. , Saturn MPR, July 13 - Aug. 13, 1962, p. 13.
67. MSFC Test Div. , Test Division MPR, Aug 12- Sept. 12, 1962, pp. 10-11.
68. MSFC Sat. Off. , Saturn MPR, Sept. 15 - Oct. 15, 1962, p. 3.
69. MSFC Sat. Off. , Saturn MPR, Aug. 14 - Sept. 14, 1962, p. 12.
70. MSFC Sat. Off. , Saturn MPR, Nov. 12 - Dec. 14, 1962, p. 1.
71. MSFC Sat. Off. , Saturn MPR, Sept. 15 - Oct. 15, 1962, p. 11.
72. MSFC Sat. Off. , Saturn MPR, Sept. 15 - Oct. 15, 1962, pp. 5-6.
73. MSFC Press Release, Oct. 5, 1962.
74. MSFC Sat. Off. , Saturn MPR, Sept. 15 - Oct. 15, 1962, p. 9.
75. MSFC Sat. Off. , Summary of C-5 Development Plan, Jan. 15, 1963, p. 43.
76. Dr. Wernher von Braun, Director, MSFC, "Statement before Subcommittee on Manned Space Flight, Committee on Science and Astronautics, House of Representatives," Mar. 18, 1963.

77. MSFC Sat. Off. , Saturn MPR, Sept. 15 - Oct. 15, 1962, p. 4.
78. MSFC Sat. Off. , Saturn MPR, Nov. 12 - Dec. 14, 1962, p. 5.
79. MSFC Sat. Off. , Saturn MPR, Nov. 12 - Dec. 14, 1962, p. 3.
80. MSFC Sat. Off. , Saturn MPR., Oct. 16 - Nov. 12, 1962, p. 6.
81. MSFC P&VE Division, "Saturn SA-3 Flight Report Supplement," Dec. 7, 1962; Dr. Kurt H. Debus, Dir. , LOC, to Dir. , MSFC, teletype, Nov. 16, 1962; MSFC Sat. Off. , Saturn MPR, Oct. 16 - Nov. 12, 1962, p. 3.
82. MSFC Sat. Off. , Saturn MPR, Nov. 12 - Dec. 14, 1962, p. 10.
83. MSFC Sat. Off. , Saturn MPR, Dec. 15 - Jan. 16, 1963, p. 5.
84. S. F. Morea, MSFC, P&VE Division, interviewed Mar. 28, 1963.
85. MSFC Test Div. , Test Division MPR, Dec. 12, 1962 - Jan. 12, 1963, p. 2.
86. MSFC Sat Off. , Saturn MPR, Jan. 17 - Feb. 15, 1963, p. 7.
87. MSFC Sat. Off. , Saturn MPR, Jan. 17 - Feb. 15, 1963, p. 3.
88. MSFC Test Div. , Test Division MPR, Jan. 12 - Feb. 12, 1963, p. 3;
MSFC Sat Off. , Saturn MPR, Jan. 17 - Feb. 15, 1963, p. 6.
89. MSFC Test Div. , Test Division MPR, Feb. 12 - Mar. 12, 1963, p. 6.
90. MSFC Press Release, Feb. 8, 1963.
91. MSFC Sat. Off. , Saturn MPR, Jan. 17 - Feb. 15, 1963, p. 10.
92. MSFC Sat. Off. , Saturn MPR, Jan. 17 - Feb. 15, 1963, p. 10.
93. MSFC Sat. Off. , Saturn MPR, Jan. 17 - Feb. 15, 1963, p. 6; Feb 16 - Mar. 18, 1963, p. 6; MSFC Test Div. , Test Division MPR, Feb. 12 - Mar. 12, 1963, p. 3.

94. John Chambers, Saturn I/IB Stage Manager, MSFC Saturn Systems (Sat.) Office, interviewed on Sept. 19, 1963; and MSFC Sat. Off., Saturn MPR, Feb. 16 - Mar. 18, 1963, p. 8.
95. MSFC Sat. Off., Saturn MPR, Feb. 16 - Mar. 18, 1963, p. 9.
96. MSFC Sat. Off., Saturn MPR, Feb. 16 - Mar. 18, 1963, p. 3.
97. MSFC P&VE Division, Engine Management Office Monthly Progress Report, February 16 - March 15, 1963, p. 1. Hereafter cited as MSFC P&VE Division, Engine Management Office MPR, Feb. 16 - Mar. 15, 1963, p. 1.
98. MSFC P&VE Division, Engine Management Office MPR, Feb. 16 - Mar. 15, 1963, p. 1.
99. MSFC Sat. Off., Saturn MPR, Feb. 16 - Mar. 18, 1963.
100. MSFC Sat. Off., Saturn MPR, Feb. 16 - Mar. 18, 1963, p. 4; Mar. 19 - Apr. 15, 1963, p. 3.
101. MSFC Sat. Off., Saturn MPR, Feb. 16 - Mar. 18, 1963, p. 8; Mar. 19 - Apr. 15, 1963, p. 8.
102. MSFC Sat. Off., Saturn MPR, Mar. 19 - Apr. 15, 1963, pp. 2-3.
103. MSFC Test Div., Test Division MPR, Mar. 12 - Apr. 12, 1963, p. 6.
104. MSFC Sat. Off., Saturn MPR, Apr. 16 - May 17, 1963, p. 2; May 18 - June 17, 1963, p. 3.
105. MSFC Test Div., Test Division MPR, May 12 - June 12, 1963, p. 2.
106. MSFC Test Div., Test Division MPR, May 12 - June 12, 1963, pp. 5-7; MSFC Sat. Off., Saturn MPR, Mar. 19 - Apr. 15, 1963, p. 6; MSFC P&VE Div., MPR for May 12 - June 11, 1963, pp. 63-64; MSFC Sat. Off., Saturn MPR, Apr. 16 - May 17, 1963, p. 5.
107. MSFC Test Div., Test Division MPR, Apr. 12 - May 12, 1963, pp. 4-5; May 12 - June 12, 1963, p. 5.

108. MSFC Sat Off. , Saturn MPR, Mar. 19 - Apr. 15, 1963, p. 4; Apr. 16 - May 17, 1963, p. 4.
109. MSFC P&VE Div. , Engine Management Office MPR, June 16 - July 15, 1963, pp. 15-16.
110. NASA, NASA Administrator's Progress Report, June 1963, p. E-12.2, and July 1963, p. E-12.2.
111. Wilbur S. Davis, Chief, Procurement and Contracts Office, MSFC, to Harry H. Gorman, Deputy Director for Administration, MSFC, memo, subj.: "Report of Activities for Week Ending May 31, 1963," May 31, 1963, MSFC Test Div. , Test Division MPR, June 12 - July 12, 1963, p. 22.
112. MSFC Sat. Off. , Saturn MPR, May 18 - June 17, 1963, p. 3.
113. MSFC Sat. Off. , Saturn MPR, May 18 - June 17, 1963, p. 7.
114. MSFC Sat. Off. , Saturn MPR, May 18 - June 17, 1963, p. 3; June 18 - July 17, 1963, p. 4.
115. MSFC Sat. Off. , Saturn MPR, June 18 - July 17, 1963, p. 3.
116. MSFC Sat. Off. , Saturn MPR, July 18 - Aug. 14, 1963, p. 3.
117. MSFC Sat. Off. , Saturn MPR, June 18 - July 17, 1963, p. 7.
118. MSFC Sat. Off. , Saturn MPR, July 18 - Aug. 14, 1963, p. 5.
119. MSFC Sat. Off. , Saturn MPR, July 18 - Aug. 14, 1963, pp. 2-3.
120. MSFC Test Lab. , Test MPR, July 12 - Aug. 12, 1963, p. 2.
121. MSFC Sat. Off. , Saturn MPR, July 18 - Aug. 14, 1963, p. 8.
122. MSFC Sat. Off. , Saturn MPR, July 18 - Aug. 14, 1963, pp. 2-3.

123. Dr. Wernher von Braun, Director, MSFC, to Distribution "B," memo, subj.: "Reorganization Study - Announcement No. 2," Aug. 12, 1963; Dr. Wernher von Braun, Director, MSFC to All MSFC Employees, memo, subj.: "Reorganization Study - Announcement No. 3," Aug. 30, 1963.
124. MSFC Test Lab., Test MPR, Sept. 12 - Oct. 12, 1963, p. 23.
125. MSFC Sat. Off., Saturn MPR, Aug. 15 - Sept. 18, 1963, p. 7.
126. MSFC Sat. Off., Saturn MPR, Aug. 14 - Sept. 18, 1963, p. 9; Sept. 19 - Oct. 20, 1963, p. 8.
127. MSFC Sat. Off., Saturn MPR, Dec. 16, 1963 - Jan. 16, 1964, p. 9; Sept. 19 - Oct. 20, 1963, p. 11.
128. MSFC Sat. Off., Saturn MPR, Sept. 19 - Oct. 20, 1963, p. 2.
129. MSFC Michoud Ops., Hist. Report, July 1 - Dec. 31, 1963, pp. 1,13, and 22.
130. MSFC Quality Lab., Hist. Data, July 1 - Dec. 31, 1963.
131. MSFC Test Lab., Acceptance Firing of Saturn Flight Stage S-1-7, Jan. 22, 1964, pp. 1 and 7-11.
132. MSFC Test Lab., Test MPR, Oct. 16 - Nov. 15, 1963, p. 6.
133. NASA, NASA Administrator's Progress Report, September 1963, p. E-20.2; MSFC Engine Project Office, Engine Monthly Progress Report, Oct. 16 - Nov. 15, 1963, p. 6. Hereafter cited as MSFC Engine Project Office, Engine MPR, Oct. 16 - Nov. 15, 1963.
134. NASA, NASA Administrator's Progress Report, October 1963, p. B-6.3; MSFC Sat. Off., Saturn MPR, Oct. 21 - Nov. 15, 1963, p. 2.
135. MSFC P&VE Lab., Monthly Progress Report for Period December 12, 1963 through January 11, 1964, p. 35. Hereafter cited as MSFC P&VE Lab., MPR for Dec. 12 - Jan. 11, 1964.
136. MSFC Test Lab., Test MPR, Nov. 12 - Dec. 12, 1963, pp. 31-32.

137. MSFC Sat. Off., Saturn MPR, Nov. 16 - Dec. 12, 1963, pp. 5-6; MSFC Engine Project Office, H-1 Engine Project Development Plan, Dec. 1, 1963, pp. 33-38.
138. MSFC P&VE Lab., MPR for Nov. 12 - Dec. 11, 1963, p. 61.
139. NASA Launch Operations Center, Launch Operations Center Progress Report, Nov. 19, 1963, p. 12.
140. U. S. Congress, House, Comm. on Science and Astronautics, Authorizing Appropriations to the National Aeronautics and Space Administration, 88th Congress, 2d Sess., Rpt. No. 1240, Washington, GPO, 1964, p. 15.
141. Chrysler Corporation Space Division (CCSD), Sixth Quarterly Review, Saturn S-1/1B Stage - Saturn I/IB Vehicle Program, Dec. 5, 1963, p. J. M. L. -2.
142. MSFC Sat. Off., Saturn MPR, Nov. 16 - Dec. 15, 1963, p. 6.
143. MSFC Sat. Off., Saturn MPR, Dec. 16, 1963 - Jan. 16, 1964, p. 6.
144. MSFC Test Lab., Test MPR, Nov. 12 - Dec. 12, 1963, p. 8.
145. MSFC Michoud Op., Hist. Report, July 1 - Dec. 31, 1963, pp. 16-17.
146. NASA, NASA Administrator's Progress Report, December 1963, p. B-12.2
147. MSFC Test Lab., Test MPR, Dec. 12, 1963 - Jan. 12, 1964, p. 29.
148. Dr. Kurt Debus, Chairman, Investigating Committee, report, "S-IV All Systems Stage Incident - January 24, 1964," May 11, 1964, J. B. Gayle, P&VE Lab., MSFC, "Investigation of S-IV All Systems Vehicle Explosion," Apr. 27, 1964, pp. 1.3; MSFC Sat. Off., Saturn MPR, Dec. 16, 1963 - Jan. 16, 1964, pp. 1 and 5.
149. MSFC P&VE Lab., Saturn SA-5 Vehicle Data Book, Flight Report Supplement, p. VI-1.
150. MSFC Saturn Flight Evaluation Working Group, Results of the Fifth Saturn I Launch Vehicle Test Flight (MPR-SAT-FE-64-15), Apr. 1, 1964, p. 5.

151. MSFC Sat. Off. , Saturn MPR, Feb. 16 - Mar. 16, 1964, p. 4.
152. MSFC P&VE Lab. , SA-9 Saturn Vehicle Data Book, pp. V-1 and V-5; D. P. Herd and R. W. Schock, P&VE Lab. , MSFC, Micrometeoroid Separation and Ejection Test of Apollo Boiler Module BP-9, July 13, 1964.
153. DAC, Saturn S-IVB Annual Technical Progress Report, July 1963 - June 1964, pp. 36-37 and 95-96. Hereafter cited as DAC, Saturn S-IVB Annual TPR, July 1963 - June 1964.
154. MSFC Sat. Off. , Saturn MPR, Jan. 16 - Feb. 16, 1964, p. 8.
155. MSFC Test Lab. , Hist. Report, Jan. 1 - June 30, 1964, pp. 6-7.
156. MSFC Engine Project Office, MPR, F-1, H-1, J-2, and RL10 Engines, Feb. 1964, p. 3.
157. MSFC Test Lab. , Hist. Report, Jan. 1 - June 30, 1964, p. 1.
158. MSFC Test Lab , Test MPR, Feb. 12 - Mar. 12, 1964, p. 38; MSFC Saturn I/IB Program Office, Saturn I/IB Progress Report, March 16 - September 30, 1964, p. 1. Hereafter cited as MSFC Saturn I/IB Prog. Off. , Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964.
159. MSFC Sat. Off. , Saturn MPR, Feb. 16 - Mar. 16, 1964, p. 6; Lee Cropp, MSFC Industrial Operations, Draft of "Saturn I, IB, and V Quarterly Progress Report, April, May, and June 1964," p. 10; DAC, Saturn S-IVB Annual TPR, July 1963 - June 1964, p. 148.
160. MSFC Sat. Off. , Saturn MPR, Feb. 16 - Mar. 16, 1964, pp. 2 and 6.
161. Garland G. Buckner, Chief, Purchasing Office, MSFC, to H. H. Gorman, Deputy Director, Administrative, MSFC, memo, subj. : "Report of Activities for Week Ending, January 24, 1964," Jan. 24, 1964, and "Report of Activities for Week Ending February 7, 1964," Feb. 7, 1964; MSFC Press Release, Mar. 31, 1964.
162. MSFC Saturn I/IB Prog. Off. , Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, p. 19.
163. MSFC Sat Off. , Saturn MPR, Feb. 16 - Mar. 16, 1964, p. 7.

164. MSFC Sat. Off., Saturn MPR, Feb. 16 - Mar. 16, 1964, p. 11.
165. KSC Press Release, Apr. 2, 1964.
166. MSFC Saturn I/IB Prog. Off., Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, p. 6.
167. MSFC Executive Staff, Managerial Data Center, Management Information, Volume IX, Sept. 1964, p. 2.
168. Lee Cropp, MSFC Industrial Operations, Draft of "Saturn I, IB, and V Quarterly Progress Report, April, May, and June 1964," p. 1; MSFC Saturn I/IB Prog. Off., Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, p. 19; MSFC Michoud Op., Hist. Report, Jan. 1 - June 30, 1964, p. 2
169. MSFC Press Release, Apr. 14, 1964.
170. MSFC Press Release, Apr. 20, 1964.
171. MSFC Engine Project Office, Engine QPR, April - June 1964, p. 32.
172. MSFC Saturn I/IB Prog. Off., Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, pp. 3-5; MSFC P&VE Lab., SA-6 Vehicle Data Book, Flight Report Supplement, pp. VI-1 - VI-19; MSFC P&VE Lab., Evaluation of Flight Test Propulsion Systems and Associated Systems, Saturn Vehicle SA-6, Aug. 28, 1964, pp. 1-5 and pp. 156-164; E. R. Matthews, Saturn I Project Office, KSC, to Office of Manned Space Flight, NASA, et al., teletype, subject.: "SA-6 Saturn/Apollo Flash Report No. 1," May 28, 1964.
173. MSFC P&VE Lab., Saturn SA-6 Vehicle Data Book, Flight Report Supplement, p. VI-1.
174. MSFC P&VE Lab., Evaluation of Flight Test Propulsion Systems and Associated Systems, Saturn Vehicle SA-6, Aug. 28, 1964, pp. 1-5 and pp. 156-164.
175. MSC, "Weekly Activity Report, June 7-13, 1964," to Office of Associate Administrator, Manned Space Flight, NASA, p. 3; MSFC Saturn I/IB Prog. Off., Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, p. 6.

176. MSFC Saturn I/IB Prog. Off., Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, pp. 14-15.
177. MSFC Engine Project Office, Engine QPR, Apr. - June 1964, p. 21.
178. Lee Cropp, MSFC Industrial Operations, Draft of "Saturn I, IB, and V Quarterly Progress Report, April, May, and June 1964," p. 1; MSFC Saturn I/IB Prog. Off., Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, p. 19; MSFC Michoud Op., Hist. Report, Jan. 1 - June 30, 1964, p. 2.
179. MSFC Hist. Office, Hist. of Geo. C. Marshall Space Flight Center, July 1 - Dec. 31, 1964, p. 27.
180. MSFC Saturn I/IB Off., Saturn I/IB MPR, Mar. 16 - Sept. 30, 1964, p. 7.
181. C. E. Catlado, P&VE Lab., H-1 Engine LOX Dome Failure, NASA TM X-53220, pp. 1-4; Apollo Program Management Off., KSC, to Apollo Program Director, NASA, teletype, subj.: "SA-7 Launch Schedule," July 17, 1964, and Manager, Apollo Spacecraft Program Off., NASA, to KSC, subj.: "SA-7 Launch Schedule," July 22, 1964.
182. Don Adams, CCSD, Saturn Stages S-1-10 Final Static Test Report, pp. 1-2; MSFC Test Lab., Hist. Report, July 1 - Dec. 31, 1964, pp. 1-2.
183. MSFC Saturn I/IB Off., Saturn I/IB Monthly Prog. Report, Mar. 16 - Sept. 30, 1964, pp. 13-14.
184. MSFC Michoud Op., Hist. Report, July 1 - Dec. 31, 1964, pp. 2 and 10; Saturn I/IB Off., Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, pp. 19-21.
185. MSFC Saturn I/IB Off., Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, p. 21.
186. DAC, Saturn S-IVB Monthly Technical Progress Report, July 1964, p. 33. Hereafter cited as DAC, Saturn S-IVB Monthly TPR, July 1964.
187. MSFC Hist. Office, Hist. of Geo. C. Marshall Space Flight Center, July 1 Dec. 31, 1964, p. 33.

188. KSC, Technical Progress Reports, Third and Fourth Quarter, CY 1964, p. 4; Lee B. James, Saturn I/IB Project Off., to Dr. Wernher von Braun, et al., memo, subj.: "Pegasus Schedule," Dec. 15, 1964.
189. George E. Mueller, Assoc., Adm. for Manned Space Flight, NASA, to NASA Adm., letter, subj.: "Saturn I Development Flight Test, SA-7," Sept. 14, 1964, with enc., "Mission Operation Report," Rpt. M-931-67-07, p. 1; F. A. Speer, Chairman, MSFC Saturn Flight Evaluation Working Group, "Saturn SA-7 Flight Resume."
190. MSFC Saturn I/IB Off., Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, p. 29; DAC, Saturn S-IVB Monthly TPR, Sept. 1964, pp. 129 and 136.
191. MSFC Engine Prog. Off., Semiannual Progress Report, F-1, H-1, J-2, C-1, and RL10 engines, July 1 - Dec. 31, 1965, Mar. 15, 1966, p. 19.
192. North American Aviation, Space and Information System Division, Saturn S-II Stage Monthly Progress Report, October 1964, p. 33. Hereafter cited as NAA S&ID, S-II Stage MPR, Oct. 1964, p. 33.
193. Don Adams, CCSD, Saturn Stage S-1-10 Final Static Test Report, pp. 1-2; MSFC Test Lab., Hist. Report, July 1 - Dec. 31, 1964, pp. 1-2.
194. MSFC Saturn I/IB Off., Saturn I/IB Prog. Report, Mar. 16 - Sept. 30, 1964, pp. 21 and 30; MSFC Michoud Op., Hist. Report, July 1 - Dec. 31, 1964, p. 12; M. Johnson, Chief, Program Control Off., MSFC, to Dir., Apollo Program Control Off., NASA, teletype, subj.: "Weekly Notes, Saturn I/IB," Jan. 4, 1965.
195. MSFC Industrial Operations, Engine Project Office, Quarterly Progress Report, F-1, H-1, J-2, and RL10 Engines, July, August, and September, 1964, pp. 11-12. Hereafter cited as MSFC Industrial Operations, Engine Project Off., QPR, F-1, H-1, J-2, and RL10 Engines, July, Aug., and Sept. 1964.
196. MSFC Saturn Flight Evaluation Working Group, Results of the Seventh Saturn I Launch Vehicle Test Flight, (MPR-SAT-FE-64-17), Nov. 25, 1964, p. 250.

197. MSFC Test Lab., Test Lab, MPR, Nov. 12 - Dec. 13, 1964, pp. 37-38; W. L. Fowler, S-IV Stage Project Engineer, P&VE Lab., Fifth Flight Vehicle, S-IV-8.
198. Minutes of Meeting, Project Pegasus Review, Aug. 19, 1964 and Oct. 26, 1964; Raymond L. Bisplinghoff, Assoc. Adm. for Advanced Research and Technology, NASA, to Assoc. Adm. for Manned Space Flight, memo, subj.: "Qualification of Capacitor Detectors for Pegasus Spacecraft," Oct. 23, 1964; George E. Mueller, Assoc., Adm. for Manned Space Flight to Dr. Wernher von Braun, Dir., MSFC, Nov. 25, 1964, letter; Lee B. James, Saturn I/IB Project Office, to Dr. Wernher von Braun, et al., memo, subj.: "Pegasus Schedule," Dec. 15, 1965.
199. MSFC P&VE Lab., MPR for Dec. 12 - Jan. 11, 1964, p. 48; MSFC Saturn V Office, Saturn V Quarterly Progress Report, July 1 - September 30, 1964, pp. 4-5, and October 1 - December 31, 1964, p. 7. Hereafter cited as MSFC Saturn V Off., Saturn V QPR, July 1 - Sept. 30, 1964.
200. MSFC Test Lab., Test Lab. MPR, Nov. 12 - Dec. 12, 1964, pp. 37-38; W. L. Fowler, S-IV Project Engineer, P&VE Lab., Fifth Flight Vehicle, S-IV-8.
201. MSFC Saturn V Off., Saturn V QPR, Oct. 1 - Dec. 31, 1964, p. 16.
202. DAC, Saturn S-IVB Monthly TPR, Dec. 1964, p. 63; Saturn V Off., Saturn V QPR, Oct. 1 - Dec. 31, 1964, p. 16.
203. MSFC Saturn Off., Saturn V QPR, Oct. 1 - Dec. 31, 1964, p. 16; DAC, Saturn S-IVB Monthly TPR, Dec. 1964, pp. 1-2 and 45-46.
204. MSFC P&VE Lab., MPR for Nov. 12 - Dec. 11, 1964, p. 48; MSFC Saturn V Off., Saturn V QPR, Oct. 1 - Dec. 31, 1964, p. 7.
205. Boeing, Saturn S-IC Quarterly Technical Progress Report, October 2, 1964 - December 31, 1964, p. 115.
206. NAA S&ID, Saturn S-II Stage MPR, Dec. 1964, pp. 25-26, and 39.
207. NASA, MSFC, The Meteoroid Satellite Project Pegasus First Summary Report, NASA TN D-3505, Nov. 1966, p. 4-6.

208. MSFC, Michoud Assembly Facility Historical Report, January 1, 1965 - June 30, 1965, pp. 7 and 23. Hereafter cited as MSFC, MAF Hist. Report Jan. 1 - June 30, 1965.
209. KSC, Technical Progress Report, First Quarter CY 1965, pp. 9-13.
210. MSFC, MAF Hist. Report, Jan. 1 - June 30, 1965, pp. 10-14.
211. U. S. Congress, House, Subcommittee on Manned Space Flight of the Comm. on Science and Astronautics, Hearing on H. R. 12718 (Superceded by H. R. 14324) No. 4- Part 2, 89th Cong., 2d Sess., Washington, GPO, Feb. 18, 24; Mar. 1, 2, 3, and 31, 1966.
212. MSFC, MAF Hist. Report, Jan. 1 - June 30, 1965, p. 6.
213. NAA S&ID, Saturn S-II Stage MPR, Feb. 1965, p. 39.
214. MSFC, Mississippi Test Facility Historical Report, January - December 1965, pp. 1 and 9-13.
215. DAC, Saturn S-IVB Monthly TPR, Feb. 1966, p. 2.
216. NASA MSFC, The Meteoroid Satellite Project Pegasus First Summary Report, NASA TN D-3505, Nov. 1966, pp. 42-60.
217. F. A. Speer, Chairman, Flight Evaluation Working Group, MSFC, to Dr. G. E. Mueller, Assoc., Adm, NASA, et al., teletype, subj.: "SA-9 Flight Results," Feb. 19, 1965; Speer to Mueller, subj.: "SA-9 Flight Result," Feb. 26, 1965.
218. MSFC, MAF Hist. Report, Jan. 1 - June 30, 1965, pp. 5 and 23.
219. MSFC Saturn I/IB Prog. Off., Saturn I/IB Prog. Report, Oct. 1, 1964 - Mar. 31, 1965, pp. 5 and 23.
220. MSFC Saturn I/IB Prog. Off., Saturn I/IB Prog. Report, Oct. 1, 1964 - Mar. 31, 1965, pp. 11.
221. MSFC, MAF Hist. Report, Jan. 1 - June 30, 1965, pp. 5 and 23.
222. MSFC Press Release No. 65-43, Feb. 16, 1965.

- 223. MSFC, MAF Hist. Report, Jan. 1 - June 30, 1965, p. 6.
- 224. MSFC, MAF Hist. Report, Jan. 1 - June 30, 1965, pp. 5 and 23.
- 225. IBM Space Systems Center, Saturn I U Program Plan, Apr. 5, 1966, pp. 1.1 - 1.2
- 226. MSFC Industrial Operations, Engine Program Office, QPR, F-1, H-1, J-2, and RL10 Engines, January, February, and March, 1965, Mar. 15, 1965, pp. 15-16.
- 227. Maj. Gen. Samuel C. Phillips, Dir., Apollo Program Off., NASA, to MSFC, Attn. Stan Reinartz, Saturn IB/Centaur Program Mgr., teletype, Apr. 7, 1965.
- 228. MSFC Test Lab., Hist. Report, Jan. - Dec. 1965, pp. 7-8.
- 229. MSFC Test Lab., Hist. Report, Jan. 1 - Dec. 31, 1965, p. 1; Systems Static Test Branch, CCSD, Saturn S-IB Stage Final Static Test Report, S-IB-1, June 4, 1965, pp. 1-2.
- 230. MSFC Saturn V Prog. Off., Saturn V QPR, April - June 1965, p. 15.
- 231. NAA S&ID, S-II Stage MPR, Apr. 1965, p. 36.
- 232. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. - June 1965, p. 21; MSFC Sat. V Prog. Off., "Saturn V Weekly Report No. 18," May 10, 1965.
- 233. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. - June 1965, p. 15.
- 234. MSFC Saturn Flight Evaluation Working Group, Results of the Ninth Saturn I Launch Vehicle Test Flight SA-8 (MPR-SAT-FE-66-10), June 13, 1966, pp. 1-6, 8-9, 14-15, 19-30, and 91-97; William M. Bland, Jr., Chief, Checkout and Test Division, MSC, to NASA Headquarters, Attn: R. R. Gilruth, et al., teletype, subj.: "Apollo Mission A-104 (SA-8) Flight Report," May 28, 1965.
- 235. L. F. Belew, Mgr., Engine Prog. Off., MSFC, paper, "Apollo Vehicle Propulsion Systems," AIAA Annual Meeting, July 26-29, 1966, Paper 65-303; Engine Prog. Off., Semiannual Progress Report, July - December 1965, p. 30.

236. MSFC Saturn V Prog. Off. , Saturn V QPR, July - Sept. 1965, p. 42.
237. MSFC Saturn V Prog. Off. , Saturn V QPR, Apr. - June 1965, p. 21.
238. Rocco A. Petrone, Dir. , Plans, Programs, and Resources, KSC, to Col. Lee B. James Saturn I/IB Program Mgr. , MSFC, teletype, subj.: "Possible Interference of Scheduled Launch Date of SA-10 with that of GT-5," June 10, 1965; Kurt H. Debus, Dir. , KSC, to Dr. George E. Mueller, Assoc. Adm. , Office of Manned Space Flight, subj.: "Possible Interface of Launch Schedules," June 11, 1965; Maj. Gen. Samuel C. Phillips, Dir, Apollo Program Office, NASA, to Dr. Wernher von Braun, Dir. , MSFC, subj.: "Reschedule of SA-10 Launch, "June 21, 1965.
239. MSFC P&VE Lab. , MPR, June 1 - 30, 1965, p. 49.
240. Maj. Gen. Samuel C. Phillips, Dir. , Apollo Program, NASA to E. Betram, KSC, et al. , teletype, subj.: "AFETR CW Radar Standardization, June 28, 1965; and Azusa/Mistram," June 28, 1965.
241. MSFC Saturn V Prog. Off. , Saturn V QPR, July - Sept. 1965, p. 26; Saturn V Prog. Off. , "Saturn V Weekly Report, No. 26," July 7, 1965.
242. MSFC Saturn V Prog. Off. , Saturn V QPR, July - Sept. 1965, p. 23.
243. MSFC Test Lab. , Hist. Report, Jan. 1 - Dec. 31, 1965, pp. 1-2.
244. MSFC Saturn V Prog. Off. , Saturn V QPR, July - Sept. 1965, p. 18.
245. MSFC Test Lab. , Hist. Report, Jan. 1 - Dec. 31. 1965, pp. 1-2.
246. MSFC, Saturn Flight Evaluation Working Group, Results of the Tenth Saturn I Launch Vehicle Test Flight SA-10, July 14, 1966, (MPR-SAT-FE-66-11), pp. 5-9.
247. DAC, Saturn S-IVB Monthly TPR, July 1965, p. 48.
248. Belew, AIAA Paper 65-303, pp. 12-14; MSFC, Engine Prog. Off. , Semi-annual Progress Report, July - December 1965, pp. 21-23.

249. MSFC Saturn V Prog. Off. , Saturn V QPR, July - Sept. 1965, pp. 26-27; MSFC Test Lab. , Hist. Report, Jan. 1 - Dec. 31, 1965, Addendum, pp. 1-3.
250. MSFC Test Lab. , Hist. Report, Jan. - Dec. 1965, pp. 7-8.
251. NASA Hist. Off. , Astronautics and Aeronautics, 1965, Chronology on Science, Technology, and Policy, SP-4006, p. 373. Hereafter cited as NASA Hist. Off. , Astronautics and Aeronautics, 1965.
252. MSFC Saturn V Prog. Off. , Saturn V QPR, July - Sept. 1965, p. 18.
253. MSFC Saturn V Prog. Off. , Saturn V QPR, July - Sept. 1965, p. 40.
254. MSFC Saturn V Prog. Off. , Saturn V QPR, July - Sept. 1965, p. 26; MSFC Saturn V Prog. Off. , "Saturn V Weekly Report No. 32," Aug. 23, 1965.
255. MSFC Saturn V Prog. Off. , Saturn V QPR, July - Sept. 1965, p. 26; MSFC Saturn V Prog. Off. , "Saturn V Weekly Report No. 32," Aug. 23, 1965.
256. DAC, Saturn S-IVB Monthly TPR, Sept. 1965, p. 38.
257. DAC, Saturn S-IVB Monthly TPR, Sept. 1965, p. 38.
258. MSFC Saturn I/IB Prog. Off. , Saturn I/IB Prog. Report, Oct. 1, 1964 - Mar. 31, 1965, p. 1; IBM, Saturn Instrument Unit Mission Monthly Progress Report for September, pp. 1, 7, 22, and 30.
259. MSFC Test Lab. , Addendum to Test Lab. Hist. Report, Jan. 1 - Dec. 31, 1965, pp. 1-3.
260. MSFC Saturn V Prog. Off. , Saturn V QPR, Oct. - Dec. 1965, pp. 15 and 17; NAA, S&ID, S-II Stage MPR, Sept. 1965, p. 41.
261. MSFC Saturn V Prog. Off. , Saturn V QPR, Oct. - Dec. 1965, p. 34.
262. MSFC Saturn Flight Evaluation Working Group, Results of the First Saturn IB Launch Vehicle Test Flight AS-201 (MPR-SAT-FE-66-8), May 6, 1966, p. 13.

263. MSFC Test Lab. , Hist. Report, Jan. - Dec. 1965, pp. 8-9. N. C. Milwee, Manufacturing Engineering Lab. , MSFC, "Quarterly Report, July - Sept. 1965," (draft) .
264. MSFC Saturn V Prog. Off. , Saturn V QPR, Oct. - Dec. 1965, p. 17.
265. Systems Static Test Branch, CCSD, Saturn S-IB Stage Final Static Test Report, Stage S-IB-3, pp. 3-5.
266. MSFC P&VE Lab. , MPR, Oct. 1-31, 1965, p. 19; MSFC Press Release No. 65-259, Oct. 28, 1965.
267. DAC, Saturn S-IVB Monthly TPR, Oct. 1965, p. 33.
268. DAC, Saturn S-IVB Monthly TPR, Nov. 1965, pp. 39-40.
269. MSFC Saturn V Prog. Off. , Saturn V QPR, Oct. - Dec. 1965, p. 14.
270. DAC, Saturn S-IVB Monthly TPR, Nov. 1965, pp. 39-40.
271. MSFC Saturn Flight Evaluation Working Group, Results of the First Saturn IB Launch Vehicle Test Flight AS-201 (MPR-SAT-FE-66-8), May 6, 1966, p. 13; MSFC P&VE Lab. , MPR, Dec. 1-31, 1965, Supplement, pp. 1-3.
272. Belew, AIAA Paper 65-303; MSFC Engine Prog. Off. , Semiannual Prog. Report, July - Dec. 1965, p. 30.
273. DAC, Saturn S-IVB Monthly TPR, December 1965, pp. 35-36 and 41.
274. MSFC Test Lab. , Hist. Report, Jan. - Dec. 1965, pp. 8-9.
275. MSFC Press Release No. 66-2 and No. 66-3, Jan. 4, 1966.
276. MSFC Press Release No. 66-4 and No. 66-8, Jan. 7, 1966.
277. MSFC Engine Prog. Off. , Semiannual Prog. Report, July - Dec. 1965, p. 21.
278. MSFC Saturn V Prog. Off. , Saturn V QPR, Oct. 1 - Dec. 31, 1965, p. 34; MSFC Saturn V Flight Evaluation Working Group, Results of the First Saturn IB Launch Vehicle Test Flight AS-201 (MPR-SAT-FE-66-8), p. 13.

279. Exec. Off. of the President, Report to the Congress from the President of the United States, 1965, p. 12.
280. MSFC Press Release No. 66-1, Jan. 3, 1966.
281. NASA Hist. Office, Astronautics and Aeronautics, 1966, p. 16.
282. MSFC Saturn V Prog. Off., Saturn V QPR, Jan. 1 - Mar. 31, 1966, pp. 12 and 38.
283. MSFC Saturn V Prog. Off., Saturn V QPR, Jan. 1 - Mar. 31, 1966, pp. 18, 25, and 39.
284. MSFC Saturn V Prog. Off., Saturn V QPR, Jan. 1 - Mar. 31, 1966, p. 18.
285. MSFC Saturn V Prog. Off., Saturn V QPR, Jan. - Mar. 31, 1966, p. 38.
286. MSFC Press Release No. 66-39, Feb. 15, 1966.
287. MSFC Saturn V Prog. Off., Saturn V QPR, Jan. 1 - Mar. 31, 1966, p. 18.
288. MSFC Saturn V Prog. Off., Saturn V QPR, Jan. 1 - Mar. 31, 1966, p. 11.
289. MSFC, Saturn Flight Evaluation Working Group, Results of the First Saturn IB Launch Vehicle Test Flight AS-201, (MPT-SAT-FE-66-8), pp. 1-3.
290. MSFC Saturn V Prog. Off., Saturn V QPR, Jan. 1 - Mar. 31, 1966, p. 27.
291. MSFC, MAF Hist. Report, Jan. 1 - Dec. 31, 1966, p. 2.
292. MSFC Saturn Flight Evaluation Working Group, Results of the Third Saturn IB Launch Vehicle Test Flight AS-202 (MPR-SAT-FE-66-13), p. 16.
293. NASA Hist. Off., Astronautics and Aeronautics, 1966, SP-4007, p. 107.
294. MSFC, MAF Hist. Report, Jan. 1 - Dec. 31, 1966, p. 3.
295. MSFC Press Release No. 66-69, Apr. 1, 1966.

- 296. MSFC, MAF Hist. Report, Jan. 1 - Dec. 31, 1966, p. 3.
- 297. MSFC PAO, Marshall Star, Apr. 20, 1966, p. 1.
- 298. MSFC Press Release No. 66-83, Apr. 21, 1966.
- 299. MSFC Press Release No. 66-91, May 6, 1966.
- 300. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. 1 - June 30, 1966, p. 29.
- 301. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. 1 - June 30, 1966, p. 19.
- 302. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. 1 - June 30, 1966, p. 19.
- 303. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. 1 - June 30, 1966, pp. 19 and 46.
- 304. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. 1 - June 30, 1966, p. 29.
- 305. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. 1 - June 30, 1966, p. 19.
- 306. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. 1 - June 30, 1966, p. 14.
- 307. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. 1 - June 30, 1966, p. 6.
- 308. MSFC Press Release No. 66-142, June 30, 1966.
- 309. MSFC, MAF Hist. Report, Jan. 1 - Dec. 31, 1966, p. 4.
- 310. MSFC Saturn Flight Evaluation Working Group, Results of the Second Saturn IB Launch Vehicle Test Flight AS-203 (MPR-SAT-FE-66-12), pp. 1-2-3.
- 311. MSFC Saturn V Prog. Off., Saturn V QPR, Apr. 1 - June 30, 1966, p. 25.
- 312. MSFC Press Release No. 66-152, July 8, 1966.
- 313. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 56.

- 314. MSFC Saturn V Prog. Off. , Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 67.
- 315. MSFC MAF, Hist. Report. Jan. 1 - Dec. 31, 1966, p. 4.
- 316. MSFC Saturn V Prog. Off. , Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 54.
- 317. MSFC Press Release No. 66-182, Aug, 10, 1966.
- 318. NASA Hist. Office, Astronautics and Aeronautics, 1966, p. 272.
- 319. MSFC Saturn V Prog. Off. , Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 72.
- 320. MSFC Saturn Flight Evaluation Working Group, Results of the Third Saturn IB Launch Vehicle Test Flight AS-202, (MPR-SAT-FE-66-13), pp. 1-3.
- 321. NASA Hist. Off. , Astronautics and Aeronautics, 1966, p. 277.
- 322. MSFC Saturn V Prog. Off. , Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 26.
- 323. MSFC Saturn V Prog. Off. , Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, pp. 58 and 71.
- 324. MSFC, MAF Hist. Report, Jan. 1 - Dec. 31, 1966, p. 5.
- 325. MSFC Press Release No. 66-223, Sept. 29, 1966.
- 326. MSFC Saturn V. Prog. Off. , Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 28.
- 327. MSFC, MAF Hist. Report, Jan. 1 - Dec. 31, 1966, p. 5.
- 328. MSFC Saturn V Prog. Off. , Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 72.
- 329. MSFC Saturn V Prog. Off. , Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 30.
- 330. NASA Hist. Off. , Astronautics and Aeronautics, 1966, p. 350.

- 331. MSFC Press Release No. 66-276, Nov. 17, 1966.
- 332. MSFC Press Release No. 66-278, Nov. 21, 1966.
- 333. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 44.
- 334. MSFC Press Release No. 66-288, Nov. 30, 1966.
- 335. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 39.
- 336. MSFC Press Release No. 66-294, Dec. 13, 1966.
- 337. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July 1 - Dec. 31, 1966, p. 25.
- 338. MSFC, MAF Hist. Report, Jan. 1 - Dec. 31, 1966, p. 6.
- 339. MSFC Management Manual, Chapter 2-3-8, "Charter - S-II Special Task Team," Jan. 5, 1967, with attachments.
- 340. Memo, Bill H. Sneed, Chief, Saturn V Program Control Office, MSFC to Chief, Apollo Program Planning Office, NASA, "Saturn V Weekly Report No. 3," Jan. 17, 1967; and Saturn V Prog. Off., Semiannual Prog. Report, Jan. - June 1967, p. 76.
- 341. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 34.
- 342. DAC, S-IVB Quarterly Progress Report, Mar. 1967, pp. 3, 4, and 5.
- 343. NASA Hist. Off., Astronautics and Aeronautics, 1966, p. 383.
- 344. Interview with James B. McPeters, MSFC Contracts Office, July 22, 1970.
- 345. Don Adams, III, Systems Static Test Branch, Chrysler Corporation Space Division, Saturn S-IB Stage Final Static Test Report, Stage S-IB-9, April 11, 1967, p. 5.

346. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 52.
347. DAC, S-IVB Quarterly Progress Report, Mar. 1967, p. 4.
348. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, pp. 9 and 34; and PAO, Marshall Star, Vol. 7, No. 16, Jan. 11, 1967, pp. 1 and 4; and Vol. 7, No. 18, Jan. 25, 1967, p. 1.
349. A Chronology of the George C. Marshall Space Flight Center, Jan. 1 - Dec. 31, 1967, p. 5.
350. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 58; and Memo, Sneed to NASA Headquarters, "Saturn V Weekly Report, No. 5," Feb. 1, 1967.
351. DAC, S-IVB Quarterly Progress Report, Mar. 1967, p. 51.
352. DAC, S-IVB Quarterly Progress Report, Mar. 1967, p. 48.
353. DAC, S-IVB Quarterly Progress Report, Mar. 1967, p. 56.
354. NASA, Astronautics and Aeronautics, 1967, p. 24.
355. Interview with William D. Putnam, Special Staff, Office of Manned Spacecraft Flight, NASA Headquarters, Feb. 2, 1967.
356. DAC, S-IVB Quarterly Progress Report, Mar. 1967, p. 4.
357. MTF, Historical Report, Jan. 1 - Dec. 31, 1967, (draft); and Memo, Sneed to NASA Headquarters, "Saturn V Weekly Report, No. 8," Feb. 21, 1967.
358. MSFC Sat. V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 30.
359. MSFC Press Release No. 67-30, Feb. 3, 1967.
360. MTF, Historical Report, Jan. 1 - Dec. 31, 1967, (draft).
361. CCSD, S-IB-9 Stage Final Static Test Report, April 11, 1967, p. 1.; and Test Lab., MPR, Feb. 1967, p. 1.

362. S&ID, NAA, S-II Quarterly Progress Report, Jan. - Mar. 1967,
pp. IV-6 - IV-7.
363. MTF, Historical Report, Jan. 1 - Dec. 31, 1967, (draft); and
MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report,
Jan. - June 1967, p. 19.
364. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. -
June 1967, pp. 1-25.
365. CCSD, S-IB-9 Stage Final Static Test Report, April 11, 1967, p. 1.
366. DAC, S-IVB Quarterly Progress Report, Mar. 1967, pp. 5 and 47.
367. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. -
June 1967, p. 6.
368. MSFC Press Release No. 67-39, Feb. 28, 1967.
369. MTF, Historical Report, Jan. 1 - Dec. 31, 1967, (draft); and MSFC
Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June
1967, p. 19.
370. Test Lab., Monthly Progress Report, Mar. 1967, p. 19.
371. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. -
June 1967, p. 74.
372. NASA, Astronautics and Aeronautics, 1967, p. 81; and DAC, S-IVB
Quarterly Progress Report, Mar. 1967, p. 51.
373. Memo, E. F. O'Connor, Dir, IO, to Distribution C., subj., "Mis-
sissippi Test Facility," Mar. 20, 1967.
374. MAF, Historical Report, Jan. 1, 1967 - Dec. 31, 1967.
375. S&ID, NAA, S-II Quarterly Progress Report, Jan. - Mar. 1967,
p. II-16.
376. Memo, Dr. Wernher von Braun, MSFC Director, To Distribution D.,
subj., "Saturn I/IB Program Office Personnel Assignments," March 24,
1967.

377. TWX, Johnson to Phillips, "Saturn IB Weekly Notes 13-67," April 3, 1967.
378. S&ID, NAA, S-II Quarterly Progress Report, Jan. - Mar. 1967, pp. III-4 - III-5; and MTF, Historical Report, Jan. 1 - Dec. 31, 1967, (draft).
379. S&ID, NAA, S-II Quarterly Progress Report, April - June 1967, p. II-6.
380. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 33.
381. TWX, Johnson to Phillips, "Saturn I/IB Weekly Notes 13-67," April 3, 1967.
382. A Chronology of the George C. Marshall Space Flight Center, Dec. 31, 1967, p. 33.
383. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 23; and Boeing, Annual Prog. Report, FY 1967, p. 23.
384. MTF, Historical Report, Jan. 1 - Dec. 31, 1967 (draft); and S&ID, NAA, S-II Quarterly Progress Report, April - June 1967, p. III-1.
385. Memo, Bart J. Slattery, Chief, Public Affairs, MSFC to Distribution B., subj., "Implementation of Apollo and AAP Designations," April 6, 1967; and NASA, Astronautics and Aeronautics, 1967, p. 125.
386. MAF, Historical Report, Jan. 1, - Dec. 31, 1967, (draft), p. 4; and TWX, Johnson to Phillips, "Saturn IB Weekly Notes 14-67," April 10, 1967.
387. Don Adams, SSTB, CCSD, Saturn S-IB Stage Final Static Test Report, Stages S-IB-10, June 26, 1967, p. 3.
388. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 21.
389. DAC, S-IVB Quarterly Progress Report, June 1967, p. 57.
390. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 36; and S&ID, NAA, S-II Quarterly Progress Report, Jan. - Mar. 1967, p. III-3.

- 391. NASA, Astronautics and Aeronautics, 1967, p. 112.
- 392. Interview with Toon Ferrell, MSFC Engine Program Office, August 4, 1970.
- 393. MTF, Historical Report, Jan. 1 - Dec. 31, 1967, (draft).
- 394. William A. Geiger, Daily Log, Transport Branch, Projects Logistics Office, MSFC, April 27, 1967.
- 395. PAO, Press Release 67-94, April 27, 1967.
- 396. M. A. Page, Advanced Systems Office, MSFC, Study of Saturn IB Improvement Programs Executive Summary Report, TM X-53604, April 27, 1967, pp. 1 and 35.
- 397. Morton T. Eldridge, Marketing Manager of Army Land Combat Systems and NASA Advance Systems, McDonnell Douglas Astronautics Company, Huntsville, Alabama, September 17, 1970.
- 398. M. A. Page, Adv. Sys. Off., MSFC, Saturn IB Improvement Program, Executive Summary Report, April 1967, p. 2.
- 399. M. A. Page, Adv. Sys. Off., MSFC, Saturn IB Improvement Program, Executive Summary Report, April 1967, p. 2.
- 400. Edwin L. Riddick, Visitors Program Record, Protocol Branch, Public Affairs Office, MSFC, April 27-28, 1967.
- 401. Vivian S. Whitley, Visitors Program Record, Protocol Branch, Public Affairs Office, MSFC, May 2-5, 1967.
- 402. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 59.
- 403. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 59.
- 404. CCSD, S-IB-10 Stage Final Static Test Report, June 26, 1967, p. 1.
- 405. NASA, Astronautics and Aeronautics, 1967, p. 149.

406. PAO, Press Release No. 67-109, May 15, 1967.
407. MTF, Historical Report, Jan. 1 - Dec. 31, 1967, (draft): MAF, Historical Report, Jan. 1 - Dec. 31, 1967, p. 10; and Boeing, Annual Prog. Report, FY 1967, p. 23.
408. S&ID, NAA, S-II Quarterly Progress Report, April - June 1967, p. III-2; and Test Lab, Monthly Progress Report, May 1967, p. 3.
409. CCSD, S-IB-10 Stage Final Static Test Report, June 26, 1967, p. 1.
410. NASA, Astronautics and Aeronautics, 1967, p. 164.
411. Boeing, Annual Prog. Report, FY 1967, p. 24.
412. PAO, "Marshall Star" Vol. 7, No. 34, May 17, 1967.
413. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 9.
414. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 23.
415. CCSD, S-IB-10 Stage Final Static Test Report, June 26, 1967.
416. MAF, Historical Report, Jan. 1 - Dec. 31, 1967, p. 2.
417. MAF, Historical Report, Jan. 1 - Dec. 31, 1967, p. 4; and Test Lab., Monthly Progress Report, June 1967, p. 1.
418. PAO, "Marshall Star", Vol. 7, No. 38, June 14, 1967.
419. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 61.
420. NASA, Astronautics and Aeronautics, 1967, p. 189.
421. Saturn V Weekly Report No. 24, June 21, 1967.
422. A Chronology of the George C. Marshall Space Flight Center, Jan. 1 - Dec. 31, 1967, p. 50.

- 423. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, p. 25; and Boeing, Annual Prog. Report, FY 1967, p. 24.
- 424. NASA, Astronautics and Aeronautics, 1967, p. 193; and PAO, Press Release 67-130, June 26, 1967.
- 425. William A. Geiger, Daily Log, Transport Branch, Project Logistics Office, MSFC, June 23, 1967.
- 426. PAO, Press Release 67-139, 1967.
- 427. A Chronology of the George C. Marshall Space Flight Center, Jan. - Dec. 31, 1967, p. 53.
- 428. Paul Anderson, Contract NAS8-18741, Contracts Office, MSFC, June 30, 1967.
- 429. NASA, Astronautics and Aeronautics, 1967, p. 187.
- 430. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, pp. 50-51.
- 431. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, pp. 50-66.
- 432. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1967, pp. 68-72.
- 433. PAO, Press Release 67-147, July 11, 1967.
- 434. Saturn IB Weekly Notes 25-67, June 26, 1967.
- 435. S&ID, NAA, S-II Quarterly Progress Report, July - Dec. 1967, p. IV-2; and MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, p. 16.
- 436. Saturn V Weekly Report No. 26, July 12, 1967.
- 437. A Chronology of the George C. Marshall Space Flight Center, Jan. 1 - Dec. 31, 1967, p. 59.
- 438. PAO, Press Release No. 67-155, July 26, 1967.

439. NASA, Astronautics and Aeronautics, 1967, p. 220; and PAO "Marshall Star", Vol. 7, No. 45, p. 4.
440. Saturn V Weekly Report No. 30, August 3, 1967.
441. Memo, Harry H. Gorman, Dep. Dir, Adm., MSFC to Distribution SDL-2 subj., "Memorandum of Agreement — KSC Utilization of Selected MSFC Personnel," August 2, 1967 w/enc. of same subj., signed July 28, 1967, by George A. Van Staden, Dir. of Adm., KSC, and July 31, 1967, by Edward D. Mohlere, Asst. to Dep. Dir., Tech., MSFC.
442. Saturn V Ground Test Plan and Status Summary, Rev. A., Sept. 15, 1967, p. 20; and MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, p. 21.
443. PAO, Press Release 67-161, August 3, 1967; and Press Release 67-162, August 4, 1967.
444. NASA, Astronautics and Aeronautics, 1967, p. 235; and PAO, "Marshall Star," Vol. 7, No. 46, Aug. 9, 1967, p. 4.
445. PAO, Press Release 67-168-, Aug. 10, 1967.
446. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, pp. 67 and 69; and DAC, S-IVB Quarterly Progress Report, Sept. 1967, p. 5.
447. DAC, S-IVB Quarterly Progress Report, Sept. 1967, pp. 4 and 6.
448. DAC, S-IVB Quarterly Progress Report, Sept. 1967; and Saturn IB Weekly Notes 34-67.
449. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, pp. 8-9.
450. Memo, Sneed to NASA Headquarters, subj., "Saturn V Weekly Report, No. 38," Sept. 28, 1967; and MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, pp. 41-42.
451. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, p. 41.

452. NASA, Astronautics and Aeronautics, 1967, p. 278.
453. Memo, Sneed to NASA Headquarters, Subj., "Saturn V Weekly Report No. 38," Sept. 28, 1967; and MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, pp. 41-42.
454. NASA, Astronautics and Aeronautics, 1967, p. 28.
455. MAF, Historical Report, Jan. 1 - Dec. 31, 1967, p. 29.
456. PAO, Press Release 67-203, Oct. 4, 1967.
457. NASA, Astronautics and Aeronautics, 1967, p. 298.
458. NASA, Astronautics and Aeronautics, 1967.
459. NASA, Astronautics and Aeronautics, 1967.
460. PAO, "Marshall Star", Vol. 8, No. 7, Nov. 1, 1967, p. 8.
461. NASA, Astronautics and Aeronautics, 1967, p. 331; and PAO, "Marshall Star" Vol. 8, Nov. 8, 1967, p. 1.
462. Saturn FEWG, Saturn V AS-501 Flight Evaluation, MPR-SAT-FE-68-1, Jan. 15, 1968, p. 3-3.
463. Saturn FEWG, Saturn V AS-501 Flight Evaluation, MPR-SAT-FE-68-1, Jan. 15, 1968, p. 3-3.
464. 18th Semi-Annual Report to Congress, July 1 - Dec. 31, 1967, NASA, GPO, p. 3; MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, pp. 11-15; Saturn FEWG, Saturn V AS-501 Flight Evaluation, MPR-SAT-FE-68-1, Jan. 15, 1968, pp. xxxviii-xlii; and NASA, Astronautics and Aeronautics, 1967, pp. 339-341.
465. NASA, Astronautics and Aeronautics, 1967, p. 341.
466. NASA, Astronautics and Aeronautics, 1967, p. 350.
467. Memo, Sneed to NASA Headquarters, subj., "Saturn V Weekly Report, No. 46," Nov. 29, 1967; and PAO, "Marshall Star," Nov. 22, 1967, Vol. 8, No. 10, pp. 1 and 10.

468. NASA, Astronautics and Aeronautics, 1967, p. 365.
469. PAO, Press Release 67-236, Dec. 5, 1967; "Marshall Star," Dec. 13, 1967, Vol. 8, No. 13, p. 1.
470. A Chronology of the George C. Marshall Space Flight Center, Jan. 1 - Dec. 31, 1967, p. 103.
471. NASA Release 67-239.
472. MAF, Historical Report, Jan. 1 - Dec. 31, 1967, p. 1.
473. PAO, "Marshall Star", Dec. 20, 1967, Vol. 8, No. 14, p. 3.
474. Boeing Co., Space Division, Final Report - Saturn V Vehicle with 260-inch Diameter Solid Motor Study - Summary, 05-134081-1, Dec. 18, 1967, p. 1-1.
475. NASA, Astronautics and Aeronautics, 1967, p. 382.
476. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, p. 23.
477. S&ID, NAA, S-II Quarterly Progress Report, Oct. - Dec. 1967, p. III-1, and MTF, Historical Report, Jan. 1 - Dec. 31, 1967 (draft).
478. MAF, Historical Report, Jan. 1 - Dec. 31, 1967, pp. 30-40.
479. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, p. 65.
480. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, pp. 76-79.
481. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, July - Dec. 1967, p. 65.
482. Ancil Kent, Contract NAS8-15476, Modification 42, Mission Support Office, Contracts Office, MSFC, Dec. 1967.
483. MSFC Saturn V Prog. Off., Saturn V Semiannual Report, Jan. - June 1968, p. 1.

- 484. PAO, "Marshall Star," Vol. 8, No. 16, January 10, 1968.
- 485. Interview with Burch H. Aldridge, Chief, Contracts Office, Michoud Assembly Facility, July 17, 1970.
- 486. Saturn V Weekly Report No. 2, January 10, 1968.
- 487. Interview with Altho J. Oberkirch, Contracts Office, MSFC, July 17, 1970.
- 488. Interview with W. T. Brown, MSFC Contracts Office, July 17, 1970.
- 489. Interview with T. B. Burton, MSFC Contracts Office, July 20, 1970.
- 490. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968.
- 491. William A. Geiger, Daily Log, Transport Branch, Project Logistics Office, MSFC, Jan. 17, 1968.
- 492. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968.
- 493. PAO Press Release No. 68-18, Jan. 30, 1968.
- 494. PAO Press Release No. 68-20, Jan. 30, 1968.
- 495. Working Paper, A Chronology of the George C. Marshall Space Flight Center, Jan. 1 - Dec. 31, 1968, p. 9.
- 496. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968, pp. 1-20.
- 497. MSFC Press Release No. 68-25, Feb. 6, 1968.
- 498. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968, p. 7.
- 499. Milton E. Buchholz, Contract NAS8-5608 (Schedule 2), Modification MSFC-241, Launch Systems Branch, Contracts Office, MSFC, Feb. 6, 1968.

- 500. Milton E. Buchholz, Contract NAS8-5608 (Schedule 2), Modification MSFC-244, Launch Systems Branch, Contracts Office, MSFC, Feb. 7, 1968.
- 501. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968, p. 7.
- 502. PAO, "Marshall Star," Vol. 8, No. 21, Feb. 14, 1968.
- 503. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968, pp. 1-33.
- 504. Martin F. Hirsch, Contract NAS8-20055, Engineering Services Division, Purchasing Office, MSFC, March 7, 1968.
- 505. Minutes of Combined Staff and Board Meeting, March 12, 1968.
- 506. MSFC Press Release 68-41, March 12, 1968.
- 507. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968, pp. 5-38.
- 508. MSFC Press Release No. 68-45, March 8, 1968.
- 509. MSFC Press Release 68-46, March 19, 1968.
- 510. PAO, "Marshall Star", Vol. 8, No. 26, March 20, 1968, p. 1.
- 511. Working Paper, A Chronology of the George C. Marshall Space Flight Center, Jan. 1 - Dec. 31, 1968.
- 512. NAR, Saturn S-II Quarterly Progress Report, First Quarter 1968, p. I-1.
- 513. Letter from O'Connor, March 28, 1968.
- 514. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968.
- 515. Royal R. Nolley, Contract 23515 (Procurement Plan), Ground Support Equipment, Contracts Office, MSFC, May 23, 1968.

- 516. MSFC Press Release No. 68-63, April 1968.
- 517. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968, p. 11.
- 518. McDonnell Douglas, Saturn S-IVB Quarterly Tech. Prog. Report, June 1968, p. 3.
- 519. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968, p. 13.
- 520. MSFC Saturn V Prog. Off., Saturn V Semiannual Prog. Report, Jan. - June 1968, p. 15.
- 521. Apollo/Saturn V Ground Systems Evaluation Report, AS-502, John F. Kennedy Space Center, May 23, 1968, pp. 5-21.
- 522. MSFC Press Release No. 68-77, April 1968.
- 523. Saturn IB Notes I-IB-C731-68, April 15, 1968.
- 524. Saturn V Weekly Report, No. 15, April 16, 1968.
- 525. Saturn V First Stage Annual Prog. Rpt., Fiscal Year 1968, The Boeing Company, July 1, 1968, p. 8.
- 526. Saturn IB Notes I-IB-3734-68, May 1, 1968.
- 527. Saturn V Weekly Report No. 17, May 2, 1968.
- 528. NASA, Release No. 68-82.

INDEX

- A-1 engine, 47, 57
- A-3 engine, 57
- AA. See Apollo Applications.
- ABMA. See Army Ballistic Missile Agency.
- Advanced Research Projects Agency (ARPA), 2-7
- Advanced Saturn, 29
- AEC. See Atomic Energy Commission.
- AEDC. See Arnold Engineering Development Center.
- Aero Spacelines, Inc., 203
- Aerojet General Corporation, 34
 - Aetron Division, 32
- Aerospike engine, 193
- AKD Point Barrow. See USNS Point Barrow.
- Aldrin, Edwin E., 200
- Allen, Joseph P., 212
- "All-up" testing, 67
- American Optical Company, 171
- AMR. See Atlantic Missile Range.
- Anders, William A., 200
- AOMC. See Army Ordnance Missile Command.
- Apollo 204 Review Board, 164
- Apollo Applications, 130, 142
 - AAP-1, 173
 - AAP-2, 173
 - Apollo Telescope Mount (ATM), 170, 171
 - contracts
 - negotiations, 197
 - Saturn V procurement, 190
 - mockups, 180, 201, 202
 - nomenclature, 173
 - payload integration, 191
 - S-II tests at MTF, 191
 - S-IVB stage mockup, 176, 209
 - S-IVB Orbital Workshop, 176-178, 181, 188, 201, 209, 218
- Apollo program, 13, 31, 106, 145, 155
 - astronauts, 150, 200, 212
 - flight scheduling. See Saturn IB and Saturn V.
 - manned lunar exploration program, 190
 - manned lunar landing program, 164
 - missions, 23, 81, 89, 132, 134, 139, 164, 170, 173, 183, 197, 198
 - nomenclature changes, 173

Apollo/Saturn IB vehicle

- AS-204, 163, 170, 174, 198, 210
 - accident, 163, 164
 - first LEM mission, 170
 - flight schedule, 203, 204
 - launch of LEM on unmanned flight, 170
 - launch with LM, 210
 - Lunar Module 1 mission, 174
- AS-205, 198, 218, 219
 - first manned Apollo flight, 198
- AS-206, 164, 170, 174, 198, 203, 204
 - first LEM mission (original plans), 170
 - flight schedule, 164, 203, 204
 - second LM mission, 198

Apollo/Saturn V vehicle, 136, 157

- AS-501, 164, 192, 194, 196, 197
 - countdown, 199
 - critical point, 199
 - erection at KSC, 166
 - flight, critical point, 119
 - flight schedule, 164, 183, 192
 - Memorandum of Agreement, 192
 - "Rollout," 194
- AS-501 through AS-515, 203
 - assembly, 203, 204
 - contract extension, 182, 183
- AS-502, 197, 198, 203, 207, 213, 214, 220, 221
 - comment on success, Dr. von Braun, 217
 - countdown demonstration test, 220
 - delivery schedule, 207
 - erection at KSC, 201
 - evaluation of ground systems support, 222
 - flight schedule, 164, 198, 220
 - launch from LC-39A, 221
 - test reentry heat shield, 189
 - transfer to Pad A, 213, 214
 - work progression, 203
- AS-503, 198, 223
 - delivery of instrument unit, 207
 - flight schedule, 223, 224
 - test of command and service modules, 198
 - vertical assembly, 223

- AS-504, 198, 200
 - crew, 200
 - flight schedule, 198
 - status of stage progression, 207
 - storage, 207
- AS-505, 198
 - crew, 200
 - status, of stage progression, 207
- AS-505 through AS-509, 198
 - flight schedule, 198
- Apollo spacecraft, 25, 31, 39, 40, 58, 89, 92, 98, 126, 135, 138, 149, 151, 157, 181, 182, 183, 189, 192, 200, 201, 211
- Apollo spacecraft 009, 134
- Apollo 1, 163
- Apollo 4, 173, 196, 197, 199
- Apollo 5, 173, 209-211
- Apollo 6, 220-222
- Boilerplate spacecraft, 58, 61, 89, 100, 103, 107, 112, 113, 114
 - BP-16, 100, 103
 - BP-9, 112, 113, 114
 - BP-26, 107
- Command Module (CM), 17, 31, 40, 51, 76, 77, 81, 89, 100, 113, 122, 125, 151, 183, 197-200, 221
- Lunar Excursion Module (LEM). See Lunar Module.
- Lunar Module (LM), 40, 51, 141, 157, 168, 170, 183, 197, 198, 200, 209, 211, 218, 224
 - Lunar Module 1, 174
 - Lunar Module 2, 211
- Service Module (SM), 51, 89, 92, 93, 100, 108, 112, 149, 151, 197, 198, 200
- Armstrong, Neil A., 200
- Army Ballistic Missile Agency (ABMA), 1, 2, 4, 5, 6, 9
- Army Ordnance Missile Command (AOMC), 3, 4, 5, 6
- Arnold Engineering Development Center (AEDC), 13, 129, 169, 187, 196
- ARPA. See Advanced Research Projects Agency.
- Astronauts (see also by name), 171, 177, 178, 196, 200, 209, 212, 214
- Astro Space Labs., Inc., 190
- Atlantic Missile Range (AMR), 3, 4, 43
- Atlas, 4, 5
- Atlas Centaur vehicle, 5
- ATM. See Apollo Applications, Apollo Telescope Mount.
- Atomic Energy Commission (AEC)
 - NASA Space Nuclear Propulsion Office, 31
- AZUSA "C", 112

B-377 aircraft, 58
 Bahamas, 94
 Baton Rouge, Louisiana, 118
 Bay St. Louis, Mississippi, 159
 Bean, Alan L., 200
 Bell Aerosystems Company, 161
 "pogo stick," 161
 Bendix Corporation, 92, 170, 185, 197
 Bendix Field Engineering Corporation, 225
 Birmingham, Alabama, 80
 Boeing Company, 24, 33, 35, 42, 47, 50, 53-55, 67, 70, 71, 77, 80, 96, 99,
 105, 109, 116, 121, 125, 127, 135, 136, 154, 164, 169, 171, 173, 178,
 182, 185, 186, 190, 192, 196, 207, 213
 Booster Evaluation Committee of the Office of the Secretary of Defense, 5
 Borman, Frank, 200
 Brown Engineering Company, 175, 218

 Canoga Park, California, 4, 78, 91, 189, 194, 209
 Cape Canaveral (see also Cape Kennedy), 3, 4, 5, 6, 12, 14, 18, 20, 21, 22,
 25, 26, 27, 28, 30, 34, 35, 36, 37, 43, 48, 49, 50, 55, 61, 63, 64, 65,
 68, 71
 Cape Kennedy (see also Cape Canaveral and Kennedy Space Center), 74, 77,
 78, 81, 82, 89, 92, 94, 95, 97, 104, 151, 181, 210
 Carr, Gerald P., 200
 CCSD. See Chrysler Corporation Space Division.
 Centaur engine, 138
 First-generation LR-115, 14
 Second-generation LR-119, 14
 Centaur vehicle, 5, 17, 20, 24, 105, 106, 107, 121
 Chaffee, Roger B., 163
 Chance-Vought, 31
 Chapman, Philip K., 212
 Chrysler Corporation Space Division (CCSD), 23, 30-32, 42, 46, 48, 53, 58,
 62, 67, 68, 70, 71, 74, 75, 77, 78, 83, 86, 87, 90, 92, 93, 95, 97, 100-
 102, 105, 107, 108, 111, 113, 116, 117, 120, 123, 124, 127, 131, 137,
 146, 150, 152-154, 157, 159, 177, 185, 186, 193, 202, 207, 208, 217
 Clarson, R. E., Inc., 101
 Cleveland, Ohio, 138
 CM. See Apollo spacecraft, Command Module.
Coastal Sentry Quebec, 211
 Collins, Michael, 200
Compromise, 22, 26, 27, 33

Conrad, Charles Jr., 200
 Consteel-Ets-Hokin, 34
 Contracts. See contractor firm names.
 Convair Astronautics, 13, 14, 20
 Corps of Engineers. See U. S. Army Corps of Engineers.
 Courtland, California, 108, 109, 117

 DAC. See Douglas Aircraft Company.
 Dallas, Texas, 31
 Debus, Kurt, 143, 162
 Director of Defense Research and Engineering, 5
 Donn, William, 200
 Douglas Aircraft Company (DAC) (see also McDonnell Douglas Corporation),
 10, 18, 20, 21, 25, 34, 35, 38, 42, 44, 47-50, 55-57, 61, 63, 65, 67,
 68, 70-72, 74, 77-79, 81, 83, 86-92, 95, 96, 98, 100, 101, 104, 117,
 125, 126, 131, 135, 136, 139, 143-145, 150, 153, 157, 158, 162, 168,
 169, 177
 Downey, California, 54, 80, 91, 99
 DX (national priority rating), 8, 37
 Dyna Soar, 5, 12, 14

 E-1 engines, 1
 East Pearl River, 60
 Edwards Air Force Base, 27, 74, 185
 Edwards, California, 92, 94, 126
 Edwards Field Laboratory (EFL), 182, 186, 202
 EFL. See Edwards Field Laboratory.
 Eisenhower, Dwight D. (President), 12, 13
 England, Anthony W., 212

 F-1 engines, 4, 24, 25, 27, 33, 36, 38, 39, 49, 50, 51, 54, 63, 67, 71, 72,
 74, 85, 88, 90, 91, 92, 94, 99, 107, 126, 136, 143, 144, 155, 156, 182,
 185, 186, 189, 202, 212, 224
 West Area Test Stand, 186, 202
 FAA. See Federal Aviation Agency.
 Fairchild Hiller Corporation, 89, 92, 97, 103, 108, 112
 FEC. See Federal Electric Corporation.
 Federal Aviation Agency (FAA), 58
 Federal Electric Corporation (FEC), 145
 Flight Readiness Test (FRT). See Apollo/Saturn, Upgraded Saturn IB, and
 Saturn V vehicles.

Gemini 5, 112
 General Dynamics/Astronautics, 25, 130
 General Electric Company, 13, 80, 97, 178
 George C. Marshall Space Flight Center (MSFC), (see also Huntsville, Alabama), 10, 12-14, 16-36, 38-50, 53-68, 70, 71, 73-82, 84, 86, 90, 92, 93, 95, 96, 98-118, 120-123, 125-127, 129-141, 143-146, 150, 152-162, 166-178, 180-182, 185, 186, 188-194, 196, 201, 202, 208-213, 216-221, 223
 MSFC/KSC Memorandum of Agreement, 192
 West Area Test Stand, 202
 Glennan, T. Keith, 12, 13
 Gordon, Richard F., 200
 Gordon, T. J., 162
 Great Siberian Meteorite, 200
 Grissom, Virgil I., 163
 Ground Support Equipment (GSE). See KSC, Upgraded Saturn I and Saturn V.
 Grumman Aircraft Engineering Corporation, 139

 H-1 engines, 3, 4, 6, 7, 14, 16, 25, 42, 68, 83, 86, 104, 106, 123, 133, 135, 138, 144, 186, 209
 H-1 engine (H-1001), 5
 H7-17, 155
 Hagerstown, Maryland, 97
 Haise, Fred W. Jr., 200
 Hayes International Corporation, 175
 Heimburg, Karl, 162, 170
 Henize, Karl G., 212
 Holmquest, Donald L., 212
 Houston, Texas, 211
 Humphrey, Hubert, 180
 Huntington Beach, California, 76, 104, 131, 135, 136, 153, 157, 166, 169, 176, 178, 188, 208
 Huntington Beach Assembly Facility, 49, 57, 58, 70, 78, 83, 87, 98, 117
 Huntsville, Alabama, (see also George C. Marshall Space Flight Center), 8, 13, 18, 22, 25, 32, 43, 46, 49, 66, 73, 75, 77, 79, 88, 95, 111, 115, 121, 122, 123, 125, 130, 145, 159, 166, 168, 169, 171, 172, 173, 175, 178, 204, 207, 217, 218
 Hurricanes
 Alma, 143
 Betsy, 118, 119
 Gladys, 89

IBM. See International Business Machines Corporation.

International Business Machines Corporation, 76, 78, 89, 105, 118, 121, 129, 131, 168, 177, 201, 204, 207, 221

International Telephone and Telegraph Corporation, 145

IU. See Saturn IB and Saturn V Instrument Unit.

J-2 engines, 10, 23, 30, 34, 36, 39, 46, 58, 67, 71, 78, 79, 88, 90, 91, 96, 99, 100, 110, 111, 114, 115, 123-126, 130, 137, 140-142, 145, 165, 169, 173, 175, 187, 196, 200, 202, 221, 224

155 J-2 engines, 145

J022-1 engine, 175

James, Lee B., 171

Jet Propulsion Laboratory (JPL), 65, 163, 178

Johnson, Lyndon B., 44, 201

JPL. See Jet Propulsion Laboratory.

Juno II, 7

Juno V, 3

Jupiter C, 7

Jupiter missile, 2, 3, 5, 7, 39, 47, 58

Jupiter program, 3

Kennedy, John F., 44

Kennedy Space Center (KSC), 70, 71, 74, 75, 82, 87, 100, 101, 102, 103, 104, 105, 107, 108, 109, 110, 111, 112, 113, 114, 116, 117, 120, 121, 122, 123, 124, 125, 130, 132, 133, 134, 135, 136, 138, 139, 140, 141, 143, 144, 148, 149, 151, 152, 154, 155, 157, 158, 212-214, 217, 218, 220, 221, 223

Launch Complex 34 (LC-34), 3, 4, 5, 6, 12, 16, 22, 29, 34, 35, 43, 47, 49, 50, 55, 78, 101, 111, 112, 117, 121, 122, 126, 134, 149, 151, 163

Launch Complex 37 (LC-37), 27, 28, 36, 37, 78, 113, 162, 168, 174, 185, 210

Launch Complex 37 Pad A-2 (LC-37-A-2), 28

Launch Complex 37 Pad B (LC-37-B), 28, 49, 50, 55, 56, 61, 66, 68, 100, 104, 105, 110, 111, 112, 114, 139, 144, 211

Launch Complex 39 (LC-39), 40, 41, 47, 49, 53, 63, 70, 78, 152, 199

Launch Complex 39 Pad A (LC-39-A), 123, 221

Launch Complex 39 Pad B (LC-39-B), 96

Kiwi-B, 32

Koppers Company, Inc., 98, 191

KSC. See Kennedy Space Center.

LaHatte, William F. , 171
 Lamont Geological Observatory, 200
 Langley Research Center (LaRC), 23, 161
 LaRC. See Langley Research Center.
 Launch Operations Center, 47
 LC, Launch Complex. See KSC.
 LEM. See Apollo spacecraft, Lunar Excursion Module.
 Lenoir, William B. , 212
 Lewis Research Center, 65, 105, 138
 Ling-Temco-Vought, 206
 Llewellyn, John A. , 212
 LM. See Apollo spacecraft, Lunar Module.
 Local Scientific Survey Module (LSSM), 185
 Lockheed Aircraft Corporation, 25, 127
 Lockheed Missiles and Space Company. See Lockheed Aircraft Corporation.
 Long Beach, California, 88
 Los Alamitos, 154
 Los Angeles, California, 25
 Lovell, James A. , 200
 LR-115 engine, 10, 14, 16
 LR-119 engine, 10, 14, 16, 17
 LSSM. See Local Scientific Survey Module.
 LVDC/LVDA, 120

M-1, 34
 MAF. See Michoud Assembly Facility.
 Malon Construction Company, 98
 Management Services, Inc. , 175
 Manned Spacecraft Center (MSC), 31, 65, 76, 81, 82, 181, 182, 191, 218
 Mars, 163
 Marshall, George C. (General), 12
 Marshall, Mrs. George C. , 13
 Marshall Space Flight Center (MSFC). See George C. Marshall Space Flight Center.
 Martin Company. See Martin Marietta Corporation.
 Martin Marietta Corporation, 13, 20, 25, 127, 191
 Mason-Rust Company, 33
 Mather Air Force Base, 157
 Mattingly, Thomas F. II, 200
 McDivitt, James A. , 200
 McDonnell Aircraft Corporation, 139, 150
 McDonnell Douglas Corporation (see also Douglas Aircraft Company and McDonnell Aircraft Corporation), 162, 168, 176-178, 181, 188, 196, 201, 208, 209, 218

McKeithen, John J. , 201
 Mercury Redstone, 7
 Merritt Island, Florida, 47, 96
 Michoud Assembly Facility (MAF), (Michoud Ordnance Plant and Michoud Test Operations), 28-31, 33, 36, 41, 42, 45, 46, 48, 53, 54, 58, 62, 66, 67, 70, 71, 73, 75, 77, 78, 80, 82, 83, 86, 87, 90, 92, 95, 99, 100, 102, 104, 105, 108, 110, 111, 115-125, 129, 132, 138, 147, 152, 154, 157, 159, 162, 168, 172-174, 179, 181, 182, 184, 186, 189, 190, 193, 201-204, 206-209, 212, 213, 215, 220, 223
 Michoud Ordnance Plant. See Michoud Assembly Facility.
 Michoud Test Operations (MTO). See Michoud Assembly Facility.
 Micrometeoroid satellite, 53, 108
 Military Sea Transport Service (MSTS), 72
 Minneapolis-Honeywell, 24
 Mississippi River, 36, 168
 Mississippi Test Facility (MTF), 29, 34, 36, 45, 60, 98, 112, 113, 116, 117, 121, 122, 132, 139, 140-142, 144, 146, 147, 150, 152-160, 163, 165-167, 170-175, 178, 179, 184, 189, 191, 194, 200, 203, 207, 212, 214-217, 220
 A-1 Test Stand, 166, 191, 195
 A-2 Test Stand, 116, 117, 122, 191
 A-3 Test Stand, 122
 B-2 Test Stand, 155, 165, 167, 169, 171
 Mississippi Test Operations (MTO), 34, 35, 36, 45, 53, 58, 61, 62, 63, 70, 73, 78, 80, 82, 89, 93, 94, 101, 102, 103, 113
 MISTRAM transponder, 112
 Mitchell, Edgar D. , 200
 Mobile, Alabama, 89
 MSC. See Manned Spacecraft Center.
 MSFC. See George C. Marshall Space Flight Center.
 MSTS. See Military Sea Transport Service.
 MTF. See Mississippi Test Facility.
 MTO. See Mississippi Test Operations.
 Mueller, George E. , 141, 164, 197
 Musgrave, F. Story, 212

 NAA. See North American Aviation.
 NAR. See North American Rockwell Corporation.
 NAS8-19, 145
 NASA. See National Aeronautics and Space Administration.
 National Aeronautics and Space Administration (NASA), 5-10, 13, 14, 16, 17, 22, 23, 25, 27-31, 34, 35, 37, 39, 41, 42, 46, 52, 53, 55, 62, 67, 68, 70-73, 77, 78, 80, 84, 86, 89, 92, 96, 103-106, 108, 109, 112-114, 118, 121, 123, 125-127, 129, 130, 132, 133-136, 138-142, 144-146, 148-150, 152, 154-157, 160, 161, 163, 164, 170, 171, 173, 177, 178, 180-182, 185-191, 193-197, 199-203, 206-209, 211, 213, 214, 217, 218, 221, 223-225

National Aeronautics and Space Council, 4
 National Vehicle Program, 4
 Navy, 44
 Nerva, 32
 New Orleans, Louisiana, 28, 29, 33, 36, 42, 47, 53, 98, 153, 168, 186, 189, 206, 207
 North American Aviation (NAA), (see also North American Rockwell Corporation), 3, 14, 28, 30, 31, 67, 83, 88, 91, 96, 99, 102, 126, 127, 138, 142, 145, 153-156, 166, 175, 180, 182, 186, 187, 189, 193, 195, 207
 El Toro Facility, 54, 66
 Rocketdyne Division, 1, 3, 4, 10, 24, 33, 38, 39, 42, 46, 49, 54, 67, 70, 71, 74, 78, 83, 86, 88, 90, 91, 93, 99, 104, 106, 110, 111, 113-115, 123, 125, 126, 136-138, 140, 144, 145, 155, 175, 182, 186, 187, 193, 194, 202, 203, 209
 Space and Information Systems Division (S&ID), (see also North American Rockwell Corporation), 35, 44, 46, 54, 55, 58, 66, 67, 71, 74, 76, 80, 91, 99, 102, 108-110, 113, 116, 122, 148
 North American Rockwell Corporation (NAR), (see also North American Aviation), 200, 209, 214, 219
 Northrop Corporation, 175
 Nova, 5, 22-24, 29, 34, 36

 Ocean of Storms, 214
 Office of Manned Space Flight (OMSF), 110
 O'Connor, Edwin (General), 223
 O'Leary, Brian T., 212
 OMSF. See Office of Manned Space Flight.
 Orbital Workshop (see also Apollo Applications, S-IVB Orbital Workshop), 176-178, 181, 188, 201, 209-211
Orion (barge), 103, 108, 109, 111, 117
 Ostrander, Don (Major General), 23, 25

 Pacific Ocean, 199
 Pad A, 141, 143, 213
Palaemon (barge), 14, 16, 18, 21, 26, 61, 105, 108, 115, 118, 122, 125, 157, 159, 162, 173, 181
 Palisades, New York, 200
 Panama Canal, 111, 163
 Parker, Robert A., 212
 Pasadena, California, 178
Pearl River (barge), 147, 172, 173, 182, 184

Pegasus, 89, 92, 93, 95, 97, 100, 101, 103, 108, 110, 112, 113, 114, 126

Pegasus A, 97, 100, 103

Pegasus B, 97, 108, 110

Pegasus C, 112, 113, 114

Pensacola, Florida, 21

Phillips, Samuel C. (Major General), 106, 197, 223, 224

Plan V, 46

"pogo effect," 224

"pogo stick," 161

Point Barrow (barge). See USNS Point Barrow.

Port Canaveral, Florida, 135

Port Canaveral Locks, 116

Poseidon (barge), 122, 129, 152-154, 172, 174, 179

Pratt & Whitney, 10, 16, 20, 30, 39, 121

Pregnant Guppy (aircraft), 58, 61, 65, 109, 112, 185

Project High Water, 37, 48

President Kennedy. See Kennedy, John F.

President Johnson. See Johnson, Lyndon B.

Promise (barge), 33, 47, 63, 110, 116, 118, 119, 132, 134, 138

RCA. See Radio Corporation of America.

Radio Corporation of America (RCA), 78, 127, 129, 175, 220

RCA Service Company. See Radio Corporation of America.

Redstone missile, 2, 7, 39

Redstone program, 3

Richmond, California, 117

RIFT (reactor-in-flight test), 25, 32

Rocketdyne. See North American Aviation, Rocketdyne Division.

Rockville, Maryland, 129

Rockwell-Standard Corporation. See North American Rockwell Corporation.

Rogallo paraglider, 14

Rose Knot Victor, 211

RP-1, 4

RP-1 tank, 5

Rust Engineering Company, 175

Ryan Aeronautical Company, 14

S&ID. See North American Aviation, Space and Information Systems Division.

S-IB-D/F, 87, 92, 93, 97, 100

S-IU-5, 63

S-IU-8, 83, 102, 104, 105

S-IU-9, 75, 77, 85, 86

S-IU-10, 95, 100, 110, 111, 113
 S-IVB-D, 98, 100
 S-IVB-F, 117
 S-IVB Orbital Workshop (program), (see also Apollo Applications)
 contract
 advanced versions, 188
 conversion of liquid hydrogen tank into a space station, 177, 178
 design review, 181, 218
 mockup, 209, 210, 218
 quick-release manhole cover, 218
 S-IVB stage (see also Saturn I, Saturn IB, and Saturn V), 36, 38, 47, 49, 55,
 57, 58, 62, 68, 93, 108, 109, 115, 117, 135, 136, 139, 144, 150
 SA-11 (Saturn I, S-I-5 flight qualification test), 53
 SAT-01, 9
 SAT-02, 9
 Sacramento Test Center. See Sacramento Test Facility.
 Sacramento Test Facility (SACTO), 20, 21, 32, 43, 47, 50, 54-57, 61-63, 65,
 67, 68, 70, 72, 75, 86, 88, 95, 98, 100, 103, 104, 108-111, 113, 115,
 117, 122, 123, 126, 136, 139, 140, 142, 143, 145, 146, 148, 154, 157-
 160, 162, 163, 166, 169, 173, 174, 178, 182, 188, 193, 204, 207
 Beta Complex, 55, 62
 Beta I Test Stand, 61, 62, 117, 123, 139, 140, 142, 163, 194, 207
 Beta II Test Stand, 54, 56, 57, 104
 Beta III Test Stand, 62, 104, 109, 117, 122, 160, 173, 188
 SACTO. See Sacramento Test Facility.
 San Salvador, 94
 Sanders Associates, 159, 220
 Santa Monica, California, 47, 49, 56, 61, 63, 86
 Santa Susana, California, 36, 69, 74, 78, 101, 108, 109, 123, 128, 129, 146
 Santa Susana Field Laboratory (SSFL), 46, 88, 114-116, 126, 175, 187, 202
 Delta 2A Test Stand, 175
 Santa Susana Test Facility. See Santa Susana Field Laboratory.
 Saturn B, 4
 Saturn Booster (proposed configuration), 2, 5
 Saturn C vehicle (concept), 4
 Saturn C-1 vehicle. See Saturn I.
 Saturn C-2 vehicle (concept), 7, 14, 16, 17, 19, 22
 S-II stage, 18
 Saturn C-3 vehicle (concept), 22, 24
 C-3/Apollo (configuration), 23
 Saturn C-5 vehicle. See Saturn V.
 Saturn C-IB. See Saturn IB.

- Saturn I vehicle, 7, 8, 10, 12-14, 18, 19, 22, 31, 35, 37, 39-41, 43, 46, 47, 49-51, 53, 55, 60, 64-68, 71-77, 81, 82, 84-87, 89, 90, 92-95, 97, 100, 103, 104, 109, 110, 114, 138, 144, 146, 150
- 188K engine, 46
- Block I, 19, 55
- Block II, 19, 47, 49, 55
- Contracts
 - S-I/S-IB, 101
- S-3D, 3
- S-I stage, 7, 8, 14, 16, 18, 19, 21, 22, 26, 28, 29, 30, 32, 50, 53, 66, 71, 104, 105, 108, 111
 - S-I-5, 53-55, 63, 71
 - SA-11 flight qualification test, 53
 - S-I-6, 56, 59
 - S-I-7, 67
 - S-I-8, 58, 66, 68, 71, 76, 77, 83, 95, 97, 104, 105
 - S-I-9, 60, 65, 75
 - S-I-10, 48, 75, 86, 92, 93, 95, 110
 - S-I-D5, 55, 61
- S-IV stage, 7, 8, 10, 12, 15-18, 20-22, 24, 26, 27, 31, 32, 34-36, 43, 47, 49, 50-52, 55-58, 61, 65, 72, 77, 82, 86, 87, 89, 93, 102, 105, 109, 138
 - RL10 engine, 30, 121, 138
 - RL10-A-1 engine, 17, 47
 - RL10-A-3 engine, 20, 39, 47, 50, 52, 57
 - RL10-A-3-3 engine, 121
 - S-IV-5, 56, 61, 63-66, 68
 - S-IV-6, 61, 65, 67, 68, 74, 81
 - S-IV-7, 68, 75, 77
 - S-IV-8, 86, 95, 104, 105
 - S-IV-9, 88, 89, 100
 - S-IV-10, 67, 95, 100, 104, 109, 111
- S-IVB stage, 44
- SA-1 vehicle, 10-14, 16, 18-20, 24, 26, 29, 30, 37, 110
 - SA-01 flight qualification test, 18
- SA-2 vehicle, 13, 19, 26, 29, 33-35, 37, 48
- SA-3 vehicle, 19, 26, 31, 35-36, 43, 48
- SA-4 vehicle, 34, 38, 39, 45, 49, 50, 55
 - SA-04 flight qualification test, 29
- SA-5 vehicle, 39, 47, 55, 66, 68, 71-73, 81
 - SA-05 flight qualification test, 29
- SA-6 vehicle, 45, 63, 67, 68, 70, 76, 77, 81, 82

- SA-7, 67, 82, 86, 88
- SA-8, 53, 74, 75, 77, 83, 84, 95, 97, 104, 110
- SA-9, 53, 74, 75, 77, 84, 89, 92, 94, 95, 97, 100, 103, 104
- SA-10, 10, 75, 77, 84, 95, 111, 112, 114
- SA-D1, 23
- SA-D5, 47, 49, 54
- SA-T, 9
- SA-T1, 13, 14, 16, 23
- SA-T2, 16, 23-26
- SA-T3, 31, 35
- SA-T4, 40
- SA-T4.5, 40, 46
- ST-124 guidance system, 82, 83
- Saturn IB program (also Uprated Saturn I)
 - nomenclature changes, 173, 197, 198
- Saturn IB vehicle (also Uprated Saturn I), 39, 43, 44, 50, 51, 63-65, 67, 68, 70, 71, 73-76, 78, 79, 81-87, 90, 92-99, 101, 104-107, 109, 110, 113, 115-117, 120, 123, 126, 132, 134, 141, 144, 149, 150-152, 154-158
- AS-9, 100
- AS-201, 121, 122, 126, 132, 134
- AS-202, 132, 136, 138, 139, 144, 149, 151
- AS-203, 138, 139, 144
- AS-204, 155
- AS-205, 155
- AS-206, 157
- AS-208, 140
- Contracts (see also stage contracts)
 - S-I/S-IB, 101
 - S-IVB, 101
 - modification for ground support and engineering equipment, 217
 - modification for support of RCA 110A computers, 220
- flight scheduling, 173, 200
- Improvement Studies, 177
- Instrument Unit
 - contract supplement, 201
 - J-2 engine, 115
 - S-IU-200D/500D (See also Saturn V), 100, 101, 122
 - S-IU-200F/500F (See also Saturn V), 103, 108, 111, 116, 117
 - S-IU-200S/500S (See also Saturn V), 100, 103, 105, 116, 120, 153
 - S-IU-200S/500S-II (See also Saturn V), 121, 123
 - S-IU-200S/500S-III (See also Saturn V), 153
 - S-IU-200V, 90, 96

- S-IU-201, 122
- S-IU-202, 134
- S-IU-205
 - shipped to KSC, 223
- S-IU-205 through S-IU-209
 - storage, 203, 204
- S-IU-209
 - assembly, 188
- S-IU-210
 - fabrication and assembly operations, 188
- S-IB stage, 62, 67, 70, 81, 90, 99, 100, 106, 113, 120, 122, 123, 127, 131, 132, 134, 137-140, 144, 157
 - contract
 - conversion to C P I F agreement, 193
 - engineering support services, 209
 - extension, 185, 203
 - negotiations, 207, 208
 - order to NAA for H-1 rocket engines, 186
 - procurement responsibilities, 220
- S-IB-1, 74, 78, 83, 86, 92, 93, 95, 97, 102, 105-108, 116, 117, 121, 124, 139
- S-IB-2, 76, 86, 92, 93, 97, 111, 113-115, 132
- S-IB-3, 97, 100, 117, 118, 120, 122, 123, 138
- S-IB-4, 97, 121, 124, 125, 131, 149
- S-IB-5, 124, 135, 137
- S-IB-6, 144, 157
 - arrival at Michoud, 173
- S-IB-8, 154
- S-IB-9
 - acceptance test firings, 169
 - long-duration test, 169
 - post-firing checkout, 162
 - post-static checkout, 188
 - shipped to MSFC, 159
 - static firing, 166
- S-IB-10
 - acceptance firing, 178
 - arrival at Michoud, 182
 - arrival at MSFC, 173
 - post-static modification, 188
 - shipped to MSFC, 168
 - static firing, 180

- S-IB-11
 - firing, 223
- S-IB-12
 - assembly and checkout, 204
 - shipped to MSFC, 223
- S-IB-202, 138
- S-IB-203, 138
- S-IVB stage, 43, 51, 65, 67, 70, 71, 74, 76, 78, 79, 81-83, 87, 90, 92, 96, 98, 100, 101, 104, 106, 109, 110, 115, 117, 120, 121, 123, 126, 135, 136, 144, 157, 158
 - contract
 - negotiations, 207
 - procurement, 196
- S-IVB-201, 104, 108, 109, 115, 117, 120-122
- S-IB-201 through S-IB-204
 - delivery to KSC/MSFC, 220
- S-IVB-202, 117, 122, 123, 125
- S-IVB-203, 123
- S-IVB-204, 126, 136
- S-IVB-205 through S-IB-209
 - storage, 204
- S-IVB-206, 157
 - de-erected from LC-37, 174
 - delivery to KSC/MSFC, 220
 - erected on LC-37, 162
 - storage, 168
- S-IVB-208
 - acceptance firing, 159
- S-IVB-209
 - airlifted to SACTO, 169
 - pre-static checkout, 162
 - static firing, 188
- S-IVB-210
 - storage, 188
- S-IVB-210 through S-IVB-212
 - at Huntington Beach, 204
- SA-201 vehicle, 78, 120, 126, 134
- SA-203 vehicle, 144
- SA-204 (see also Apollo/Saturn IB, AS-204)
 - flight schedule, 203, 204
 - test of lunar module, 168, 185
- SA-205 (see also Apollo/Saturn IB, AS-205)

- erected at KSC, 223
- shipment to KSC, 211
- storage, 188
- SA-206 (see also Apollo/Saturn IB, AS-206)
 - checkout, 162
 - first LM mission (original plans), 168
 - storage, 188
 - storage of instrument unit, 168
- SA-208
 - storage, 188
- SA-209
 - stages of development, 188
- SA-210
 - development, 188
- SA-211
 - static firing, 202
- SA-212
 - flight schedule, 204
 - storage, 204
- Saturn I/IB Operations, 171
- Saturn V program
 - nomenclatures changes. See Apollo Program.
- Saturn V vehicle, 31, 34, 35, 37, 39-42, 44, 46-48, 50, 51, 53, 59, 60, 64-67, 70, 71, 73-82, 84, 85, 87, 88, 90-94, 96-99, 101, 102, 105, 107, 109, 110, 112-117, 121-123, 125-127, 129-136, 139-141, 143, 148, 150-155, 157, 158
- AS-504, 140
- contract
 - operation of development "Breadboard" Facility, 213
 - modification for support of RCA 110A computers, 220
 - stage procurement, 164, 182, 183, 190, 213
 - transportation, 203
- F-1 engines
 - first flight, 199, 200
 - flight schedule, 180, 200
- Instrument Unit (IU)
 - contract supplement, 201
 - S-IU-200D/500D (see also Saturn IB), 100, 101, 122
 - S-IU-200F/500F (see also Saturn IB), 103, 108, 111, 116, 117
 - S-IU-200S/500S (see also Saturn IB), 100, 103, 105, 116, 120, 153
 - S-IU-200S/500S-II (see also Saturn IB), 121, 123
 - S-IU-200S/500S-III (see also Saturn IB), 153

- S-IU-500F, 135, 136
- S-IU-500FS, 104, 105, 132, 135
- S-IU-500 ST, 113
- S-IU-500V, 105, 111, 117, 130
- S-IU-501, 131, 151, 154-155
 - vertical assembly, 160
- S-IU-502, 155
 - transported to KSC, 170
- S-IU-503
 - checkout and systems testing, 158
 - delivery, 207
- S-IU-504
 - completion, 204
 - storage, 207
- S-IU-505
 - assembly, 207
 - post-manufacturing checkout, 204
- Integration, 182, 183
- Liftoff switch, 192
- S-IC stage, 30, 33, 35, 36, 39, 43, 45-48, 50, 51, 53-55, 58, 60-63,
 - 65-67, 69-71, 74, 76, 77, 80, 84, 85, 89, 94, 99, 107, 115, 126-129, 134-136, 143, 154, 155
- B-2 Test Stand, 165
- Battleship/All Systems stage (see also S-IC-T), 165, 166, 192
- contract
 - Boeing, prime contractor, 190
 - procurement, 164, 196, 220
- checkout, 214
- LOX depletion sensors, 199
- "pogo effect," 224
- program briefing, 223
- recovery and reuse, 186
- S-IC-1, 130, 133, 134, 152, 160
- S-IC-2, 130, 143
 - arrival at KSC, 169
 - transported to KSC, 167
- S-IC-3, 153, 154, 155
- S-IC-4, 116, 130
 - acceptance firing test, 178
 - arrival at Michoud, 181
 - arrival at MTF, 173

- S-IC-5
 - acceptance firing test, 194
 - storage, 207
 - transported to MTF, 184
- S-IC-7
 - F-1 engine, 186
- S-IC-8
 - F-1 engine, 186
- S-IC-9
 - F-1 engine, 186
- S-IC-16 through S-IC-25
 - procurement, 196
 - static tests, 203
 - static test stand, 173
 - Test Complex, 192
 - test stand adapter, 160
- S-IC-D (dynamic test stage), 105, 122, 128, 129
 - arrival at MTF, 175
- S-IC-F, 136
- S-IC-S (fuel tank), 98, 99, 112
- S-IC-T (Battleship/All Systems stage), 65, 96, 98, 104, 107, 108, 115, 121, 125, 130, 145, 154, 157
 - firing, 165, 166, 169, 192
 - removal from B-2 Test Stand, 171
 - transported to MAF, 172
 - transported to MSFC, 169, 174
- S-II stage, 14, 16, 17, 20, 22, 28, 30, 36, 39, 44-46, 51, 52, 54, 55, 58, 62, 66, 67, 69, 71, 72, 74, 76, 80, 82, 84, 88, 91, 94, 96, 98, 99, 101, 102, 108-110, 112-114, 116, 117, 120, 121, 123, 126, 128, 129, 131, 133, 139-141, 143, 144, 146, 147, 153, 154
 - battleship stage, 169, 173
 - transition and full duration testing, 181
 - Battleship Test No. 041, 165
 - checkout, 214
- contract
 - modification, 193, 195
 - North American Rockwell, 166, 167
- J-2 engine, 187, 224
- propellant tanks, 181
- S-II-1, 104, 113, 124, 125, 146, 147, 150, 155, 158
 - arrival at KSC, 160
 - dismantled at KSC, check for "hairline" cracks, 180

- static firing, 191
- transported to KSC, 159
- verification tests, 187
- vertical assembly at KSC, 162
- S-II-2, 110, 125
 - arrival at MTF, 165
 - departure Seal Beach, 163
 - mated to S-IC-2, 189
 - schedule slippage, 220
 - static firing, 172-175
 - transported to KSC, 179
 - vertical assembly at KSC, 189
- S-II-3, 113, 146, 156
 - acceptance firing, 195
 - arrival at MTF, 191
 - checkout, 191
 - departure Seal Beach, 189
 - static firing, 195
- S-II-4
 - arrival at MTF, 200
 - cryogenic proof pressure test, 216, 219, 220
 - static firing, 214
 - test stand, MTF, 207, 217
- S-II-5
 - cryogenic proof pressure test, 216
 - departure Seal Beach to MTF, 212
 - shakedown inspection, 207
 - test stand, MTF, 217
- S-II-6
 - test stand, MTF, 217
- S-II-11 through S-II-25
 - contract modification, 195
- Stage Manager, 158
- static test, 203
- S-II-A2, 122
- S-II-D, 101
- S-II-F/D, 155
- S-II-F, 102, 109, 133, 135, 136, 155
- S-II-S, 97, 99-102, 108
- S-II-S/D, 109, 120
- S-II-T, 101, 110, 120, 121, 122, 131, 139, 140, 141, 142, 144
- S-II-T/D, 131, 132, 143

- S-IVB stage, 34, 42, 48, 51, 82, 88, 89, 92, 94, 96, 103, 109, 110, 112, 126, 129, 135, 136, 139, 141, 153
- battleship stage, 186
- contract
 - negotiations, 208
 - procurement, 196, 208
- delivery, 220
- J-2 engine, 115, 187
- restart, 199, 221
- S-IVB-500F (Facility Checkout Stage), 103, 104, 111, 113, 117, 136
 - delivery, 220
- S-IVB-500-ST, 136
 - delivery, 220
- S-IVB-501, 92, 131, 136, 140, 142, 148
 - circular orbit, 197
 - verification tests, 187
 - vertical assembly at KSC, 160
- S-IVB-502, 135, 143, 145, 146
 - departure SACTO to KSC, 166
- S-IVB-503, 135, 153, 154
 - Beta I Test Stand, 163
 - destruction, 160, 162, 173
 - nomenclature changes, 162
- S-IVB-503N
 - acceptance firing, 178
 - nomenclature change, 161, 162
- S-IVB-504, 135, 157
 - nomenclature change, 162
 - post-static checkout, 204
- S-IVB-504N
 - acceptance firing, 194
 - arrival at SACTO, 182
 - nomenclature change, 162
- S-IVB-505
 - checkout, 166
 - nomenclature change, 162
 - post-static checkout, 204
 - storage, 207

- S-IVB-505N
 - nomenclature change, 162
- S-IVB-506
 - nomenclature change, 162
 - post-manufacturing checkout, 204
- SA-500D (Dynamic Test Vehicle), 157
 - Configuration I testing, 169
- SA-500F, 141, 143, 154
- SA-501, 155
 - erection at KSC, 183
 - vertical assembly, 160, 181
- SA-502
 - erection at KSC, 189, 201
 - flight schedule, 164
- SA-503, 146
 - arrival at MTF, 191
 - on dock at KSC, 203
- Static test stands, 217
- Systems and performance briefing, 177
- Systems Engineering and Integration requirements, 162
- Television broadcast satellites, 176
- Saturn-Dyna Soar, 5
- Saturn program, 9, 10, 64, 101
- Saturn System Study, 4, 6
- Saturn Vehicle Evaluation Committee (the Silverstein Committee), 7, 10
- Schweickart, Russel L., 200
- Scott, David R., 200
- Seal Beach, California, 36, 44, 51, 52, 66, 71, 76, 80, 84, 101-104, 108, 110, 111, 113, 120, 121, 124, 125, 133, 146, 147, 150, 163, 180, 189, 200, 207, 212
- Sea of Tranquility, 214
- Seamans, Robert C., 34, 141
- Silverstein Committee (Saturn Vehicle Evaluation Committee), 7, 10
- Slidell Computer Facility, 36, 54
- Slidell, Louisiana, 41, 42, 54, 206
- SM. See Apollo Service Module.
- Smith Builder, 47
- Space Task Group, 25
- Space Technology Laboratories, Inc., 25
- Spaco, Incorporated, 175
- Sperry Rand Corporation, 174, 216
- SSFL. See Santa Susana Field Laboratory.

Steel Executive, 117, 120
St. Louis, Missouri, 150
Sullivan, Long, and Hagerty of Birmingham, Alabama, 80
Super Guppy, 135, 136, 139, 143, 148, 151, 154, 157, 162, 168, 170, 174,
178, 182, 202, 209, 223
Surveyor, 215
Sverdrup Parcell Company, 35

Tennessee River, 6, 21, 26, 37
Thor missile, 3
Thor-Jupiter engine, 2, 3
Thornton, William E., 212
Teir, William, 171
Titan, 4, 5
Titan C, 5
TRW Systems, Inc., 153, 178
Tullahoma, Tennessee, 13, 117, 118, 129, 169

Uprated Saturn I. See Saturn IB.
U. S. Army Corps of Engineers, 28, 48, 53, 60, 62, 63, 89, 98, 102, 166
USNS Point Barrow, 72, 111, 113, 121, 133, 147, 189, 212
USS Bennington, 199
USS Okinawa, 221

Van Nuys, California, 129
Vice-President Humphrey. See Humphrey, Hubert.
Vice-President Johnson. See Johnson, Lyndon B.
Vitro Corporation, 174
von Braun, Dr. Wernher, 1, 12, 22, 25, 64, 93, 171, 180, 202, 217, 223
Voyager, 163, 178

Washington, D. C., 81
Webb, James E., 23, 25, 113, 201
Webb, Mrs. James E., 201
West Area F-1 Test Stand, 186, 202
Wheeler Dam, 21, 26, 33, 37
White, Edward H. II, 163
Witchita, Kansas, 50, 55
Wisconsin, University of, 154
Worden, Alfred M., 200
Wyle Laboratories, 130

Yarchin, Colonel Sam, 158

